QUANTITIES

REVISIONS NO	DESCRIPTION	DATE

SHEET NO. → 4 5 6 7

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET			
1		2" A.C. PAVEMENT	S.Y.	3,290		3,290		
2		REMOVE EXIST. LANDSCAPING & CURB, REPLACE W/ 2" A.C. PAVEMENT	S.Y.	181		181		
3		TYPE II GRAVEL BASE	C.Y.	450		450		
4		30" "ROLL" TYPE CURB & GUTTER	L.F.	1,170		1,170		
5		4' SIDEWALK	S.F.	3,956		3,956		
6		SIDEWALK RAMP (NOTE TRANSITION LENGTHS)	EA.	3		3		
7		CONCRETE DRIVEWAY	S.F.	4,536		4,536		
8		8' VALLEY GUTTER	S.F.	658		658		

WATER:

1		RELOCATE EXIST. STD. F.H. W/6" G.V. & 6" A.C.P. LATERAL	EA.	1	1			
2		3/4" METER BY L.V.V.W.D.	EA.	12	12			
3		3/4" SERVICE W/ METER BOX	EA.	12	12			

SEWER:

1		4" SEWER LATERAL (TO EXIST. LINE)	L.F.	500	500			

STREET LIGHTS:

1		100W. HRS LUMINAIRE W/11 GA. POLE	EA.	3	3			
2		1 1/4" PVC CONDUIT	L.F.	934	934			
1		3 1/2" PULL BOX	EA.	1	1			

MISCELLANEOUS:

1		6" D-3 STREET NAME SIGN	EA.	1	1			
2		30" R1-1 STOP SIGN	EA.	1	1			

STORM DRAIN

NOTE TO CONTRACTOR

QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

JOB NO. 701.235 PLOTTED: 10/13/95 2:04 pm DRAWING: C:\DRAWINGS\DELWEBB\UNIT33B\33B2-SH3 BY: D.L.H.

REV	DATE	DESCRIPTION	C.L.V.	DATE

RECOMMENDED: PROFESSIONAL ENGINEER STATE OF NEVADA SONNY W. CHEN 10118 CIVIL 10/16/95 P.E. NO. DATE

G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD/LAS VEGAS, NEVADA 89102

DEL WEBB COMMUNITIES, INC.
SUN CITY LAS VEGAS UNIT NO. 33B - PHASE 2
ESTIMATE OF QUANTITIES

SHEET 3 OF 8 SHEETS

10-8-73 107Y-4141-33B-2