QUANTITIES

REVISIONS | NO. | DESCRIPTION | DATE

C.L.V. DATE | DESCRIPTION | DATE | REV | DATE

SHEET NO. →	4	5	6	7	8	9	10	11	12	13	14	15	16	17

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET													
1		2" AC PAVEMENT	S.Y.	13,573				2,589	3,272	3,475	2,036	2,201						
2		TYPE II GRAVEL BASE	C.Y.	2,521	23	52	27	445	592	616	368	398						
3		30" "ROLL" TYPE CURB & GUTTER	L.F.	7,592				1,316	1,900	1,912	1,186	1,278						
4		4' SIDEWALK	S.F.	30,292				5,215	7,600	7,669	4,695	5,113						
5		SIDEWALK RAMP (NOTE TRANSITION LENGTHS)	EA.	4				2			2							
6		CONCRETE DRIVEWAY	S.F.	5,508	1,242	2,808	1,458											

WATER:

					PHASE I				PHASE II			
					4	5	6	TOTAL	4	5	6	TOTAL
1		STD. F.H. W/6" G.V. & 6" A.C.P. LATERAL	EA.	8		2	2	4	2	2		4
2		3/4" SERVICE W/METER BOX	EA.	102		34	27	61	23	18		41
3		3/4" METER BY L.V.V.W.D.	EA.	102		34	27	61	23	18		41
4		BLOW OFF VALVE	EA.			1		1		1		1
5		10" PVC	L.F.	994		24	970	994				
6		8" PVC	L.F.	2,025		716	100	816	917	292		1,209
7		6" PVC	L.F.	600		300		300		300		300
8		8" GATE VALVE	EA.			1	1	2	4			4
9		10" GATE VALVE	EA.	1			1	1				
10		8"x 8" TEE	EA.	2			1	1	1			1
11		8"-45° BEND	EA.	2					2			2
12		6" X 8" REDUCER	EA.	4		2		2		2		2
13		8" X 10" REDUCER	EA.	2		1	1	2				
14		10"-45° BEND	EA.	2			2	2				
15		8" X 10" TEE	EA.	1			1	1				
16		CONN. TO EXIST. WATER LINE	EA.	2			1	1	1			1

SEWER:

1		8" PVC SEWER	L.F.	3,865				692	950	979	605	639																		
2		4" LATERAL	L.F.	2,549				256	700	643	450	500																		
3		STD. M.H. OVER 6'	EA.	14				6	2	3	1	2																		
4		CONC. SEWER ENCASEMENT	L.F.	20				20																						
5		CONN. TO EXIST. SANITARY SEWER	EA	2				1		1																				

STREET LIGHTS:

1		100W. HRS LUMINAIRE W/11 GA. POLE	EA.	24	7	10	7																							
2		3 1/2" PULL BOX	EA.	1	1																									
3		1 1/4" PVC CONDUIT	L.F.	3,991	1,093	1,699	1,199																							

MISCELLANEOUS:

1		6" D-3 STREET NAME SIGN	EA.	5	3		2																							
2		30" R1-1 STOP SIGN	EA.	1	1																									
3		STEEL CASING (FOR WATER LINE)	L.F	40						20		20																		

STORM DRAIN:

1		18" R.C.P.	L.F.	74						74																				
2		24" R.C.P.	L.F.	26						26																				
3		30" R.C.P.	L.F.	306				300				6																		
4		36" R.C.P.	L.F.	475						217	258																			
5		STD. M.H.	EA.	4				1		2	1																			
6		MODIFIED TYPE "C" DROP INLET L = 6'-0"	EA.	2								2																		
7		MODIFIED TYPE "C" DROP INLET L = 9'-0"	EA.	2						2																				
8		MODIFIED TYPE "C" DROP INLET L = 12'-0"	EA.	2						2																				
9		CONNECT TO EXIST. STORM DRAIN	EA.	1						1																				
10		CONCRETE OVERFLOW SWALE (10' X 109' X 4")	EA.	1									1																	

NOTE TO CONTRACTOR

QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

RECOMMENDED FOR APPROVAL — REGISTERED ENGINEER — STATE OF NEVADA — DONALD MICHAEL D. ROSS — P.E. NO. 6218 — DATE 10-10-97

G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89102

DEL WEBB COMMUNITIES, INC.
SUN CITY LAS VEGAS UNIT NO. 41 PHASE I
ESTIMATE OF QUANTITIES

SHEET 3 OF 17 SHEETS

JOB NO. 701.180
PLOTTED: 06/29/93 11:39 am DRAWING: C:\DRAWINGS\DWG 41\D41-3 BY: JDS

10-10-137 1074-4141-41