

# QUANTITIES

SHEET NO.

REVISIONS  
NO DESCRIPTION DATE

4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24

## STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
1		2" AC PAVEMENT	S.Y.	47501							3827	4472	4309	3872	4104	3515	3282	3702	3457	1505	2992	3787	2177	2500	
2		TYPE II GRAVEL BASE	C.Y.	8979	43	51	61	50	79	78	703	757	700	687	752	629	605	691	629	336	563	649	401	509	
3		30" "ROLL" TYPE CURB & GUTTER	L.F.	25532							1762	2151	1986	2129	2286	1815	1805	2187	2024	893	1639	2049	1249	1557	
4		8" VALLEY GUTTER	S.F.	10127										632	632	614	1341	618	632	2280	1496		633	1881	
5		4' SIDEWALK	S.F.	101961							7049	8605	7945	8517	9145	7258	7222	8500	8094	3573	6638	8195	4994	6226	
6		SIDEWALK RAMP (NOTE TRANSITION LENGTHS)	EA.	44										2	4	2	6	4	4	6	6		2	8	
7		CONCRETE DRIVEWAY	S.F.	19548	2322	2754	3294	2700	4266	4212															
8		TRANS. FROM "L" TYPE TO "TYPE" CURB	L.F.	80							20		20								20	20			

## TOTALS BY SHEET

## WATER:

1		STD. F.H. W/6" G.V. & 6" A.C.P. LATERAL	EA.	28	3	5	5	3	5	7														
2		3/4" SERVICE W/METER BOX	EA.	249	29	42	34	42	55	47														
3		3/4" METER BY L.V.V.W.D.	EA.	249	29	42	34	42	55	47														
4		5/8" SERVICE W/METER BOX	EA.	54		9	27	2		16														
5		5/8" METER BY L.V.V.W.D.	EA.	54		9	27	2		16														
6		BLOW OFF VALVE	EA.	5		1		1	2	1														
7		8" PVC	L.F.	6937	1230	546	1360	1764	1159	878														
8		6" PVC	L.F.	6103	118	1600	715	537	1203	1930														
9		8" GATE VALVE	EA.	13	3		3	3	1	2														
10		6" GATE VALVE	EA.	15	1	1	2	2	3	5														
11		8" x 8" TEE	EA.	3		2		2																
12		8" x 6" TEE	EA.	10	1			2	2	3														
13		6" x 6" TEE	EA.	3		2				2														
14		8"-45° BEND	EA.	4		1	2	2																
15		6"-45° BEND	EA.	4					2	2														
16		6"-11 1/4" BEND	EA.	6			1	2		3														
17		CONN. TO EXIST. WATER LINE	EA.	3	1			1	1															
18		1 1/2" IRRIGATION METER & SERVICE	EA.	11		1	5	1	1	3														
19		8" x 8" CROSS	EA.	1			1																	
20		8" x 6" REDUCER	EA.	3			1		1	1														

## SEWER:

1		8" PVC SEWER	L.F.	9498							982	57		1158	1179	763	954	1129			692	1098	652	834
2		15" PVC SEWER	L.F.	3860								1091	1133			272			1023	341				
3		4" LATERAL	L.F.	7575							425	550	500	700	900	625	410	725	625	125	365	675	500	450
4		STD. M.H.	EA.	2							0						1							
5		STD. M.H. OVER 6'	EA.	46							3	4	5	4	6	4	3	3	3	1	2	4	2	2
6		CONN. TO EXIST. SANITARY SEWER	EA.	3							1		1						1					
7		CONC. SEWER ENCASEMENT	L.F.	20																	20			
8		6" PVC SEWER	L.F.	425							425													
9		CLEAN OUT	L.F.	3							5													
10		REMOVE EXISTING 8" SANITARY SEWER.	L.F.	95									95											

## STREET LIGHTS:

1		100W. HRS LUMINAIRE W/11 GA. POLE	EA.		8	12							13	16										
2		3 1/2" PULL BOX	EA.		2	1							1	1										
3		1 1/4" PVC CONDUIT	L.F.	13582	1445	2224		2146	2440	2305	3022													
4		ELECTRICAL SERVICE	EA.																					

## MISCELLANEOUS:

1		6" D-3 STREET NAME SIGN	EA.	27	3	3		4	6	4	7													
2		30" R1-1 STOP SIGN	EA.	5	1			1	1	1	1													

## STORM DRAIN:

1		MODIFIED TYPE "C" DROP INLET L = 14'- 6"	EA.	4												2					2			
2		MODIFIED TYPE "C" DROP INLET L = 20'- 6"	EA.	6							2	2												
3		MODIFIED TYPE "C" DROP INLET L = 23'- 6"	EA.	4									2										2	
4		18" R.C.P.	L.F.	68												35					33			
5		24" R.C.P.	L.F.	1060							98	37				105					247		207	366
6		36" R.C.P.	L.F.	12																				
7		STD. M.H.	EA.	5									#5 1			#1 1					#2 1		#3,4 2	
8		CONNECT TO EXIST. STORM DRAIN	EA.	2																			1	
9		DOUBLE 16' x 4' ARCH CULVERTS	L.F.	80							80													

## NOTE TO CONTRACTOR

QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

REVISIONS  
NO DESCRIPTION DATE

DATE: 4/11/04  
REVISED ST. LIGHT QUANTITY: KNJ 4/13/04

PROJECT: SUNNY W. NEIGHBORHOODS  
NO. 10118  
P.E. NO. 17274

REGISTERED PROFESSIONAL ENGINEER  
STATE OF NEVADA  
NO. 10118

G.C. WALLACE, INC.  
Engineering/Architecture

1585 SOUTH RENO BLVD. SUITE 200 LAS VEGAS, NEVADA 89102

DEL WEBB COMMUNITIES, INC.  
SUN CITY LAS VEGAS UNIT NO. 42  
ESTIMATE OF QUANTITIES

SHEET  
3  
OF 46 SHEETS

JOB NO. 701.182  
PLOTTER: 03/25/04 10:53 am  
DRAWING: C:\DRAWINGS\DW\12\142-3  
BY: D.Lee

10-10-91 107Y-4141-42