QUANTITIES

REVISIONS NO	DESCRIPTION	DATE

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27
					TOTALS BY SHEET																							
1		2" AC PAVEMENT	S.Y.	40900								4185	4083	3920	3751	4225	2577	3141	2550	977	1866	1898	2055	1213	1007	1989	1462	
2		TYPE II GRAVEL BASE	C.Y.	8322	44	53	34	40	53	50	42	976	922	915	726	744	507	540	504	174	340	353	387	219	20	347	331	
3		30" "ROLL" TYPE CURB & GUTTER	L.F.	20689								2151	1908	2016	2094	2195	1326	1484	1348	507	1023	1100	1222	598	158	889	673	
4		8' VALLEY GUTTER	S.F.	7550								960	1264		1264	960	1590		1512									
5		4' SIDEWALK	S.F.	67660								7850	1824	2016	8324	6668	5279	5879	5366	2027	4098	4372	4888	2582	251	3546	2691	
6		SIDEWALK RAMP (NOTE TRANSITION LENGTHS)	EA.	37								4	8		6	4	4	4	4					3				
7		CONCRETE DRIVEWAY	S.F.	17056	2374	2844	1836	2160	2868	2684	2290																	
8		TRANS. FROM "L" TYPE TO ROLL "TYPE" CURB	L.F.	120									20	20		20	20				10			30				

WATER:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27
1		STD. F.H. W/6" G.V. & 6" A.C.P. LATERAL	EA.	23	5	3	3	2	4	3	3																	
2		5/8" SERVICE W/METER BOX	EA.	39	6	8			12	4	8																	
3		5/8" METER BY L.V.V.W.D.	EA.	39	6	9			12	4	8																	
4		3/4" SERVICE W/METER BOX	EA.	196	28	30	26	34	29	33	16																	
5		3/4" METER BY L.V.V.W.D.	EA.	196	28	30	26	34	29	33	16																	840
6		BLOW OFF VALVE	EA.	10	1	2	2	1	2	2	0																	
7		16" D.I.P.	L.F.	1701	861																							
8		8" PVC	L.F.	5920	282	578	430	1419	1015	1162	1034																	
9		6" PVC	L.F.	4101	1015	1068	768	711	365	174																		
10		8" GATE VALVE	EA.	9	1	1	1	3	1	2																		
11		6" GATE VALVE	EA.	8	2	3	2																					
12		16"x 8" TEE	EA.	1	1																							
13		16"x 6" TEE	EA.	2	2																							
14		8"x 8" TEE	EA.	3				2		1																		
15		8"x 6" TEE	EA.	4		1		1		2																		
16		6" X 6" TEE	EA.	5	1	2	2																					
17		8"-45° BEND	EA.	6				4			2																	
18		6"-45° BEND	EA.	2				2																				
19		8"-90° BEND	EA.	1				1																				
20		16"-90° BEND	EA.	1	1																							
21		CONN. TO EXIST. WATER LINE	EA.	4			1			1	2																	
22		1 1/2" IRRIGATION METER & SERVICE	EA.	4	1	1			1		1																	
23		16" x 8" REDUCER	EA.	1	1																							
24		8" x 6" REDUCER	EA.	3				1	2																			
25		16" BUTTERFLY VALVE W/ MANHOLE	EA.	2	2																							

SEWER:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27
1		8" PVC SEWER	L.F.	△ 10665								957	1002	1036	1135	1136	667	798	747	466	468	587	611	294		331		
2		15" PVC SEWER	L.F.																									
3		4" LATERAL	L.F.	6980								810	480	730	600	715	300	100	370	150	350	575	500	180		480		
4		STD. M.H.	EA.																									430
5		STD. M.H. OVER 6'	EA.	△ 41								4	3	3	4	4	3	2	3	3	2	1	1	3		2		
6		CONN. TO EXIST. SANITARY SEWER	EA	2										1			1											640
7		CONC. SEWER ENCASEMENT	L.F.																									
8		REMOVE EXISTING 8" SANITARY SEWER.	L.F.	74										41										33				

STREET LIGHTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10
1		100W. HRS LUMINAIRE W/11 GA. POLE	EA.	△ 64	12	10	7	11	8	10	6
2		3 1/2" PULL BOX	EA.	6	2		1	3			
3		1 1/4" PVC CONDUIT	L.F.	9821	1595	1664	1091	1810	1208	1567	886
4		ELECTRICAL SERVICE	EA.								

MISCELLANEOUS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10
1		6" D-3 STREET NAME SIGN	EA.	21	4	3	3	5	0	4	2
2		30" R1-1 STOP SIGN	EA.								

NOTE TO CONTRACTOR

QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

STORM DRAIN:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
1		MODIFIED TYPE "C" DROP INLET L = 11'- 6"	EA	3																	1			2	
2		MODIFIED TYPE "C" DROP INLET L = 14'- 6"	EA	0																					
3		MODIFIED TYPE "C" DROP INLET L = 23'- 6"	EA.	8									2	1		2	3								
4		MODIFIED TYPE "C" DROP INLET L = 5'- 6"	EA	1										1											
5		MODIFIED TYPE "C" DROP INLET L = 8'- 6"	EA	0																					
6		MODIFIED TYPE "C" DROP INLET L = 18'- 6"	EA	0																					
7		30" R.C.P.	L.F.	159									44					115							
8		24" R.C.P.	L.F.	1019								67	40	75	30	49	68	675			15				
10		36" R.C.P.	L.F.	1313																	537			494	282
11		18" R.C.P.	L.F.	193													55							138	
12		STD. M.H.	EA.	11								1					1	2			3			4	
13		CONCRETE RIP-RAP	C.Y.	5																					
14		TYPE III BARRICADES	EA.	2	1						1														

REV	DATE	DESCRIPTION	C.L.V.	DATE
△1	6/16/94	REV. QUANTITIES	CB	8/1/94

RECOMMENDED: SONNY W. NEIGHBORS 10118 P.E. NO. 4-27-94 DATE

G&T 6/20/94

PROFESSIONAL ENGINEER - STATE OF NEVADA - SONNY W. NEIGHBORS - CIVIL - No. 10118

G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89102

DEL WEBB COMMUNITIES, INC.
SUN CITY LAS VEGAS UNIT NO. 43
ESTIMATE OF QUANTITIES

SHEET 3 OF 38 SHEETS

JOB NO. 701.184

PLOTTED: 04/21/94 08:00 am DRAWING: C:\DRAWINGS\DW\UNIT43\D43-3 BY: SMC

1910-53

107Y-4141-43