QUANTITIES

REVISIONS NO	DESCRIPTION	DATE

C.L.V.	DESCRIPTION	DATE	REV

SHEET NO.	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27

STREET IMPROVEMENTS:

NO.	LEGEND	DESCRIPTION	UNIT	TOTAL	TOTALS BY SHEET																							
1		2" AC PAVEMENT	S.Y.	62558									3223	3444	1110	1590	1595	2420	2128	2331	2928	1274	948	2400	3492	3064	2736	3422
2		TYPE II GRAVEL BASE	C.Y.	12091	41	45	63	34	52	82	18	40	631	693	219	286	327	425	370	435	618	272	174	443	681	577	513	635
3		30" "ROLL" TYPE CURB & GUTTER	L.F.	33355									1829	1932	600	846	891	1211	1058	1354	1650	713	528	1364	1887	1608	1460	1966
4		8' VALLEY GUTTER	S.F.	14103									1249	1986	612		1164				2705	1265			1598	638	643	
5		4' SIDEWALK	S.F.	132340									7182	7668	2354	3387	3460	4809	3984	5414	6388	2788	2113	5454	7503	6908	5813	7879
6		SIDEWALK RAMP (NOTE TRANSITION LENGTHS)	EA.	64									6	6	4	2	4	4	2		6	4		4	8	4		4
7		CONCRETE DRIVEWAY	S.F.	20215	2196	2408	3408	1836	2798	4432	972	2164																
8		TRANS. FROM "L" TYPE TO ROLL "TYPE" CURB	L.F.	200									40				20					80			20	20		20

WATER:

1		STD. F.H. W/6" G.V. & 6" A.C.P. LATERAL	EA.	39	3	4	7	3	7	8	4	4																
2		3/4" SERVICE W/METER BOX	EA.	309	38	38	46	30	44	63	14	38																
3		3/4" METER BY L.V.V.W.D.	EA.	309	38	38	46	30	44	63	14	38																
4		5/8" SERVICE W/METER BOX	EA.	92		10	21		16	26	11	8																
5		5/8" METER BY L.V.V.W.D.	EA.	92		10	21		16	26	11	8																
6		BLOW OFF VALVE	EA.	12	2	1	4	1	1		1	2																
7		16" D.I.P.	L.F.	2662.10	841.10	793				1028																		
8		8" PVC	L.F.	8107	137.49	764	1840	533	1419	1460	1153	799																
9		6" PVC	L.F.	5941	379.98	719	909	580	984	1399	107	862																
10		8" GATE VALVE	EA.	26	1	2	9	1	2	4	3	4																
11		6" GATE VALVE	EA.	11		2	1		3	4		1																
12		16"x 8" TEE	EA.	2	1	1																						
13		16"x 6" TEE	EA.	5	1	2				2																		
14		8"x 8" TEE	EA.	9		1	4		2		1	1																
15		8"x 6" TEE	EA.	6			1	1	2	2																		
16		16" X 16" TEE	EA.	2						2																		
17		8" x 90° ELL	EA.	2			2																					
18		8"-45° BEND	EA.	2						2																		
19		8"-90° BEND	EA.	1		1																						
20		16" 90° BEND	EA.	1	1																							
21		6" x 11-1/4° BEND	EA.	2						1		1																
22		8" x 11-1/4° BEND	EA.	4	1	1	1				1																	
23		6" x 22-1/2° BEND	EA.	1		1																						
24		1 1/2" RPPA	EA.	9		1	2		2	2	1	1																
25		16" x 11-1/4° BEND	EA.	1						1																		
26		CONN. TO EXIST. WATER LINE	EA.	5				2	2			1																
27		1 1/2" IRRIGATION METER & SERVICE	EA.	9		1	2		2	2	1	1																
28		16" x 8" REDUCER	EA.	2						2																		
29		8" x 6" REDUCER	EA.	15		1	4	3	1		2	4																
30		16" BUTTERFLY VALVE W/ MANHOLE	EA.	6	2	1				3																		
31		8" CROSS	EA.	2							1	1																
32		6" x 90° ELL	EA.	2			1					1																

SEWER:

1		8" PVC SEWER	L.F.	15793									924	1001	346.20	497.10	450	500	489.10									
2		15" PVC SEWER	L.F.	2096															175	711	851.4	359	409.2	756.3	988	907	759	1006
3		4" LATERAL	L.F.	10315									380	285	60	225	175	300	400	550	275	60	475	450	420	660	405	710
4		STD. M.H.	EA.																									
5		STD. M.H. OVER 6'	EA	66									5	5	2	2	3	2	2	2	3	1	1	4	6	4	1	5
6		CONN. TO EXIST. SANITARY SEWER	EA	3									1				1					1						
7		CONC. SEWER ENCASEMENT	L.F.	220									20				20							20	20	20		20

STREET LIGHTS:

1		100W. HRS LUMINAIRE W/11 GA. POLE	EA.	86	8	14	16	8	16	20	7	12																
2		3 1/2" PULL BOX	EA.	20	2	1	3	3	4	3	1	3																
3		1 1/4" PVC CONDUIT	L.F.	18770.39	1778.68	2305.98	2918.27	1763.64	3108.10	3617.02	1230.96	2047.74																
4		ELECTRICAL SERVICE	EA.																									

MISCELLANEOUS:

1		6" D-3 STREET NAME SIGN	EA.	33	2	5	4	3	6	5	3	5																
2		30" R1-1 STOP SIGN	EA.	2					1			1																

NOTE TO CONTRACTOR

QUANTITIES SHOWN ARE ESTIMATES ONLY AND ARE INTENDED TO ILLUSTRATE SCOPE OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXACT QUANTITIES INVOLVED.

STORM DRAIN:

1		MODIFIED TYPE "C" DROP INLET L = 20'- 6"	EA.	16									4				2					8			2	2		
2		MODIFIED TYPE "C" DROP INLET L = 14'- 6"	EA.	2																					2			2
3		MODIFIED TYPE "C" DROP INLET L = 5'- 6"	EA.	2																								
4		42" R.C.P.	EA.	90.28																								
5		36" R.C.P.	EA.	564																		31						
6		30" R.C.P.	L.F.	282																		86				41		
7		24" R.C.P.	L.F.	347									58				45					111.42			44	35		53
8		18" R.C.P.	L.F.	318									70									140			35			35
9		4" CONC. ENCASEMENT	L.F.	100									40												20	20		20
10		STD. M.H.	EA.	4																								
11		CONNECT TO EXIST. STORM DRAIN	EA.	4									1									1						

RECOMMENDED FOR APPROVAL BY COUNTY ENGINEER — STATE OF NEVADA — REGISTERED PROFESSIONAL ENGINEER — P.E. NO. 10118 — DATE 7-14-94

DEL WEBB COMMUNITIES, INC.
SUN CITY LAS VEGAS UNIT NO. 44
ESTIMATE OF QUANTITIES

G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89102

SHEET 3 OF 49 SHEETS

JOB NO. 701.186
PLOTTED: 07/12/94 3:43 pm
DRAWING: C:\DRAWINGS\DWG\4141044-3
BY: D.Lee

10-1

107Y-4141-44