

SEWER MANHOLE SCHEDULE

M.H. #	I.D.	TYPE	STATION	OFFSET	N. INV. EL.	S. INV. EL.	E. INV. EL.	W. INV. EL.	COMMENTS
1-1		SD-1	18+90.94	25' LT	2295.47	N/A	2295.27	N/A	PUBLIC
1-2A		SD-1	21+07.44	25' LT	N/A	N/A	2294.40	2294.40	PUBLIC
1-2		SD-1	23+90.94	25' LT	N/A	N/A	2293.27	2293.27	PUBLIC
1-3		SD-1	28+90.23	25' LT	2291.88	N/A	N/A	2291.68	PUBLIC
1-4		SD-1	10+07.00	5' RT	2292.42	2292.22	N/A	N/A	PUBLIC
1-5		SD-1	11+31.09	5' RT	2293.12	2292.92	N/A	2293.12	PUBLIC
1-6		SD-1	23+17.54	5' LT	N/A	N/A	2293.66	2293.46	PUBLIC
1-7		SD-1	21+31.27	5' LT	N/A	2294.60	2294.40	2294.60	PUBLIC
1-8		SD-1	26+10.71	7.5' RT	2295.63	N/A	N/A	2295.83	PUBLIC
1-9		SD-1	24+12.99	8.5' LT	N/A	N/A	2296.63	2296.83	PUBLIC
1-10		SD-1	21+79.00	8.5' LT	N/A	N/A	2298.22	N/A	PUBLIC
1-11		SD-1	14+16.94	5' RT	2294.47	2294.27	N/A	2294.27	PUBLIC
1-12		SD-1	19+61.11	5' LT	N/A	N/A	2294.73	2294.93	PUBLIC
1-13		SD-1	17+52.13	5' RT	2296.00	2295.80	N/A	2296.00	PUBLIC
1-14		SD-1	14+08.47	5' LT	N/A	N/A	2296.76	2296.96	PUBLIC
1-15		SD-1	22+02.14	5' RT	2297.82	2297.62	N/A	N/A	PUBLIC
1-16		SD-1	28+38.99	5' RT	N/A	2298.43	2298.63	2298.63	PUBLIC
1-17		SD-1	15+14.16	5' LT	N/A	N/A	2296.65	2296.45	PUBLIC
3-1		SD-1	16+64.34	5' LT	N/A	N/A	2296.31	2296.11	PUBLIC
4-1		SD-1	19+31.72	5' LT	N/A	N/A	2295.60	2295.40	PUBLIC

QUANTITY ESTIMATES

SEWER

ITEM #	DESCRIPTION	UNIT	QUANTITY	PUBLIC	PRIVATE
1	SEWER MANHOLE	1	16 EA.	X	
2	8" SEWER MAIN	1	3892 LF	X	

WATER

ITEM #	DESCRIPTION	UNIT	QUANTITY	PUBLIC	PRIVATE
1	COMPLETE F.H. ASSEMBLY	1	6 EA.	X	
2	8" WATER MAIN	1	2350 LF	X	
3	8" GATE VALVE	1	18 EA.	X	
4	1" SERVICE WITH 1" METER	1	7EA.	X	
5	8" TEE	1	9 EA.	X	
6	2" BLOW OFF	1	11 EA.	X	
7	8" 90° ELBOW	1	6 EA.	X	
8	10" W.L.	1	2221 L.F.	X	

ITEM #	DESCRIPTION	UNIT	QUANTITY	PUBLIC	PRIVATE
9	10" GATE VALVE	1	7 EA.	X	
10	12"X10" M.J. TPPNG .SLV. & VALVE	1	1 EA.	X	
11	10"X8" TEE	1	2 EA.	X	
12	10"X8" REDUCER	1	3 EA.	X	
13	10" 45° BEND	1	2 EA.	X	
14	10" 11 1/4° BEND	1	3 EA.	X	
15	10"X6" TEE	1	2 EA.	X	
16	6" W.L.	1	125 L.F.	X	
17	8"X6" REDUCER	1	2 EA.	X	
18	1" SERVICE W/ 3/4" METER	1	50 EA.	X	
19	3/4" RPPA	1	3 EA.	X	
20	10" D.I.P. W.L.	1	115 L.F.	X	
21	10" Tee	1	4 EA.	X	

SURFACE IMPROVEMENT

ITEM #	DESCRIPTION	QUANTITY	PUBLIC	PRIVATE
1	CURB & GUTTER (TYPE "L" & "A")	8,611 LF	X	X
2	SIDEWALK 4"	22,262 SF	X	X
3	2" ASPHALTIC CONCRETE PAVING	11,879 SY	X	X
4	POWER TO LOTS	52 EA.		X
5	TELEPHONE TO LOTS	52 EA.		X
6	STREET LIGHT (STANDARD BASE)	13 EA.	X	
7	STREET/STOP SIGNS	7 EA.	X	
8	4" ASPHALTIC CONCRETE PAVING	11,374 SY	X	
9	TYPE I AGGRAGATE BASE	2,843 CY	X	X
10	TYPE II AGGRAGATE BASE	4,538 CY	X	X
11	CROSS GUTTER	4,875 SF	X	X

Avoid overhead power
line contact
Call
before you
OVERHEAD
1-702-593-6111
NEVADA POWER ENVIRONMENT
SAFETY SERVICES DEPARTMENT

Avoid cutting underground
utility lines. It's costly
Call
before you
Dig
1-800-227-2600
UNDERGROUND SERVICE (USA)

APPROVED FOR CONSTRUCTION

[Signature] 4/10/97
L.V.V.W.D. DATE

D. R. HORTON
CUSTOM HOMES
2920 N. GREEN VALLEY PKWY. SUITE 111 HENDERSON, NV. 89014
(702) 435-4888, FAX (702) 435-4900

HUNSAKER & ASSOCIATES
PLANNING
ENGINEERING
SURVEYING
N. V. P. O. BOX 111
401 N. Buffalo Dr., Suite 200, Las Vegas, Nevada 89108 (702) 248-4200

QUANTITY AND SCHEDULE SHEET

TROPICAL/JONES - UNIT 1
A.K.A. PARADISE FALLS - UNIT 1
CITY OF LAS VEGAS, NEVADA

QUALITY CONTROL BY:
DESIGNED BY:
CHECKED BY:
A. SALCIDO
PROJECT NO.
2291-1

SEAL
REGISTERED PROFESSIONAL ENGINEER STATE OF NEVADA
LARRY W. BRADSHAW
LICENSE NO. 9115
EXPIRES 3-11-97

SHEET
C4
4 OF 31
DRAWING NO.
107Y4592-1

