

ESTIMATED
QUANTITIES

2' curb & gutter	350 lin. ft.
Sidewalk	1187 sq. ft.
Driveway	785 sq. ft.
6" ACP drain	180 lin. ft.
Fire hydrant	1 ea
12x12x6 wet tap	1 ea
6" valve & valve box	1 ea
6" C.I.P.	92 lin. ft.

Existing paving to be cut back and removed as necessary to meet new curb and gutter at the direction of Field Engineer.

NOTE: UTILITY INFORMATION WAS
DERIVED FROM DATA FURNISHED BY
UTILITY COMPANIES. CONTRACTOR
MUST CONFIRM LOCATION OF UTILITIES
BEFORE COMMENCING EXCAVATION.

Bench Mark: CLV 06130C1 located
near the Southeast corner of the
intersection of Decatur Blvd.
and Washington Ave.
Elev = 2199.38

REVISIONS

APPROVALS

Land Surveyors
Las Vegas, Nevada

LEAVITT & HOLLER
Registered Professional Engineers
536 East Sahara Avenue

STREET DESIGN
DECATUR BOULEVARD

being a portion of the Northwest Quarter (NW1/4) of the Southwest Quarter (SW1/4) of Section 30, T.20S., R.6E., M.1M. Nevada
City of Las Vegas

J. L. Mink *6-15-68*
File Chief *date*

Horiz. 1"=10'
Vert. 1"=5'

Designed	Date
D. J. Buckley	5/28/68

Being a portion of the Northwest Quarter (NW1/4) of the Southwest Quarter (SW1/4) of Section 30, T.20S, R.61E, M.D.M. Nevada
City of Las Vegas

107-V763
Sheet 1 of 3 Sheets

Richfield
Svc Sta-
Lgt-207-1