

SUBDIVISION
THE SOUTHEAST 1/4, OF THE SOUTHWEST 1/4,
SECTION 29, TOWNSHIP 20 SOUTH, RANGE 62 EAST, M.D.B.&M.
CLARK COUNTY
NEVADA
TRACT 1

1. All work shall be done in strict accordance with the City of Las Vegas Specifications.
2. All work shall be done in strict accordance with City of Las Vegas Fire Department "Hydrant Specifications", "Hydrant Installation Specifications" and "Water Resolutions and Requirements". *Authorized Hydrants are Kennedy Guardrail or Keller 4-430 Containers*
3. On any new home or building construction, accessible fire hydrants are to be installed before actual construction commences and said fire hydrants shall be in good working order with adequate water supply.
4. Painting of curb or stripping of asphalt areas, and protection of hydrants from physical injury per City of Las Vegas Fire Department Hydrant Installations shall be completed before approval of the hydrants by the City of Las Vegas Fire Department.
5. No fire hydrant shall be located within 45 feet of any driveway, power pole, light standard, or other obstructions, for wall, fence and planter locations. Drawings 44-0 "B" shall be used.

TRACT 1

- 1 each 8" x 6" Reducer
1 each 8" 221/2" ell
1 each 12" x 6" Tapping Tee & Valve(M.J.)
375.00 L.F. 8" ACP Water Main Remove & Replace
8 each Fire Hydrants Ex. 6" Gate Valve
8 each 8" x 6" Tees
13 each 6" Gate Valves
1 each 8" x 12" Tapping Tee & Valve (M.J.)
5 each 8" Tees Remove & Replace
1 each 8" 45° Bend Ex. Fire Hydrant
13 each 8" Gate Valves
1551.00 L.F. 6" ACP Water Main
5 each 8" Plug W/2" Blowoff
91 each 3/4" Services
3 each 6" Plug W/2" Blowoff
TRACT 2
3301.00 L.F. 8" ACP Water Main Remove & Replace
5 each Fire Hydrants Ex. 6" Gate Valve
3 each 8" x 6" Tees
9 each 6" Gate Valves
4 each 8" Tees
9 each 8" Gate Valves
160.00 L.F. 6" ACP Water Main
1 each 8" 90° Bend
1 each 8" x 8" x 6" Tee
1 each 6" Plug W/2" Blowoff Assy.
98 each 3/4" Services

1. All work to conform to Las Vegas Valley Water District standard plates.
2. All work, except as modified hereon or by Note No. 1 shall be done in accordance with the most current draft or edition of Uniform Standard Specifications for Public Works Construction Offsite Improvements Clark County Area.
3. Notice to be given Engineering Department of the Las Vegas Valley Water District 48 hours prior to actual construction.
4. Service saddles or tapped collars will be required on all services, double tap collars are not permitted.
5. All lines to be pressure tested to 200 psi.
6. All valve boxes shall have concrete collars at surface of paved areas.
7. Deflection angle shall not exceed 2½ degrees per 13 foot section of pipe for pipe sizes smaller than 14 inches and shall not exceed 2 degrees for pipe sizes between 14" and 16".
8. All meters shall be located outside of driveways.
9. Service laterals for lots
will be tapped on existing main by owner's contractor under direction of the Las Vegas Valley Water District.

City	Fire Marshall	Date	6/6/84
City	William E. Kuhl	Date	4/2/84
City	Quality Control Engineer	Date	
City	Field Operations Engineer	Date	
City	Engineer	Date	6-26-84
City	Consulting Engineer	Date	7/2/84

Las Vegas Valley Water Dist. Date

LOCATION MAP

MASTER WATER PLAN

