TOTAL APPROXIMATE QUANTITIES – STRESSED AREAS

ITEM NO.	DESCRIPTION	UNIT	QUANTITY
	REMOVE 4" A.C. & 1/2" OPEN GRADE	S.Y.	20,184
	REMOVE 1 1/2" A.C. (ISLANDS)	S.Y.	1,972
	REMOVE 5" CONC. SLAB (ISLANDS)	S.F.	8,556
	REMOVE ISLAND CURB ("A" TYPE)	L.F.	2,762
	REMOVE 24" "L" TYPE CURB & GUTTER	L.F.	1,848
	REMOVE 12" LIME STABILIZED BASE	C.Y.	7,976
	REMOVE 12" SUB-GRADE SOIL (STOCK PILE)	C.Y.	7,976
	REMOVE TYPE 2 GRAVEL (STOCK PILE)	C.Y.	4,728

TOTAL APPROXIMATE QUANTITIES – RECONSTRUCTION

ITEM NO.	DESCRIPTION	UNIT	QUANTITY
	FILL MATERIAL (FROM STOCK PILE)	C.Y.	7,976
	NEW LIME STABILIZED FILL	C.Y.	7,976
	TYPE 2 GRAVEL (FROM STOCK PILE)	C.Y.	4,728
	24" "L" TYPE CURB & GUTTER	L.F.	1,848
	ISLAND CURB ("A" TYPE)	L.F.	2,762
	5" CONCRETE FLATWORK (ISLANDS)	S.F.	8,556
	1 1/2" A.C. ISLAND PAVEMENT-COLORED	TON	180
	4" A.C. & 1/2" OPEN GRADE PAVEMENT	TON	5,370

CITY OF LAS VEGAS
CLARK COUNTY, NEVADA

Department of Public Services Engineering Design Division

STEWART AVE.
REPAIRS

DETAILS &
APPROXIMATE QUANTITIES

Scale (h) 1"=20' | Scale (v) ——— | W.O. no. 0120
Fld. bk. no. —— | Date 2-15-79
Design by ——— | Drawn by ———
Approved by the Director of Public Services | Date

Revisions | Date

Drawing no. 107-V8I9C 2/21

16-4-63