



LAS VEGAS CITY COUNCIL

OSCAR B. GOODMAN
MAYOR

GARY REESE
MAYOR PRO TEM

STEVE WOLFSON


LOIS TARKANIAN

STEVEN D. ROSS

RICKI Y. BARLOW

STAVROS S. ANTHONY

ELIZABETH N. FRETWELL
CITY MANAGER



CITY OF LAS VEGAS
400 STEWART AVENUE
LAS VEGAS, NEVADA 89101

VOICE 702.229.6011
TTY 702.386.9108

www.lasvegasnevada.gov

FM-0044-08-09

March 19, 2010

Ms. Elizabeth Fretwell
City Parkway V, Inc.
400 Stewart Avenue, 8th Floor
Las Vegas, Nevada 89101

RE: EOT-37340 – EXTENSION OF TIME – SPECIAL USE PERMIT
CITY COUNCIL MEETING OF MARCH 17, 2010

Dear Ms. Fretwell:

The City Council at a regular meeting held March 17, 2010 APPROVED the Request for an Extension of Time of a previously approved Site Development Plan Review (SDR-25059) FOR A PROPOSED 57-STORY MIXED-USE DEVELOPMENT INCLUDING 1.12 MILLION SQUARE FEET OF COMMERCIAL SPACE AND 98 MULTI-FAMILY RESIDENTIAL UNITS WITH WAIVERS OF THE UNION PARK STREETScape STANDARDS, BUILDING PLACEMENT AND FRONTAGE REQUIREMENTS, ARCHITECTURAL STANDARDS AND ACCESS STANDARDS on a portion of 53.6 acres at the southwest corner of Grand Central Parkway and City Parkway (APN 139-34-110-007), PD (Planned Development) Zone. The Notice of Final Action was filed with the Las Vegas City Clerk on March 18, 2010. This approval is subject to:

Planning and Development

1. This Site Development Plan Review (SDR-25059) shall expire on February 6, 2012 unless another Extension of Time is approved by the City Council.
2. Conformance to the conditions of approval of the Site Development Plan Review (SDR-25059) and all other site related actions as required by the Planning and Development Department and Department of Public Works.

Sincerely,

Leann Coleman
Deputy City Clerk II for
Beverly K. Bridges, MMC, City Clerk

cc: Mr. Robert Zarnegin
Heritage-Nevada VIII, LLC
421 North Beverly Drive, Suite #350
Beverly Hills, California 90210

PLANNING & DEVELOPMENT



DEVELOPMENT SERVICES CENTER

731 S. Fourth Street
Las Vegas, NV 89101

Voice: 702-229-6301
Fax: 702-474-0352
TTY: 702-386-9108

www.lasvegasnevada.gov

March 5, 2010

Ms. Elizabeth Fretwell
City Parkway V, Inc.
400 Stewart Avenue, 8th Floor
Las Vegas, Nevada 89101

RE: EOT-37340 - EXTENSION OF TIME - SPECIAL USE PERMIT

Dear Ms. Fretwell:

Please be advised the City Council at its regular meeting on *March 17, 2010* as referred to above, will consider your request. This meeting will be held at 1:00 P.M. at the Council Chambers of City Hall, 400 Stewart Avenue, Las Vegas, Nevada.

A copy of staff's recommendations, any conditions related to your application and the *final agenda* will be available on-line on *Friday, March 12, 2010* at www.lasvegasnevada.gov. If you do not have access to the Internet and would prefer receiving hard copies of the documentation, please call the Case Planning Division at (702) 229-6301 or come into the Development Services Center at 731 South Fourth Street to request your copies.

The City Council requires that you or your representative be present at this meeting.

Sincerely,

M. Margo Wheeler, AICP
Director, Planning and Development Department

MW:clb

cc: Mr. Robert Zarnegin
Heritage-Nevada VIII, LLC
421 North Beverly Drive, Suite #350
Beverly Hills, California 90210

Mayor
Oscar B. Goodman
City Council
Gary Reese
(Mayor Pro Tem)
Steve Wolfson
Lois Tarkanian
Steven D. Ross
Ricki Y. Barlow
Stavros S. Anthony
City Manager
Elizabeth N. Fretwell





FEB 13 2008

February 8, 2008

LAS VEGAS CITY COUNCIL

OSCAR B. GOODMAN
MAYOR

GARY REESE
MAYOR PRO TEM

LARRY BROWN
STEVE WOLFSON
LOIS TARKANIAN
STEVEN D. ROSS
RICKI Y. BARLOW

DOUGLAS A. SELBY
CITY MANAGER

Dr. Doug Selby
City Parkway V, Inc.
400 Stewart Avenue, 8th Floor
Las Vegas, Nevada 89101

RE: SDR-25059 – SITE DEVELOPMENT PLAN REVIEW
CITY COUNCIL MEETING OF FEBRUARY 6, 2008
RELATED TO SUP-25060

Dear Dr. Selby:

The City Council at a regular meeting held February 6, 2008 APPROVED the request for a Site Development Plan Review FOR A PROPOSED 57-STORY MIXED-USE DEVELOPMENT INCLUDING 1.12 MILLION SQUARE FEET OF COMMERCIAL SPACE AND 98 MULTI-FAMILY RESIDENTIAL UNITS WITH WAIVERS OF THE UNION PARK STREETScape STANDARDS, BUILDING PLACEMENT AND FRONTAGE REQUIREMENTS, ARCHITECTURAL STANDARDS, AND ACCESS STANDARDS on a portion of 53.6 acres at the southwest corner of Grand Central Parkway and City Parkway (APN 139-34-110-004), PD (Planned Development) Zone. The Notice of Final Action was filed with the Las Vegas City Clerk on February 7, 2008. This approval is subject to:

Planning & Development

1. Approval of and conformance to the Conditions of Approval for Special Use Permit (SUP-25060) shall be required.
2. This approval shall be void two years from the date of final approval, unless a building permit has been issued for the principal building on the site. An Extension of Time may be filed for consideration by the City of Las Vegas.
3. All development shall be in conformance with the site plan, landscape plan, and building elevations, date stamped 10/09/07, and the revised parking study data, date stamped 10/19/07, except as amended by conditions herein.
4. The following Waivers from Union Park Design Standards are hereby approved as follows:
 - a. A Waiver from Subsection 1.6.2 is hereby approved, to allow two vehicle access points on Grand Central Parkway where only one access point is allowed.

CITY OF LAS VEGAS
400 STEWART AVENUE
LAS VEGAS, NEVADA 89101

VOICE 702.229.6011
TTY 702.386.9108
www.lasvegasnevada.gov

EOT-37340
03/1710 CC

- b. A Waiver from Subsection 1.6.4 is hereby approved, to allow the exterior parking structure treatment as shown in the elevations date stamped 10/09/07, where an architecturally consistent treatment is required.
 - c. A Waiver from Subsection 1.9.2 is hereby approved, to allow a different curvature to the alignment of The Promenade as shown on the site plan date stamped 10/09/07, where conformance to the alignment shown in illustration in Subsection 1.9 is required.
 - d. A Waiver from Subsection 2.5 is hereby approved, to allow a 10-foot sidewalk width for a segment along the Grand Central Parkway frontage of the property where a 12-foot width is required.
 - e. A Waiver from Subsection 3.1(B) is hereby approved to allow building setbacks at 55'-9" and 103'-4" where a setback at 80'-0" is required.
 - f. A Waiver from Subsection 3.13.1 is hereby approved, to allow no streetwall offset along the Grand Central Parkway and City Parkway facades as shown in the elevations dated 10/09/07, where a three-foot streetwall offset is required.
 - g. A Waiver from Subsection 4.5(E.2) is hereby approved, to allow the use of non-specified palm trees on the enclosed interior of The Promenade in accordance with the landscape plans dated 10/09/07, where conformance to the palm trees specified in the Union Park standards is required.
- 5. Any exterior art or streetscape furniture contemplated in the Union Park Owner's Association sidewalk streetscape area shall be submitted to the UP-DRC for review and approval prior to installation in accordance with Union Park Design Standards.
 - 6. The paving materials utilized at the Grand Central Parkway main entry and the City Parkway valet entry shall delineate the pedestrian pathway with a paving pattern and/or color across all vehicular driveways that cross the perimeter Union Park Owner's Association sidewalk streetscape area in order to increase pedestrian safety.
 - 7. The final transparency and reflectivity of glazing at either end of the enclosed retail space shall be reviewed and approved by the UP-DRC prior to the issuance of a building permit in accordance with Subsection 3.5 of the Union Park Design Standards.
 - 8. As part of the building permit/construction document submittal process as outlined in the Union Park Design Standards, the completed project LEED checklist and a letter from the commissioning agent confirming preparation of documents for submission to the USGBC shall be submitted to the UP-DRC for review and approval prior to the issuance of a certificate of occupancy.
 - 9. Construction documents shall be submitted to the UP-DRC for review and approval prior to the issuance of a building permit in accordance with Section 5 of the Union Park Design Standards. The review shall be limited to the conditions of approval placed upon the project by the City of Las Vegas. A letter of approval from the UP-DRC must be submitted with the building permit application.

10. A technical landscape plan, signed and sealed by a Registered Architect, Landscape Architect, Residential Designer or Civil Engineer, must be submitted prior to or at the same time application is made for a building permit. A permanent underground sprinkler system is required, and shall be permanently maintained in a satisfactory manner; the landscape plan shall include irrigation specifications.
11. No turf shall be permitted in the non-recreational common areas, such as medians and amenity zones in this development.
12. Pre-planting and post-planting landscape inspections are required to ensure the appropriate plant material, location, size of planters, and landscape plans are being utilized. The Planning and Development Department must be contacted to schedule an inspection prior to the start of the landscape installation and after the landscape installation is completed. A certificate of occupancy will not be issued or the final inspection will not be approved until the landscape inspections have been completed.
13. Any new utility or power service line provided to the parcel shall be placed underground from the property line to the point of on-site connection or on-site service panel location.
14. All mechanical equipment, air conditioners and trash areas shall be fully screened in views from the abutting streets.
15. All utility boxes exceeding 27 cubic feet in size shall meet the standards of LVMC Title 19.12.040.
16. Parking lot lighting standards shall be no more than 30 feet in height and shall utilize downward-directed lights with full cut-off luminaires. Lighting on the exterior of buildings shall be shielded and shall be downward-directed.
17. Approval of this Site Development Plan Review application does not constitute approval of the signage. A more detailed master sign package and tenant design criteria shall be submitted to the UP-DRC for review and approval prior to the issuance of any sign permits in accordance with Subsection 3.16 of the Union Park Design Standards.
18. A Comprehensive Construction Staging Plan shall be submitted to the Planning and Development Department for review and approval prior to the issuance of any building permits. The Construction Staging Plan shall include the following information: Design and location of construction trailer(s); design and location of construction fencing; all proposed temporary construction signage; location of materials staging area; and the location and design of parking for all construction workers.
19. Written approval by the Clark County Department of Aviation with no change in flight patterns shall be submitted to the City of Las Vegas prior to the issuance of building permits.


Dr. Doug Selby
SDR-25059 – Page Four
February 8, 2008

20. Prospective buyers shall be informed that views may be obscured by future adjacent development and this information shall be included in project CC & R's.
21. Prior to the submittal of a building permit application, the applicant shall meet with Planning and Development Department staff to develop a comprehensive address plan for the subject site. A copy of the approved address plan shall be submitted with any future building permit applications related to the site.
22. All City Code requirements and design standards of all City Departments must be satisfied, except as modified herein.

Public Works

23. Coordinate with the Collection Systems Planning Section of the Department of Public Works to determine the appropriate connection/outfall point for the increased wastewater flow prior to the submittal of any construction drawings or a Tentative Map, whichever may occur first.
24. Contact the City Engineer's Office at 229-6272 to coordinate the development of this project with the Downtown Bus Rapid Transit Connector project, the Union Park project and any other public improvement projects adjacent to this site. Comply with the recommendations of the City Engineer.
25. An update to the previously approved Drainage Plan and Technical Drainage Study must be submitted to and approved by the Department of Public Works prior to the issuance of any grading or building permits, submittal of any construction drawings or the submittal of a Final Map for this site, whichever may occur first. Provide and improve all drainageways as recommended in the approved drainage plan/study.
26. Civil improvement plans for this site shall be coordinated with the final approved Union Park Phase II civil improvement plans.
27. Site development to comply with all applicable conditions of approval for SDR-16267 and all other applicable site-related actions.

Sincerely,



Lean Coleman
Deputy City Clerk II for
Beverly K. Bridges, CMC, City Clerk

cc: See Attached List

Dr. Doug Selby
SDR-25059 – Page Five
February 8, 2008

cc: Planning and Development Dept.
Development Coordination-DPW
Dept. of Fire Services

Ms. Carla Romero
Heritage – Nevada VIII, LLC
421 North Beverly Drive, Suite #350
Beverly Hills, California 90210

Mr. Ben Doyle
Aviation Management Associates
1101 King Street, Suite #325
Alexandria, Virginia 22314

Report Date 02/08/2010 02:10 PM

Submitted By

Page 1

A/P # 37340 EXTENSION OF TIME

Application Information

Stages

	Date / Time	By		Date / Time	By
Processed	02/04/2010 10:31	984727	Temp CDO		
Approved			COO Issued		
Final			Expires		

Associated Information

Type of Work	# Plans	0	Declared Valuation	0.00
Dept of Commerce	# Plans	0	Calculated Valuation	0.00
Priority	☒ Auto Reviews	Bill Group	Actual Valuation	0.00

Description of Work

EOT-37340 - EXTENSION OF TIME - SITE DEVELOPMENT PLAN REVIEW - APPLICANT: HERITAGE-NEVADA VIII, LLC - OWNER: CITY PARKWAY V, INC. - Request for an Extension of Time of a previously approved Site Development Plan Review (SDR-25059) FOR A PROPOSED 57-STORY MIXED-USE DEVELOPMENT INCLUDING 1.12 MILLION SQUARE FEET OF COMMERCIAL SPACE AND 98 MULTI-FAMILY RESIDENTIAL UNITS WITH WAIVERS OF THE UNION PARK STREETSCAPE STANDARDS, BUILDING PLACEMENT AND FRONTAGE REQUIREMENTS, ARCHITECTURAL STANDARDS AND ACCESS STANDARDS on a portion of 53.6 acres at the southwest corner of Grand Central Parkway and City Parkway (APN 139-34-110-007), PD (Planned Development) Zone, Ward 5 (Barlow).

Parent A/P # 25059
Project # 37340 Project/Phase Name WORLD JEWELRY CENTER Phase #
Size/Area 5.84 ACRE Size Description Subdivision Code
Proposed Start Proposed Stop % Completed 0.00
% Complete Formula

Property/Site Information

Parcel 13934110007

Location

Owner/Tenant

Contact ID AC1301955 Name CITY PARKWAY V INC
Mailing Address 400 STEWART AVE 9TH FLOOR Organization % CITY OF LV
City LAS VEGAS State/Province NV
ZIP/PC 89101-2913 Country ☐ Foreign
Day Phone (702)229-6501 x Evening Phone
Fax (702)388-1807 Mobile #

A/P Linked Addresses

No Addresses are linked to this Application

Linked Addresses

No Addresses are linked to this Application

A/P Addresses

No Other Addresses are associated to this Application

Linked Parcels

No Parcels are linked to this Application

A/P Linked Parcels

13934110007

Report Date 02/08/2010 02:10 PM

Submitted By

Page 2

Applicants/Contacts

Primary N Capacity OWNER Contact ID AC1301955 ☐ Foreign
Effective
Name CITY PARKWAY V INC
Day Phone (702)229-6501 x Eve Phone Organization % CITY OF LV
Pager PIN # Position % CITY ATTORNEYS OFFICE
Fax (702)388-1807 Mobile Profession
E-Mail
Address 400 STEWART AVE 9TH FLOOR
LAS VEGAS, NV 89101-2913
Seasonal Addr

Valid From To
Comments No Comments

Primary Y Capacity APPL Contact ID AC986753 ☐ Foreign
Effective
Name HERITAGE-NEVADA VII L L C
Day Phone (310)888-1882 x Eve Phone Organization % PROBITY INTL CORP
Pager PIN # Position
Fax Mobile Profession
E-Mail
Address 421 N BEVERLY DR #350
BEVERLY HILLS, CA 90210-4640
Seasonal Addr

Valid From To
Comments No Comments

Contractors

No Contractors

Project # A/P Type Status Stage Relation

No children exist for this project

Planning Condition Description Effective Expire Comments

There is no planning condition for this project.

EXTENSION OF TIME

Y Will this go to the City Council? Final City Council letter received
Y Will this go DIRECTLY to City Council? Annotated minutes received

Parent Application Type SDR

Hearing Type

Parent Project # 25059

Public, Non-Public or Admin? NON-PUBLIC

Staff Recommendation

Meeting Information

Report Date 02/08/2010 02:10 PM

Submitted By

Page 3

Meeting Grid Meeting Date Comments Added By	Meeting Type Add Date	Meeting Status Modified by	Modified Date	YES Votes	NO Votes	ABSTENTIONS
--	--------------------------	-------------------------------	---------------	-----------	----------	-------------

03/17/2010	CC	SCHEDULED		0	0	0
RGUMARANG	02/04/2010	RGUMARANG	02/04/2010			

Template Type	A/P.#	A/P Type	Status	Stage
---------------	-------	----------	--------	-------

No children exist for this project

Employee Employee ID	Last	First	MI	Comments
984478	SULLIVAN	DEBORAH	J	Planning x6895

Log Action Comments	Description	Entered By	Start	Stop	Hours
---------------------------	-------------	------------	-------	------	-------

PAYMNT	CO NAME WHO PICKED UP CONTACT#	970040	02/04/2010 10:48		0.00
TOM BURKART, 310.888.1882, HERITAGE-NEVADA VIII, LLC CK 1087					

PLANNING & DEVELOPMENT DEPARTMENT

APPLICATION / PETITION FORM

Application/Petition For: Extension of Time re-SDR-25059
 Project Address (Location) Southwest Corner Grand Central Parkway & Parkway
 Project Name World Jewelry Center Proposed Use Mixed Use
 Assessor's Parcel #(s) 139-34-110-007 Ward # 5
 General Plan: existing MXU proposed N/A Zoning: existing PD proposed N/A
 Commercial Square Footage 2.3 Million Floor Area Ratio N/A
 Gross Acres 5.84 Acres Lots/Units 98 Density N/A
 Additional Information _____

PROPERTY OWNER City Parkway V, Inc. Contact Elizabeth N. Fretwell
 Address 400 Stewart Avenue, 8th Floor Phone: (702) 229-6501 Fax: (702) 388-1807
 City Las Vegas State NV Zip 89101
 E-mail Address _____

APPLICANT Heritage-Nevada VIII, LLC Contact Robert Zarnegin
 Address 421 N. Beverly Drive, Suite 350 Phone: (310) 888-1882 Fax: (310) 888-8838
 City Beverly Hills State CA Zip 90210
 E-mail Address rzarnegin@probitryinternational.com

REPRESENTATIVE _____ Contact _____
 Address _____ Phone: _____ Fax: _____
 City _____ State _____ Zip _____
 E-mail Address _____

FOR DEPARTMENT USE ONLY

Property Owner Signature* Elizabeth N. Fretwell

* An authorized agent may sign in lieu of the property owner for Final Maps, Tentative Maps, and Parcel Maps.


Print Name Elizabeth N. Fretwell

Subscribed and sworn before me

This 3 day of February, 20 10

Kim Barrera

Notary Public in and for said County and State



Case #	<u>EOT - 37340</u>
Meeting Date:	<u>3/17/10</u>
Total Fee:	<u>\$ 300</u>
Date Received:*	<u>2/4/10</u>
Received By:	<u>Romeo</u>

*The application will not be deemed complete until the submitted materials have been reviewed by the Planning and Development Department for consistency with applicable sections of the Zoning Ordinance.


RECEIVED BY
BUSINESS DEVELOPMENT

2010 FEB -1 A 11: 04

January 27, 2010

Planning and Development Department
City of Las Vegas
731 South Fourth Street
Las Vegas, NV 89101

Re: World Jewelry Center
Extension of SRD-25059 and SUP-25060



Gentlemen:

The attached application package is for the World Jewelry Center, to be built on Parcel E, a 5.84 acre parcel at the North end of Symphony Park.

At a regular meeting held on February 6, 2008, the City Council approved SDR-25059 and SUP-25060, subject to the conditions listed in the approval letters, enclosed herewith.

The Project was found to be consistent with The City and Mayor Goodman's vision for the future of Union Park, as an Urban District in the Heart of Las Vegas, providing varied services to the Community and added revenue to The City.

World Jewelry Center will become a hub for the worldwide jewelry business anchored by domestic and international jewelry market leaders and a Mecca for jewelry buyers.

World Jewelry Center consists of three buildings -- Office/Residential Condo Tower, Retail Center and a Parking Structure.

Office/Residential Tower

The Tower consists of a basement and 54 floors above ground. Because of the open atrium Entry Lobby and the relation ship to the Parking Structure, the Tower floor numbering jumps from 3 to 7 (with floors 4, 5 and 6 missing) and floors 53 and 54 as Mechanical Floors. So the actual number of habitable floors is 49. Out of these, ten are Residential.

Commercial Floors:

Basement: Includes a designated Foreign Trade Zone area, Mail Room and various other services.
Floors 1 through 3: Include the Main Entry Lobby to the Tower, a Bank, Restaurants and the Building Management offices.

EOT-37340
03/1710 CC

Floors 7 through 42: Include Commercial Office Condos, Grading Labs, Private Club and a Conference Floor.
For a break down of the different uses by sq ft, please refer to the attached Shared Parking Study.

Residential Floors:

Floors 43 through 52: Include the Residential Common spaces and 98 Residential Condos. For break down of unit types, please refer to the attached Shared Parking Study.

The Gross Area of the Tower's habitable areas (office condos, residential condos, bank, conference center, private club...etc) is 1,350,000 Sq Ft.

Retail Center

The Retail Center consists of a basement and the floors above ground. It includes Retail Stores, a Museum with its Café and Store, a Food Court, Restaurants and a Health club/Spa.
For a break down of the different uses by sq ft, please refer to the attached Shared Parking Study.

The Gross Area of the Retail Center (stores, museum, restaurants, food court...etc) is 225,000 Sq Ft.


Parking Structure


The Parking Structure consists of one below and ten above grade levels.
The parking structure, the retail basement and the Tower basement will provide enough parking for the Project with a surplus.
The World Jewelry Center will self-park without the need for additional outside parking.
Please refer to the attached Shared Parking Study.

Due to current economic conditions, we sought an extension of time to acquire the property and commence development. This extension was granted by entering into an Amended and Restated Disposition and Development Agreement, effective as of August 19, 2009. At this time, we are seeking the extension of the existing entitlements (SDR-25059 and SUP-25060) as well. Thank you for your consideration

Sincerely,

HERITAGE-NEVADA VIII, LLC

By: 
Daniel E. Parks
Chief Financial Officer





PLANNING & DEVELOPMENT DEPARTMENT

STATEMENT OF FINANCIAL INTEREST

Case Number: **EOT-37340** APN: 139-34-110-007

Name of Property Owner: City Parkway V, Inc.

Name of Applicant: Heritage-Nevada VIII, LLC

Name of Representative: _____

To the best of your knowledge, does the Mayor or any member of the City Council or Planning Commission have any financial interest in this or any other property with the property owner, applicant, the property owner or applicant's general or limited partners, or an officer of their corporation or limited liability company?

☐ Yes

☒ No

If yes, please indicate the member of the City Council or Planning Commission who is involved and list the name(s) of the person or persons with whom the City Official holds an interest. Also list the Assessor's Parcel Number if the property in which the interest is held is different from the case parcel.

City Official: _____

Partner(s): _____

APN: _____

Signature of Property Owner: Elizabeth N. Pretwell


Print Name: Elizabeth N. Pretwell

Subscribed and sworn before me

This 3 day of February, 2010

Kim A. Barrera

Notary Public in and for said County and State



20040429-0001073

Fee: \$8.00 RPTT: EX002
04/29/2004 08:26:45 T20040011029
Req: CITY PARKWAY V INC
Frances Deane
Clark County Recorder Pgs: 5

APN 139-34-110-003

Recorded at the Request of:

City Parkway V, Inc.
400 Las Vegas Boulevard South
Las Vegas, Nevada 89101

5-1

When Recorded, Return to:
Mail tax bills to:

City Attorney's Office
City of Las Vegas
400 Stewart Avenue, 9th Floor
Las Vegas, Nevada 89101

QUITCLAIM DEED

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged, City Parkway IV, Inc., a Nevada non-profit corporation, does hereby REMISE, RELEASE AND QUITCLAIM to the City Parkway V, Inc., a Nevada non-profit corporation, the real property in the City of Las Vegas, County of Clark, State of Nevada, described on Exhibit "A" attached hereto, together with all and singular tenements, hereditaments and appurtenances thereunto belonging or in anywise appertaining.



DATED this 21st day of April, 2004.

CITY PARKWAY IV, INC.

By: Douglas Seby
Douglas Seby, President

Approved as to form:

J. P. Briccillo 4/21/04
Date



71-82


ACKNOWLEDGEMENT

State of Nevada)
) ss.
County of Clark)


On this 21st day of April, 2004, personally appeared before me, a Notary Public in and for said County and State, Douglas Selby, known to me to be the President of City Parkway IV, Inc., and he acknowledged to me that he executed the same for and on behalf of City Parkway IV, Inc. and that he executed the said instrument freely and voluntarily and for the uses and purposes therein mentioned.

WITNESS my hand and official seal.

Ceceli C. Green
NOTARY PUBLIC in and for said County
and State



ASSESSOR'S COPY



THE PURPOSE OF THIS LEGAL DESCRIPTION IS TO DESCRIBE A PARCEL OF LAND BEING SUBDIVIDED OUT OF LOT 5 OF PARKWAY CENTER AS RECORDED IN BOOK 53, PAGE 61 OF PLATS.

BEING A PORTION OF SAID LOT 5, SAME BEING A PORTION OF THE WEST HALF (W1/2) OF SECTION 34 AND THE EAST HALF (E1/2) OF SECTION 33, TOWNSHIP 20 SOUTH, RANGE 61 EAST, M.D.M., CITY OF LAS VEGAS, CLARK COUNTY, NEVADA, AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:


BEGINNING at the southeast corner of said lot 5, being on the north line of Bonneville Avenue (100 foot right-of-way), same being on the west line of the Union Pacific Railroad right-of-way (100 foot wide);

THENCE, along the north line of said Bonneville Avenue the following four(4) courses and distances:

1. North $62^{\circ}04'12''$ West, a distance of 204.98 feet to a point of curvature to the left;
2. With said curve to the left, concave southerly, having a radius of 550.00 feet, a central angle of $36^{\circ}45'51''$, and along the arc 352.91 feet to a point of tangency;
3. South $81^{\circ}09'57''$ West, a distance of 485.41 feet to a point of curvature to the right;
4. With said curve to the right, concave northeasterly, having a radius of 55.00 feet, a central angle of $95^{\circ}00'00''$, and along the arc 91.19 feet to a point of tangency on the east line of Grand Central Parkway (100 foot right-of-way);

THENCE, along the east, southeasterly, and southerly line of said Grand Central Parkway the following ten (10) courses and distances:

1. North $03^{\circ}50'03''$ West, a distance of 94.71 feet to a point of curvature to the right;
2. With said curve to the right, concave easterly, having a radius of 450.00 feet, a central angle of $31^{\circ}45'19''$, and along the arc 249.41 feet to a point of tangency;
3. North $27^{\circ}55'16''$ East, a distance of 1058.21 feet to a point of curvature to the right;
4. With said curve to the right, concave southeasterly, having a radius of 450.00 feet, a central angle of $20^{\circ}42'14''$, and along the arc 162.61 feet to a point of tangency;
5. North $48^{\circ}37'30''$ East, a distance of 1217.02 feet to a point of curvature to the right;
6. With said curve to the right, concave southeasterly, having a radius of 450.00 feet, a central angle of $25^{\circ}40'39''$, and along the arc 201.67 feet to a point of tangency;
7. North $74^{\circ}18'09''$ East, a distance of 331.32 feet to a point of curvature to the right;





8. With said curve to the right, concave southerly, having a radius of 350.00 feet, a central angle of $43^{\circ}37'41''$, and along the arc 266.51 feet to a point of non-tangency from which a radial line bears South $27^{\circ}55'50''$ West;
9. South $27^{\circ}55'50''$ West, a distance of 5.00 feet to an interior angle point;
10. South $62^{\circ}04'10''$ East, a distance of 68.80 feet to a point on said west line of the Union Pacific Railroad;

THENCE, along said west line South $27^{\circ}55'16''$ West, a distance of 741.16 feet to a point of non-tangent curvature to the left from which a radial line bears South $31^{\circ}53'35''$ East; THENCE, leaving said west line and crossing a portion of said lot 5, from a tangent bearing South $58^{\circ}06'25''$ West, with said curve to the left, concave southeasterly, having a radius of 1510.00 feet, a central angle of $30^{\circ}11'04''$, and along the arc 795.50 feet to a point of tangency;

THENCE, South $27^{\circ}55'21''$ West, a distance of 150.00 feet to a point of curvature to the left;

THENCE, with said curve to the left, concave easterly, having a radius of 1510.00 feet, a central angle of $30^{\circ}11'15''$, and along the arc 795.57 feet to a point of non-tangency from which a radial line bears North $87^{\circ}44'06''$ East, same point being on said west line of the Union Pacific Railroad;

THENCE, with said west line, South $27^{\circ}55'16''$ West, a distance of 365.64 feet to the POINT OF BEGINNING, containing 56.03 acres of land.



1700 1000 1000 1000

22

STATE OF NEVADA
DECLARATION OF VALUE

1. Assessor Parcel Number(s)

a) 139-34-110-003
b) _____
c) _____
d) _____

2. Type of Property:

a) ☒ Vacant Land b) ☐ Single Fam. Res.
c) ☐ Condo/Twnhse d) ☐ 2-4 Plex
e) ☐ Apt. Bldg f) ☐ Comm'l/Ind'l
g) ☐ Agricultural h) ☐ Mobile Home
i) ☐ Other

3. Total Value/Sales Price of Property

Deed in Lieu of Foreclosure Only (value of property)

Transfer Tax Value:

Real Property Transfer Tax Due

\$ 10.2
(_____)
\$ _____
\$ _____

FOR RECORDERS OPTIONAL USE ONLY

Document/Instrument #: _____
Book _____ Page: _____
Date of Recording: _____
Notes: _____

4. If Exemption Claimed:

a. Transfer Tax Exemption per NRS 375.090, Section 02

b. Explain Reason for Exemption: GOVERNMENT entity

5. Partial Interest: Percentage being transferred: _____ %

The undersigned declares and acknowledges, under penalty of perjury, pursuant to NRS 375.060 and NRS 375.110, that the information provided is correct to the best of their information and belief, and can be supported by documentation if called upon to substantiate the information provided herein. Furthermore, the disallowance of any claimed exemption, or other determination of additional tax due, may result in a penalty of 10% of the tax due plus interest at 1% per month. Pursuant to NRS 375.030, the Buyer and Seller shall be jointly and severally liable for any additional amount owed.

Signature _____

Capacity Manager, Real Estate

Signature _____

Capacity _____

SELLER (GRANTOR) INFORMATION
(REQUIRED)

Print Name: City Parkway IV, Inc.
Address: 400 Stewart
City: Las Vegas
State: NV Zip: 89101

BUYER (GRANTEE) INFORMATION
(REQUIRED)

Print Name: City Parkway V, Inc.
Address: 400 Stewart
City: Las Vegas
State: NV Zip: 89101

COMPANY/PERSON REQUESTING RECORDING (required if not seller or buyer)

Print Name: _____

Escrow # _____


Address: _____

City: _____

State: _____

Zip: _____

(AS A PUBLIC RECORD THIS FORM MAY BE RECORDED)



WORLD JEWELRY CENTER



PLANNING & DEVELOPMENT DEPARTMENT SUBMITTAL
OCTOBER 9, 2007


APA # 25034



PRIORITY INTERNATIONAL CORPORATION

421 N. Beverly Drive, Suite 350
Beverly Hills, California 90210
310.888.1.888 voice
310.888.8838 fax

WORLD
JEWELRY
CENTER




EOT-37340
03/1710 CC

ALIGNED FOR THE
CITY OF LAS VEGAS


421 South Main Street, 10th Floor
Las Vegas, NV 89101
Tel: 702.228.1000 Fax: 702.228.1001
Web: www.cityoflasvegas.com
© 2007 Priority International Corporation

100-443887-100

SCALE: N.T.S.



PROJECT LOCATION



VACANT (ZONED PD)

VACANT (ZONED PD)

VACANT (ZONED PD)

VACANT (ZONED PD)


VACANT
(ZONED PD)

WEST CARSON AVENUE

GRAND CENTRAL PARKWAY

FEB - 4 2010

RECEIVED



SIGNAGE LOCATION PLAN


October 09, 2007

1.2

APA # 25034



WORLD JEWELRY CENTER



LA TOON...PORTER ARCHITECTS

2015-11-03

398-A135

October 9, 2007

Nabil Albert, RA
Director, Development and Construction
Probitly International Corporation
421 North Beverly Drive, Suite 350
Beverly Hills, CA 90210

Subject: World Jewelry Center Shared Parking Study

Dear Mr. Albert:

G. C. Wallace (GCW) has updated the shared parking study summarized in a letter dated August 13, 2007. The new analysis accounts for an increase in office, retail, and residential land use.

The subject Project is now planned to incorporate the following land use square footages:

- Office – 906,481 SF Gross Floor Area, which is an increase of 7,643 SF compared to the previous analysis (809,667 SF Gross Floor Area minus elevator shafts, stairwells, and floor area containing mechanical, electrical, communications, and security equipment, an increase of 9,879 SF compared to the previous analysis)
- Retail – 112,481 SF (GFA), an increase of 6,468 SF compared to the previous analysis (100,500 SF Gross Leasable Area (GLA), an increase of 8,274 SF compared to the previous analysis)
- Food Court – 8,831 SF a decrease of 1,247 SF compared to the previous analysis (6,473 SF public seating and 2,158 SF service area) (GLA)
- Museum Cafe – 5,875 SF a decrease of 3,009 SF compared to the previous analysis (4,406 SF public seating and 1,469 SF service area) (GLA)
- Casual Dining Restaurant – 10,701 SF an increase of 712 SF compared to the previous analysis (8,026 SF public area and 2,675 SF service area) (GLA)
- Health Club – 23,879 SF (GFA) the same when compared to the previous analysis (20,919 SF Gross Floor Area minus elevator shafts, stairwells, and floor area containing mechanical, electrical, communications, and security equipment, the same when compared to the previous analysis)
- Museum – 24,802 (GFA), a decrease of 244 SF compared to the previous analysis
- Bank – 19,930 (GFA), an increase of 1,051 SF over the previous analysis
- Residential Condos (studio & 1 Bedroom) – 21 Units, an increase of 9 units compared to the previous analysis.
- Residential Condos (2 Bedroom) – 72 units, a decrease of 1 unit compared to the previous analysis.
- Residential Condos (3 Bedroom) – 5 units, the same when compared to the previous analysis.
- Raw Bar – 2,094 SF a decrease of 1,001 SF compared to the previous analysis (1,880 SF public seating and 214 SF service area) (GLA)
- Tower Restaurant – 11,145 SF an increase of 638 SF compared to the previous analysis (7,609 SF public seating and 2,536 SF service area) (GLA)

1555 South Rainbow Boulevard • Las Vegas, NV 89146 • T: 702.804.2000 • F: 702.804.2299 • gwallace.com



G. C. WALLACE INC.
111 WALLACE OF CALIFORNIA, INC.
G. C. WALLACE HOLDINGS, INC.

World Center Information
702.804.2184

Probitly International Corporation
October 9, 2007
Page 2

398-A135

The starting point of a shared parking analysis is the calculation of unadjusted parking demand based on individual base parking ratios. Unadjusted demand has been calculated based on ratios recommended in *Shared Parking, 2nd Edition* published by the Urban Land Institute (ULI). The base ratio for office use, which is approximately 28% less than the CLV Code requirement, is based on the average rate reported in *Parking Generation 3rd Edition* for office use in an urban area. The rate recommended in *Parking Generation 3rd Edition* reflects the urban characteristic of Union Park, while the CLV Code does not differentiate between urban or suburban areas.

It should be noted that the *Shared Parking, 2nd Edition* notes that regardless of the methodology used, GFA should exclude vehicle-parking areas, and floor areas occupied by mechanical, electrical, communications and security equipment. Additionally, elevator shafts, stairwells and atrium areas were excluded for the *Shared Parking 2nd Edition* ratios calculation, due to the fact these are either non-floor areas (Atrium) or common areas (Elevator shafts and stairwells) and are not purchased by the individual office tenants.

If land uses were taken individually, without the benefit of shared parking adjustments, parking requirements would total 4,397 based on CLV Code requirement and 3,315 spaces based on recommended *Shared Parking 2nd Edition* ratios. Parking requirement calculations without adjustments for shared parking analyses are summarized and included as Table 1.

It should be noted, only weekday demands were analyzed as it was assumed that much of the office component, accounting for over 80% of the proposed onsite land use, would not be operating on the weekend, and would therefore not be critical to the estimation of the peak parking demand.

Because the proposed Project is a mixed-use development, it is reasonable to assume that, as a whole, it will demand fewer parking spaces than predicted by the summation of each individual land use. This is the direct result of varying peak parking demand hours for different land uses and captive market reductions, which is a concept readily recognized in the Institute of Transportation Engineers (ITE) *Parking Generation Manual* and *Shared Parking 2nd Edition*. As a result, a shared parking analysis is applicable, especially when considering uninterrupted pedestrian connections between proposed land uses.

As stated, the values reported in Table 1 represent the unadjusted individual land use parking requirements that compose the Project. Using the total demands outlined in Table 1, the anticipated operating times for each land use, and the historical hourly parking accumulation distribution data presented on pages 18 through 19 of the Urban Land Institute (ULI) *Shared Parking 2nd Edition*, shared parking demands for each weekday hour can be calculated. Tables 2, 3 and 4 depict total parking demands by hour of day and land use type for a typical weekday. As shown in Table 3 and 4, the peak hour demands occur from 2:00 PM to 3:00 PM at 4,243 for CLV Code requirements and 3,135 spaces for Shared Parking ratios.

As outlined in the ULI *Shared Parking 2nd Edition*, past experience and studies indicate customer-parking needs at mixed-use sites are further reduced due to the patronage of multiple onsite land uses. Patrons utilizing multiple onsite land uses are termed "captive market" per *Shared Parking 2nd Edition*. An example of a "captive market" could be the following scenario: A person working in the office land use eats lunch at the onsite restaurant and shops at one of the retail sites. This person will not require additional parking demand since one parking spot is accommodating three different unique land uses. With this concept in mind, parking demands were further reduced for the restaurant and retail sites as summarized in Table 4.


As shown in Table 4, the retail and casual dining land use demands have been reduced by 18% based on typical captive market reductions taken in the various case study analyses compiled in the

SEE PAGE THREE OF THREE ON SHEET 1.4

APA # 25034

PROBITLY INTERNATIONAL CORPORATION
421 N. Beverly Drive, Suite 350
Beverly Hills, California 90210
310.889.1882 ext. 4
310.889.8836 fax

SITE PLAN



OCTOBER 9, 2007 1.3

ALUMINUM ARCHITECTURE
ARCHITECTS
141 South Power Street, 10th Floor
Las Vegas, NV 89101
Tel: (702) 399-1111 Fax: (702) 399-1101
Web: www.aluminumarchitect.com
© 2007 Aluma - Probitly International LLP

Shared Parking 2nd Edition. We believe this factor is very conservative, and that it could easily be much higher, particularly in the context of the whole Union Park site.

A captive market reduction of 67% has been assumed for the museum. We understand the majority of museum visitors are expected to be retail patrons who are interested in how gems are mined and cut, and brought to market. Relatively few primary trips to the museum are expected.

A captive market reduction of 85% has been assumed for the food court and museum café. These uses are amenities to other Project uses, and the only primary vehicular trips to them are likely to be employees.

A captive market reduction of 94% and 85% has been assumed for the Health Club and Bank, respectively. It is understood that these amenities will be for office tenants only not for the general public. Therefore, it is anticipated that the only primary vehicular demands will be from employees.

The final calculated parking demand after shared parking savings are accounted for is 3,852 based on CLV Code requirements and 2,720 spaces based on recommended Shared Parking ratios.

It should be noted that further parking demand reductions could be realized, depending on the proportion of transit and taxi trips to and from the Union Park development.

The current site plan provides 2,778 parking spaces (previously 2,711 parking spaces). This resulting in a shortfall of 1,074 spaces (previously a shortfall of 1,078 spaces) based on CLV Code Requirements and a surplus of 58 spaces (previously a surplus of 57 spaces) based on recommended Shared Parking ratios for the weekday peak hour. The utilization of common parking areas provided by the Union Park development could augment the proposed parking supply.

Very truly yours,
G. C. WYLLACE, INC.

Patrick S. Byrd, P.E., P.T.O.E.
Traffic Engineer

cc: Attach.

cc: Gary Dempster, Alton Porter Architects
John Tobin, GCW



SEE PAGES ONE AND TWO ON SHEET 1.3



Table 6. Captive Market Adjustment

	Parking Demand per CLV Ratios			Parking Demand per Shared Parking Ratios		
	Unadjusted Demand (2:00 PM)	Non Captive	Adjusted Demand	Unadjusted Demand (2:00 PM)	Non Captive	Adjusted Demand
Office	3,029	100%	3,029	1,842	100%	1,842
General Retail	428	90%	385	348	90%	313
Food Court	92	15%	14	102	15%	15
Museum Café	63	15%	9	70	15%	11
Tower Rest.	108	90%	97	121	90%	108
Raw Bar	26	15%	4	25	15%	4
Restaurant	114	90%	102	127	90%	114
Museum	83	33%	27	83	33%	27
Condo	179	100%	179	179	100%	179
Health Club	84	6%	5	103	6%	6
Bank	39	6%	2	36	6%	2
Total	4,121		3,882	3,136		2,720

NOTE:
TOTAL STANDARD SPACES = 2,716
TOTAL COMPACT SPACES = 0
TOTAL HANDICAP SPACES = 63



D FREE-STANDING VEHICULAR DIRECTIONAL SIGNS - PER UNION PARK DESIGN STANDARDS



PROPOSED 75° TOWER PARKING


SITE PLAN

OCTOBER 9, 2007 1.4


APA # 25034

PROPERTY SYSTEMS/ARCHITECTURAL CONSULTANTS
421 N. Beverly Drive, Suite 202
Beverly Hills, California 90210
310.888.1827 voice
310.888.6838 fax

WORLD JEWELRY CENTER



ALTON PORTER ARCHITECTS
AECOM
444 South Flower Street, 10th Floor
San Diego, CA 92101
Tel: 619.236.2000 Fax: 619.236.1000
Web: www.altonporter.com
© 2007 Alton Porter Architects LLP



APA # 25034

LANDSCAPE PLAN


SCALE: 1" = 30'-0"

OCTOBER 9, 2007


2.1

PROPERTY INTERNATIONAL CORPORATION
421 N. Beverly Drive, Suite 330
Beverly Hills, California 90210
310.858.1857 voice
310.858.8838 fax

WORLD
JEWELRY
CENTER




ALISON J. FOXER
ARCHITECTS
111 South Flower Street, 19th Floor
Los Angeles, CA 90012
Tel: 213.555.1000 Fax: 213.555.1001
E-mail: alfox@ajfoxer.com
© 2007 Alison J. Foxer Architects LLP



EAST

ROOF	100'-0"
TOP OF TOWER	100'-0"
28	98'-0"
27	96'-0"
26	94'-0"
25	92'-0"
24	90'-0"
23	88'-0"
22	86'-0"
21	84'-0"
20	82'-0"
19	80'-0"
18	78'-0"
17	76'-0"
16	74'-0"
15	72'-0"
14	70'-0"
13	68'-0"
12	66'-0"
11	64'-0"
10	62'-0"
9	60'-0"
8	58'-0"
7	56'-0"
6	54'-0"
5	52'-0"
4	50'-0"
3	48'-0"
2	46'-0"
1	44'-0"
0	42'-0"
28	100'-0"
27	98'-0"
26	96'-0"
25	94'-0"
24	92'-0"
23	90'-0"
22	88'-0"
21	86'-0"
20	84'-0"
19	82'-0"
18	80'-0"
17	78'-0"
16	76'-0"
15	74'-0"
14	72'-0"
13	70'-0"
12	68'-0"
11	66'-0"
10	64'-0"
9	62'-0"
8	60'-0"
7	58'-0"
6	56'-0"
5	54'-0"
4	52'-0"
3	50'-0"
2	48'-0"
1	46'-0"
0	44'-0"



SOUTH

BUILDING ELEVATIONS


SCALE: 1" = 80'-0"

OCTOBER 9, 2007 3.1


APA # 25034

PROPERTY INTERNATIONAL CORPORATION
 421 N. Beverly Drive, Suite 120
 Beverly Hills, California 90210
 310.256.1862 ext. 6
 310.256.8736 fax

WORLD
 JEWELRY
 CENTER



ALCOA-PORTER
 1440 South Power Street, 4th Floor
 Las Vegas, NV 89102
 Tel: 702.251.1000 Fax: 702.251.1001
 Tel: 702.251.1002 / 1003 / 1004 / 1005
 © 2007 Alcoa-Porter International LLP



A EXPOSED CONCRETE



B "SILVER SMITH" PAINTED, MATTE FINISH METAL PANELS




C 1/4" WARM GRAY GLASS SPANDREL



D 1" BLUE GRAY TINTED CLEAR GLASS



D1 1" BLUE GRAY TINTED TRANSLUCENT GLASS



E BUILDING MOUNTED PROJECT IDENTITY



F PERFORATED CORRUGATED METAL PANELS



G BRUSHED STAINLESS STEEL COLUMN COVERS



H PERFORATED PAINTED METAL PANELS



I LARGE ROCK GABION WALLS

SOUTH



INDICATES PROPOSED SIGN LOCATION-SEE SHEET 1.2

BUILDING ELEVATIONS

SCALE: N.T.S.


OCTOBER 9, 2007 3.3

APA # 25034



PROJECT INTERNATIONAL CORPORATION
421 N. Beverly Drive, Suite 320
Beverly Hills, California 90210
310.888.1882 voice
310.888.8030 fax

WORLD JEWELRY CENTER



ALDO D. PORTER ARCHITECTS
444 South Flower Street, 4th Floor
Los Angeles, CA 90013
Tel: 213.698.1000 Fax: 213.698.1001
Web Site: <http://www.aldoporter.com>
© 2007 Aldon & Porter Architects LLP

11


2

11

11

11

11




A EXPOSED CONCRETE




B "SILVER SMITH" PAINTED, MATTE FINISH METAL PANELS




C 1/4" WARM GRAY GLASS SPANDREL



D 1" BLUE GRAY TINTED CLEAR GLASS



E BUILDING MOUNTED PROJECT IDENTITY



F PERFORATED CORRUGATED METAL PANELS



G BRUSHED STAINLESS STEEL COLUMN COVERS

NORTH


XX

INDICATES PROPOSED SIGN LOCATION- SEE SHEET 1.2

BUILDING ELEVATIONS

SCALE: N.T.S.

WORLD
JEWELRY
CENTER



APA ♦ 25034


PRIORITY INTERNATIONAL CORPORATION
421 N. Beverly Drive, Suite 320
Beverly Hills, California 90210
310 888 1882 voice
310 888 8638 fax




OCTOBER 9, 2007 3.4

**ALDORE-HOPKINS
ARCHITECTS**
441 South Power Street, 4th Floor
San Francisco, CA 94105
Tel: 415.774.8888 Fax: 415.774.8888
Web: www.aladore-hopkins.com
© 2007 Aldore-Hopkins Architects LLP

1
第
一
卷
第
一
期



- 
A EXPOSED CONCRETE
- 
B "SILVER SMITH" PAINTED, MATTE FINISH METAL PANELS
- 
C 1/4" WARM GRAY GLASS SPANDREL
- 
D 1" BLUE GRAY TINTED CLEAR GLASS
- 
E BUILDING MOUNTED PROJECT IDENTITY
- 
F PERFORATED CORRUGATED METAL PANELS
- 
G BRUSHED STAINLESS STEEL COLUMN COVERS

EAST

XX ——— INDICATES PROPOSED SKIN LOCATION- SEE SHEET 1.2

BUILDING ELEVATIONS

SCALE: N.T.S.


REF N

OCTOBER 9, 2007 3.5


APA # 25034






ALDOUS PETERSON ARCHITECTS
 421 N. Beverly Drive, Suite 320
 Beverly Hills, California 90210
 310.888.1882 ext. 4
 310.888.1818 fax

WORLD JEWELRY CENTER




ALDOUS PETERSON ARCHITECTS
 421 North Beverly Blvd., 4th Floor
 Los Angeles, CA 90048
 310.888.1882
 Fax: 310.888.1818
 Web: www.alldesign.com
 © 2007 Aldous Peterson Architects LLP



- | | | | | | | | | | |
|---|---|---------------------------------|-----------------------------------|--|---|---|---|---|---|
|  |  | | | |  |  |  |  |  |
| A EXPOSED CONCRETE | B "SILVER SMITH" PAINTED, MATTE FINISH METAL PANELS | C 1/4" WARM GRAY GLASS SPANDREL | D 1" BLUE GRAY TINTED CLEAR GLASS | D1 1" BLUE GRAY TINTED TRANSLUCENT GLASS | E BUILDING MOUNTED PROJECT IDENTITY | F PERFORATED CORRUGATED METAL PANELS | G BRUSHED STAINLESS STEEL COLUMN COVERS | H PERFORATED PAINTED METAL PANELS | I LARGE ROCK GABION WALLS |

WEST



INDICATES PROPOSED SIGN LOCATION- SEE SHEET 1.2

APA # 25034

BUILDING ELEVATIONS


SCALE: N.T.S.

OCTOBER 9, 2007 3.6



HIERARCHY INTERNATIONAL CORPORATION
421 N. Beverly Drive, Suite 320
Beverly Hills, California 90210
310.206.1882 voice
310.898.8838 fax


WORLD
JEWELRY
CENTER



ALTOON-HORTON
ARCHITECTS

441 South Flower Street, 18th Floor
Los Angeles, CA 90012
Tel: 213.227.1800 Fax: 213.227.1801
Fax: 213.227.1801 / 213.227.1802
© 2007 Alton-Horton LLP





BASEMENT LEVEL COMPOSITE PLAN

FLOOR PLANS

SCALE: 1" = 32'-0"

WORLD
JEWELRY
CENTER



APA # 25034




PEABODY INTERNATIONAL CORPORATION
421 N. Beverly Drive, Suite 350
Beverly Hills, California 90210
312.898.1885 voice
312.898.6836 fax




OCTOBER 9, 2007 4.1

ALFONSO PORTER
ARCHITECTS

141 South Flower Street, 14th Floor
Los Angeles, CA 90012
Tel: 213.233.1000 Fax: 213.233.1000
Web: www.alfonsoporter.com
© 2007 Alfonso Porter Architects LLP





LOBBY LEVEL COMPOSITE PLAN

FLOOR PLANS

SCALE: 1" = 30'-0"

LEGEND
● BUILDING ENTRANCES/ EXITS




APA # 25034

OCTOBER 9, 2007 4.2


PROSITY INTERNATIONAL CORPORATION
421 N. Beverly Drive, Suite 300
Beverly Hills, California 90210
310.886.1182 - voice
310.886.8838 fax

WORLD
JEWELRY
CENTER



ALLOCH-PORTER
ARCHITECTS
441 South Power Street, 4th Floor
Las Vegas, NV 89101
Cell: 702.399.1111
Fax: 702.399.1111
Web: www.alloch-porter.com
© 2007 Alloch-Porter Architects LLP

0165 A - 837



SECOND LEVEL COMPOSITE PLAN

FLOOR PLANS

SCALE: 1" = 30'-0"




OCTOBER 9, 2007 4.3

APA # 25034




PROPERTY INVESTMENT CORPORATION
 171 N. Nevada Ave., Suite 300
 Reno, NV, California 95210
 310.888.1882 voice
 310.888.8878 fax

WORLD
 JEWELRY
 CENTER



ALTON H. FORT
 442 South Pearl Street, 4th Floor
 Reno, NV 95201
 Tel: 310.888.1882 Fax: 310.888.8878
 Web: http://www.altonhfort.com
 © 2007 Alton H. Fort Properties, LLC

LEB - 5013



THIRD LEVEL COMPOSITE PLAN

FLOOR PLANS

SCALE: 1" = 20'-0"




OCTOBER 9, 2007 4.4

APA # 25034




PROPERTY INTERNATIONAL CORPORATION
421 N. Beverly Drive, Suite 330
Beverly Hills, California 90210
310.858.1382 voice
310.858.3838 fax

WORLD
JEWELRY
CENTER



ALCOO PAPER
411 South Flower Street, 10th Floor
Los Angeles, CA 90012
Tel: 213.441.1000 Fax: 213.441.1001
Web: www.alcoo.com
© 2007 Alcoa Paper Company


5-1-59



POOL DECK LEVEL 10 COMPOSITE PLAN

FLOOR PLANS

WORLD
JEWELRY
CENTER



LEGEND

● BUILDING ENTRANCES/ EXITS



OCTOBER 9, 2007 4.5


APA # 25034

PROSITY INTERNATIONAL CORPORATION
421 N. Beverly Drive, Suite 330
Beverly Hills, California 90210
310.888.1887 voice
310.888.8838 fax

ALISON H. PORTER
ARCHITECT
111 South Flower Street, 4th Floor
Los Angeles
California 90012
Tel: 213.521.1000 Fax: 213.521.1001
Web: www.alisonporter.com
© 2007 Alison H. Porter Architects LLP


১৯৭৭

১৯৭৭




RESIDENTIAL PLAN


PLEASE SEE SHEET 4.7 FOR PROPOSED INTERIOR CONDO LAYOUTS



MID RISE OFFICE PLAN



HIGH RISE OFFICE PLAN



LOW RISE OFFICE PLAN

TYPICAL TOWER FLOOR PLANS

FLOOR PLANS

SCALE: 1" = 30'-0"



OCTOBER 9, 2007 4.6


APA # 25034



Hensley Hensley & Associates, Corporation

421 N. Beverly Drive, Suite 330
Beverly Hills, California 90210
310.886.1882 voice
310.886.8038 fax


WORLD
JEWELRY
CENTER



ALTON H. C. P. A. R.
ARCHITECTS

444 South Flower Street, 4th Floor
Los Angeles, CA 90013
Office: 213.621.1000
Fax: 213.621.1001
Web: www.altonhensley.com
© 2007 Alton Hensley & Associates, LLP

100



APA # 25034

PROPOSED RESIDENTIAL INTERIOR LAYOUT
FLOOR PLANS


SCALE: N.T.S.



OCTOBER 9, 2007 4.7


HOOPER INTERNATIONAL ASSOCIATES
421 N. Beverly Drive, Suite 300
Beverly Hills, California 90210
310.889.1882 voice
310.889.8936 fax

WORLD
JEWELRY
CENTER



ALTON H. PETERSON ARCHITECTS
111 South River Street, 8th Floor
Las Vegas, NV 89101
Tel: 702.251.8800 Fax: 702.251.8801
Web: www.altonhpeterson.com
© 2007 Alton H. Peterson Architects, LLP

1990



ROOF PLAN
FLOOR PLANS

SCALE: 1" = 30'




OCTOBER 9, 2007 4.8

APA # 25034





city of las vegas
4711 W. Beverly Drive, Suite 320
Beverly Hills, California 90210
310.888.1882 voice
310.888.9838 fax

WORLD
JEWELRY
CENTER



ALTON & ASSOCIATES
ARCHITECTS
101 South Power Street, Suite 100
Las Vegas, NV 89101
Tel: 702.585.1882 Fax: 702.585.1883
Web: www.alton.com
© 2007 Alton & Associates, LLP

222




October 11, 2007 6.5


CURB STUDY SECTION & RENDERINGS

APA # 25034


ALL RIGHTS RESERVED
 422 South Power Road, Suite 100
 Las Vegas, NV 89102
 Tel: 702.735.1111
 Fax: 702.735.1112
 www.apa.com




ARCHITECTURAL CONSULTANTS
 422 N. Lake Street, Suite 100
 Las Vegas, NV 89101
 702.735.1111
 702.735.1112




SECTION- R3, SOUTH



SECTION- R8, SOUTH



SECTION- R13, SOUTH



SECTION- RB, WEST


SCALE: 1/8" = 1'-0"

October 11, 2007 7.9


APA # 25034

PRIMITY INTERNATIONAL CORPORATION
421 N. Beverly Drive, Suite 350
Beverly Hills, California 90210
310.889.1857 voice
310.889.8538 fax

WORLD
JEWELRY
CENTER



ALSO REPORTED
144 South Power Street, 4th Floor
Las Vegas, NV 89101
Tel: 702.441.2000 Fax: 702.441.2001
Web: www.lasvegasplanning.com
© 2007 City of Las Vegas Planning & Development






APA # 25034

RETAIL PROMENADE RENDERINGS

October 11, 2007 7.10

PRIORITY INTERNATIONAL CORPORATION
 421 N. Beverly Drive, Suite 350
 Beverly Hills, California 90210
 310.886.1882 voice
 310.886.8538 fax

**WORLD
 JEWELRY
 CENTER**



ATTACHED DISCLOSURE
 111 South Flower Street, 10th Floor
 Los Angeles, CA 90012
 Tel: 213.288.5000 Fax: 213.288.5001
 E-mail: info@worldjewelrycenter.com
 © 2007 World Jewelry Center, LLC