

AGENDA MEMO

CITY COUNCIL MEETING DATE: December 2, 2009

DEPARTMENT: Public Works

ITEM DESCRIPTION: Bid No. 09.1762-LED, Federal Project Numbers ARRA-003(119); ARRA-003(120); ARRA-003(121) and ARRA-003(122), 2009 Asphalt Overlay

The work will consist of removal and replacement of asphalt pavement, asphaltic concrete pavement patches, median islands, removal and replacement of concrete sidewalks, removal and replacement of concrete curb and gutter, installation of tactile warning panels, installing new traffic delineations, markings, and symbols and installing traffic loop detectors. The work includes traffic signs and markings, adjusting utility covers to grade with concrete collars, dense grade asphalt patching, cold milling and 1" thick ultra thin asphaltic concrete surface (UTACS) S3 gradation.