



January 23, 2006

LAS VEGAS CITY COUNCIL

OSCAR B. GOODMAN
MAYOR

GARY REESE
MAYOR PRO TEM

LARRY BROWN
LAWRENCE WEEKLY
STEVE WOLFSON
LOIS TARKANIAN
STEVEN D. ROSS

DOUGLAS A. SELBY
CITY MANAGER

Mr. Herb Sider
PO Box 28887
Las Vegas, Nevada 89126

RE: SDR-10143 – SITE DEVELOPMENT PLAN REVIEW
CITY COUNCIL MEETING OF JANUARY 18, 2006

Dear Mr. Sider:

The City Council at a regular meeting held January 18, 2006 APPROVED the request for a Site Development Plan Review FOR A 68-STORY MIXED-USE DEVELOPMENT CONSISTING OF 1,011 RESIDENTIAL UNITS AND 9,260 SQUARE FEET OF RETAIL SPACE; AND WAIVERS OF THE DOWNTOWN STREETSCAPE STANDARDS, BUILD-TO-LINE STANDARDS AND STEPBACK STANDARDS on 1.30 acres at 1209 South Third Street (APN 162-03-110-005 through 010), R-4 (High Density Residential) Zone. The Notice of Final Action was filed with the Las Vegas City Clerk on January 19, 2006. This approval is subject to:

Planning and Development

1. This Site Development Plan Review shall expire two years from the date of final approval, unless it is exercised or an Extension of Time is granted by City Council.
2. The parking structure elevations shall be reviewed and approved by the Planning and Development Department staff, prior to the time application is made for a building permit, to ensure that there is adequate façade articulation and visual interest where smooth stucco and woven metal fabric panels over cmu substrate is called out on all building elevations.
3. The proposed water feature shall be subject to Title 14.11.190 Potable or non-potable water utilization.
4. All proposed walls shall be consistent with Title 19 Wall requirements.
5. This Site Development Plan Review shall expire two years from date of final approval unless it is exercised or an Extension of Time is granted by the City of Las Vegas.

CITY OF LAS VEGAS
400 STEWART AVENUE
LAS VEGAS, NEVADA 89101

VOICE 702.229.6011
TTY 702.386.9108

www.lasvegasnevada.gov

18112-001-06-05
CLV 7009

EOT-36746

01-06-10 CC

RECEIVED

NOV 19 2009

Mr. Herb Sider
SDR-10143 - Page Three
January 23, 2006

17. Prior to the submittal of a building permit, the applicant shall meet with Planning and Development Department staff to develop a comprehensive address plan for the subject site. A copy of the approved address plan shall be submitted with any future building permit applications related to the site.
18. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.
19. The applicant shall file FAA Form 7460-1 (Notice of Proposed Construction or Alteration), and obtain any necessary permits and navigation easements from the Clark County Director of Aviation, as well as any necessary variances from the Airport Hazard Areas Board of Adjustment, prior to construction of this project.
20. Signage for the development shall be permitted in conformance to the Arts District requirements of the Downtown Centennial Plan.
21. All City Code requirements and design standards of all City departments must be satisfied.
22. This development shall not exceed a height of 2,700 feet above Mean Sea Level.

Public Works

23. Coordinate with the Traffic Engineering Division of the Department of Public Works to discuss the proposed Bus Rapid Transit route on 3rd Street adjacent to this site, and how the anticipated modifications to the 3rd street cross-section design will affect this site prior to submittal of construction drawings for this site.
24. Remove all substandard public street improvements and unused driveway cuts adjacent to this site, if any, and replace with new improvements meeting current City Standards concurrent with development of this site. Coordinate with the Land Development Section of the Department of Public Works to determine what improvements are substandard. All existing off site improvements damaged or removed by this development shall be restored at its original location and to its original width concurrent with development of this site.
25. Driveways shall be designed, located and constructed in accordance with Standard Drawing #222A.
26. Show the existing public sewer line and easement along the eastern edge of this site; no building or permanent structure shall encroach into the existing sewer easement. If the existing sewer is to be relocated, an abandonment/relocation plan shall be approved by

EOT-36746
01-06-10 CC


NOV 19 2009

Mr. Herb Sider
SDR-10143 - Page Five
January 23, 2006

concurrent with the commencement of on site development activities unless specifically noted as not required in the approved Traffic Impact Analysis. If additional rights-of-way are not required and Traffic Control devices are or may be proposed at this site outside of the public right-of-way, all necessary easements for the location and/or access of such devices shall be granted prior to the issuance of permits for this site. Phased compliance will be allowed if recommended by the approved Traffic Impact Analysis. No recommendation of the approved Traffic Impact Analysis, nor compliance therewith, shall be deemed to modify or eliminate any condition of approval imposed by the Planning Commission or the City Council on the development of this site.

33. Meet with the Flood Control Section of the Department of Public Works for assistance with establishing finished floor elevations and drainage patterns for this site prior to submittal of construction plans, the issuance of any building or grading permits or the submittal of a map subdividing this site, whichever may occur first. Provide and improve all drainage ways as recommended.
34. The final layout of the subdivision shall be determined at the time of approval of the Tentative Map.
35. The approval of all Public Works related improvements shown on this Site Development Plan Review is in concept only. Specific design and construction details relating to size, type and/or alignment of public improvements, including but not limited to street, sewer and drainage improvements, shall be resolved prior to submittal of a Tentative Map or construction drawings, whichever may occur first. No deviations from adopted City Standards shall be allowed unless specific written approval for such is received from the City Engineer prior to the submittal of a Tentative Map or construction drawings, whichever may occur first.

Sincerely,



Ydoleena Yturralde
Deputy City Clerk II for
Barbara Jo Ronemus, City Clerk

cc: Planning and Development Dept.
Development Coordination-DPW
Dept. of Fire Services

Mr. Richard Layfield
Renzi Development
2200 South Dixie Highway, Suite #705
Coconut Grove, Florida 33133

Mr. Renzo Renzi
Renzi Development
2200 South Dixie Highway, Suite #705
Coconut Grove, Florida 33133

RECEIVED

NOV 19 2009

EOT-36746
01-06-10 CC