



LAS VEGAS CITY COUNCIL

OSCAR B. GOODMAN
MAYOR

GARY REESE
MAYOR PRO TEM

LARRY BROWN
STEVE WOLFSON
LOIS TARKANIAN
STEVEN D. ROSS
RICKI Y. BARLOW

DOUGLAS A. SELBY
CITY MANAGER

February 15, 2008

Rabbi Shea Harlig
Chabad Southern Nevada Inc.
1261 South Arville Street
Las Vegas, Nevada 89102

RE: SDR-18342 – SITE DEVELOPMENT PLAN REVIEW
CITY COUNCIL MEETING OF JANUARY 9, 2008

Dear Rabbi Harlig:

The City Council at a regular meeting held January 9, 2008 APPROVED the request for Site Development Plan Review FOR A PROPOSED 84,276 SQUARE FOOT, 44-FOOT TALL PRIVATE SCHOOL AND A WAIVER OF THE PERIMETER LANDSCAPE BUFFER REQUIREMENTS TO ALLOW NO LANDSCAPING ALONG THE NORTH AND EAST PROPERTY LINES AND ALONG PORTIONS OF THE SOUTH AND WEST PROPERTY LINES WHERE A MINIMUM EIGHT FOOT WIDE BUFFER IS REQUIRED on 4.01 acres adjacent to the west side of Vista Drive, approximately 530 feet south of Charleston Boulevard (APNs 162-06-510-007, 008, 009, and 017), R-E (Residence Estates) and P-R (Professional Office and Parking) Zones. NOTE: THIS APPLICATION HAS BEEN AMENDED TO 77,881 SQUARE FOOT, 35-FOOT HIGH PRIVATE SCHOOL WITH NO LANDSCAPE WAIVERS REQUESTED. The Notice of Final Action was filed with the Las Vegas City Clerk on January 10, 2008. This approval is subject to:

Added Conditions

- A. There shall be a maximum enrollment of 250 students, including the daycare.
- B. The school shall submit a drop-off/pick-up plan to the City Traffic Engineer and receive approval of this plan prior to the submittal of civil improvement drawings or the issuance of any permits, whichever may occur first. The plan shall include proposed enforcement mechanisms to ensure compliance and adequate implementation of the plan.
- C. There shall be no right turn on Vista Drive south bound from school drive exit.
- D. Diverters shall be placed in street in front of school to prevent southbound traffic from school on Vista Drive.
- E. There shall be a right turn only north bound on Vista Drive on to West Charleston Boulevard.

CITY OF LAS VEGAS
400 STEWART AVENUE
LAS VEGAS, NEVADA 89101

VOICE 702.229.6011
TDD 702.386.9108
www.lasvegasnevada.gov

RECEIVED
MAR 04 2010


ROC-37581

8. All mechanical equipment, air conditioners and trash areas shall be fully screened in views from the abutting streets.
9. All utility boxes exceeding 27 cubic feet in size shall meet the standards of LVMC Title 19.12.040.
10. Parking lot lighting standards shall be no more than 30 feet in height and shall utilize downward-directed lights with full cut-off luminaries. Lighting on the exterior of buildings shall be shielded and shall be downward-directed. Non-residential property lighting shall be directed away from residential property or screened, and shall not create fugitive lighting on adjacent properties.
11. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.
12. All City Code requirements and design standards of all City Departments must be satisfied, except as modified herein.

Public Works

13. Coordinate with the City Surveyor to determine whether a Reversionary Map or other map is necessary; comply with the recommendations of the City Surveyor.
14. Construct all incomplete half-street improvements, including transition paving, on Vista Street adjacent to this site concurrent with development of this site. All existing paving damaged or removed by this development shall be restored at its original location and to its original width concurrent with development of this site. Extend all required underground utilities, such as electrical, telephone, etc., located within public rights-of-way, past the boundaries of this site prior to construction of hard surfacing (asphalt or concrete).
15. Remove all substandard public street improvements and unused driveway cuts adjacent to this site, if any, and replace with new improvements meeting current City Standards concurrent with development of this site.
16. Submit an application to the Land Development section of the Department of Public Works for a deviation from Standard Drawing #222a for all of the driveways accessing this site from Vista Drive and Arville Street. Pan driveways are acceptable on Arville Street.
17. Unless otherwise allowed by the City Engineer, construct sidewalk on at least one side of all access drives connecting this site to the adjacent public streets concurrent with development of this site. The connecting sidewalk shall extend from the sidewalk on the public street to the first intersection of the on-site roadway network and shall be terminated on-site with a handicap ramp.


ROC-37581



Rabbi Shea Harlig
SDR-18342 – Page Five
February 15, 2008

construction of neighborhood or local drainage improvements, the amount of such monies shall be determined by the approved Drainage Plan/Study and shall be contributed prior to the issuance of any building or grading permits, or the recordation of a Map subdividing this site, whichever may occur first, if allowed by the City Engineer.

Sincerely,



Lean Coleman
Deputy City Clerk II for
Beverly K. Bridges, CMC, City Clerk



M. Margo Wheeler, AICP
Director
Planning and Development Department

cc: Planning and Development Dept.
Development Coordination-DPW
Dept. of Fire Services

Ms. Sue Gray
Perlman Design Group
2230 Corporate Circle, Suite #200
Henderson, Nevada 89074

RECEIVED
MAR 04 2010

ROC-37581