



LAS VEGAS CITY COUNCIL

OSCAR B. GOODMAN
MAYOR

GARY REESE
MAYOR PRO TEM

LARRY BROWN
STEVE WOLFSON
LOIS TARKANIAN
STEVEN D. ROSS
RICKI Y. BARLOW

DOUGLAS A. SELBY
CITY MANAGER



CITY OF LAS VEGAS
400 STEWART AVENUE
LAS VEGAS, NEVADA 89101

VOICE 702 229 6011

September 7, 2007

Mr. Paul Wagner
Day Star Ventures LLC
6985 West Sahara Avenue, Suite #201
Las Vegas, Nevada 89117

RE. SDR-22253 – SITE DEVELOPMENT PLAN REVIEW
CITY COUNCIL MEETING OF SEPTEMBER 5, 2007
RELATED TO WVR-22255

Dear Mr. Wagner:

The City Council at a regular meeting held September 5, 2007 APPROVED the request for a Major Amendment to an approved Site Development Plan Review (SDR-4626) FOR A 19-LOT SINGLE-FAMILY RESIDENTIAL DEVELOPMENT WITH ACCESS TO HALEY AVENUE INSTEAD OF DORRELL LANE on 5.35 acres adjacent to the northeast corner of Hualapai Way and Haley Avenue (APNs 125-19-201-001 and 003), U (Undeveloped Zone [R (Rural Density Residential) General Plan Designation] under a Resolution of Intent to R-PD3 (Residential Planned Development - 3 Units per Acre). The Notice of Final Action was filed with the Las Vegas City Clerk on September 6, 2007. This approval is subject to:

Planning & Development

1. Conformance to the conditions for Rezoning (ZON-4623), Site Development Plan Review (SDR-4626) and Waiver (WVR-22255), if approved.
2. This approval shall be void two years from the date of final approval, unless a building permit has been issued for the principal building on the site. An Extension of Time may be filed for consideration by the City of Las Vegas.
3. All development shall be in conformance with the site plan, landscape plan, and building elevations, date stamped May 29, 2007, except as amended by conditions herein.
4. A Waiver from 18.12.160 is hereby approved, to allow 210 feet between street intersections where 220 feet is the minimum distance separation required.
5. The standards for this development shall include a Minimum lot size of 5,200 square feet and Building height shall not exceed two stories or 35 feet, whichever is less

EOT-40744

Mr. Paul Wagner
SDR-22253 – Page Two
September 7, 2007

6. The setbacks for this development shall be a minimum of 18 feet to the front of the house, 20 feet to the front of the garage as measured from back of sidewalk or from back of curb if no sidewalk is provided, five feet on the side, 10 feet on the corner side, and 15 feet in the rear.
7. A technical landscape plan, signed and sealed by a Registered Architect, Landscape Architect, Residential Designer or Civil Engineer, must be submitted prior to or at the same time as Final Map submittal. A permanent underground sprinkler system is required, and shall be permanently maintained in a satisfactory manner; the landscape plan shall include irrigation specifications.
8. No turf shall be permitted in the non-recreational common areas, such as medians and amenity zones in this development.
9. Pre-planting and post-planting landscape inspections are required to ensure the appropriate plant material, location, size of planters, and landscape plans are being utilized. The Planning and Development Department must be contacted to schedule an inspection prior to the start of the landscape installation and after the landscape installation is completed. A certificate of occupancy will not be issued or the final inspection will not be approved until the landscape inspections have been completed.
10. Air conditioning units shall not be mounted on rooftops.
11. All utility boxes exceeding 27 cubic feet in size shall meet the standards of LVMC Title 19.12.040.
12. Parking lot lighting standards shall be no more than 30 feet in height and shall utilize downward-directed lights with full cut-off luminaires. Lighting on the exterior of buildings shall be shielded and shall be downward-directed. Non-residential property lighting shall be directed away from residential property or screened, and shall not create fugitive lighting on adjacent properties.
13. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.
14. All City Code requirements and design standards of all City Departments must be satisfied, except as modified herein.

Public Works


15. Install a crash gate at the north end of Aqua Ridge Street.

EOT-40744

Mr. Paul Wagner
SDR-22253 – Page Three
September 7, 2007

16. The onsite street shall be labeled as a private street, be designated as a common lot and shall be labeled as a private street, public utility easement (P.U.E.), public sewer easement and public drainage easement to be privately maintained by the Homeowners' Association on the Final Map for this site.
17. A Homeowners' Association shall be established to maintain all private roadways, landscaping and common areas created with this development. All private improvements and landscaping shall be situated and maintained so as to not create sight visibility obstructions for vehicular traffic at all development access drives and abutting street intersections.
18. Landscape and maintain all unimproved rights-of-way, if any, on adjacent to this site.
19. Submit an Encroachment Agreement for all landscaping, if any, located in the public right-of-way adjacent to this site prior to occupancy of this site.
20. Site development to comply with all applicable conditions of approval for ZON-4623, WVR-22255, and all other applicable site-related actions.
21. The approval of all Public Works related improvements shown on this Site Development Plan Review is in concept only. Specific design and construction details relating to size, type and/or alignment of improvements, including but not limited to street, sewer and drainage improvements, shall be resolved prior to submittal of a Tentative Map or construction drawings, whichever may occur first. No deviations from adopted City Standards shall be allowed unless specific written approval for such is received from the City Engineer prior to the submittal of a Tentative Map or construction drawings, whichever may occur first. Approval of this Site Development Plan does not constitute approval of any deviations.
22. The final layout of the subdivision shall be determined at the time of approval of the Tentative Map.

Sincerely,



Lean Coleman
Deputy City Clerk II for
Beverly K. Bridges, CMC, City Clerk

cc: See Attached List

EOT-40744

Mr. Paul Wagner
SDR-22253 – Page Four
September 7, 2007

cc: Planning and Development Dept.
Development Coordination-DPW
Dept. of Fire Services

Mr. Paul Wagner
Wagner Homes
6985 West Sahara Avenue, Suite #201
Las Vegas, Nevada 89117

Mr. Jeffrey Armstrong
VTN Nevada
2727 South Rainbow Boulevard
Las Vegas, Nevada 89146