




LAS VEGAS CITY COUNCIL

OSCAR B. GOODMAN
MAYOR

GARY REESE
MAYOR PRO TEM

LARRY BROWN
STEVE WOLFSON
LOIS TARKANIAN
STEVEN D. ROSS
RICKI Y. BARLOW

DOUGLAS A. SELBY
CITY MANAGER



CITY OF LAS VEGAS
400 STEWART AVENUE
LAS VEGAS, NEVADA 89101

VOICE 702.229.6011
TDD 702.386.9108
www.lasvegasnevada.gov

November 26, 2007

Mr. Gregory Berkewitz
750 Fremont, LLC
125 North Halsted, Suite #203
Chicago, Illinois 60661

RE: SDR-24527 – SITE DEVELOPMENT PLAN REVIEW
CITY COUNCIL MEETING OF NOVEMBER 21, 2007
RELATED TO SUP-24529

Dear Mr. Berkewitz:

The City Council at a regular meeting held November 21, 2007 APPROVED the request for a Site Development Plan Review FOR A 43,000 SQUARE FOOT TAVERN, WITH NIGHT CLUB AND BANQUET FACILITY on 0.64 acres at 760 Fremont Street (APN 139-34-612-019), C-2 (General Commercial) Zone. The Notice of Final Action was filed with the Las Vegas City Clerk on November 21, 2007. This approval is subject to:

Planning & Development

1. This approval shall be void two years from the date of final approval, unless a building permit has been issued for the principal building on the site. An Extension of Time may be filed for consideration by the City of Las Vegas.
2. All development shall be in conformance with the site plan date stamped 09/21/07 and landscape plan and building elevations date stamped 09/11/07, except as amended by conditions herein.
3. A technical landscape plan, signed and sealed by a Registered Architect, Landscape Architect, Residential Designer or Civil Engineer, must be submitted prior to or at the same time application is made for a building permit. A permanent underground sprinkler system is required, and shall be permanently maintained in a satisfactory manner; the landscape plan shall include irrigation specifications.
4. Pre-planting and post-planting landscape inspections are required to ensure the appropriate plant material, location, size of planters, and landscape plans are being utilized. The Planning and Development Department must be contacted to schedule an inspection prior to the start of the landscape installation and after the landscape installation is completed. A certificate of occupancy will not be issued or the final inspection will not be approved until the landscape inspections have been completed.



5. Reflective glazing at the pedestrian level is prohibited. Glazing above the pedestrian level shall be limited to a maximum reflectance rating of 22% (as defined by the National Institute of Standards and Technology).
6. All mechanical equipment, air conditioners and trash areas shall be fully screened in views from the abutting streets.
7. All utility boxes exceeding 27 cubic feet in size shall meet the standards of LVMC Title 19.12.040.
8. Parking lot lighting standards shall be no more than 30 feet in height and shall utilize downward-directed lights with full cut-off luminaires. Lighting on the exterior of buildings shall be shielded and shall be downward-directed. Non-residential property lighting shall be directed away from residential property or screened, and shall not create fugitive lighting on adjacent properties.
9. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.
10. All City Code requirements and design standards of all City Departments must be satisfied, except as modified herein.

Public Works

11. Coordinate with the Department of Building and Safety to determine if existing property lines have any impact to development of this site.
12. Dedicate a 10 foot radius on the northwest corner of Fremont Street and 8th Street prior to the issuance of any permits.
13. Remove all substandard public street improvements and unused driveway cuts adjacent to this site, if any, and replace with new improvements meeting current City Standards concurrent with development of this site. All new improvements shall be constructed to the Downtown Centennial Plan Standards, unless specifically allowed otherwise through waivers approved by City Council.
14. Submit an application to the Land Development section of the Department of Public Works for a deviation from Standard Drawing #222a for the driveway accessing this site from 8th Street.
15. Landscape and maintain all unimproved rights-of-way, if any, on Fremont Street and 8th Street adjacent to this site. All landscaping and private improvements installed with this project shall be situated and maintained so as to not create sight visibility obstructions for vehicular traffic at all development access drives and abutting street intersections.
16. Submit an Encroachment Agreement for all landscaping, if any, located in the public rights-of-way adjacent to this site prior to occupancy of this site.

EOT-43817

Mr. Gregory Berkewitz
SDR-24527 – Page Three
November 26, 2007

17. Meet with the Flood Control Section of the Department of Public Works for assistance with establishing finished floor elevations and drainage paths for this site prior to submittal of construction plans or the issuance of any building or grading permits, whichever may occur first. Provide and improve all drainage ways as recommended.
18. A Traffic Impact Analysis must be submitted to and approved by the Department of Public Works prior to the issuance of any building or grading permits, submittal of any construction drawings or the recordation of a Map subdividing this site. Comply with the recommendations of the approved Traffic Impact Analysis prior to occupancy of the site. The Traffic Impact Analysis shall also include a section addressing Standard Drawings #234.1 #234.2 and #234.3 to determine additional right-of-way requirements for bus turnouts adjacent to this site, if any; dedicate all areas recommended by the approved Traffic Impact Analysis. All additional rights-of-way required by Standard Drawing #201.1 for exclusive right turn lanes and dual left turn lanes shall be dedicated prior to or concurrent with the commencement of on-site development activities unless specifically noted as not required in the approved Traffic Impact Analysis. If additional rights-of-way are not required and Traffic Control devices are or may be proposed at this site outside of the public right-of-way, all necessary easements for the location and/or access of such devices shall be granted prior to the issuance of permits for this site. Phased compliance will be allowed if recommended by the approved Traffic Impact Analysis. No recommendation of the approved Traffic Impact Analysis, nor compliance therewith, shall be deemed to modify or eliminate any condition of approval imposed by the Planning Commission or the City Council on the development of this site.

Sincerely,



Angela Crolli
Deputy City Clerk II for
Beverly K. Bridges, CMC, City Clerk

cc: Planning and Development Dept.
Development Coordination-DPW
Dept. of Fire Services

Mr. Victor Perillo
1345 South Lewis Street
Anaheim, California 92805

Ms. Kristen Neuman
APTUS Architecture
1200 South Fourth Street, Suite #206
Las Vegas, Nevada 89104

