

Bumpers or tire stops shall be provided for all parking stalls heading into a sidewalk, landscaped area, street, or alley. Each shall be installed at a minimum of two-feet from the beginning of said sidewalk, landscaped area, street, or alley.

Parking spaces directly adjacent to buildings are discouraged.

h. Parking Lot Access.

When possible, adjacent parcels requiring access drives shall share a common centrally located access drive.

Wherever a driveway is abandoned, the owner shall remove all driveway pavement and approach, re-install curb and gutter, and landscape the area to match the adjacent landscaping/streetscape.

i. On-Street Valet Parking.

On-Street Valet parking is permitted within the Centennial Planning area. Requests for an on-street valet parking permit must be made in writing and shall be accompanied by a filing fee to the City Traffic Engineer. A right-of-way usage fee may also apply. The City Traffic Engineer is solely responsible for issuing on-street valet permits with conditions that are in the best interest of the City and the general safety of the public.

4. Streetscape Standards.

a. Right-of-Way Improvements.

All streets shall have a five foot amenity zone and a 10 foot wide, unobstructed sidewalk (Graphic 12).


The surface of the sidewalk should appear as a consistent pattern. At the corners, the sidewalk must ramp down to provide for handicapped access and have stamped pattern concrete (Graphic 13).


The entire 10-foot width of public right-of-way sidewalks shall not exceed a 2 percent slope.



All new developments shall provide and install light fixtures, benches, trash receptacles and **tree grates** in accordance with the Las Vegas Downtown Centennial Plan area models and specifications. Placement and spacing of light fixtures shall be as directed by Public Works.

Supporting landscape and streetscape improvements shall be incorporated into the streetscape design including lighting, and other landscape elements such as freestanding planters, planter boxes and hanging baskets.


Streetlights and decorative pedestrian lights shall be incorporated into any new streetscape improvements per district standards. Overhead lights must provide the ambient light necessary for safety and traffic











* When required tree(s) that are larger than above openings, a similar designed tree grate may be used.





MAP 12: DOWNTOWN SOUTH DISTRICT



18b The Las Vegas Arts District
(80.76 Acres)

Downtown Districts

MAP 13: 18b THE LAS VEGAS ARTS DISTRICT