

TECHNICAL DRAINAGE STUDY
UPDATE No. 1
Skye Canyon Phase 3 Infrastructure
City of Las Vegas, Nevada

Job No.: OLY1602.000
Date: October 2017

Prepared By:

Slater Hanifan Group, Inc.
5740 S. Arville Street, Suite 216
Las Vegas, Nevada 89118
Phone: 702-284-5300 • Fax: 702-284-5399

Prepared For:

Ninety-Five Management, LLC
11411 Southern Highlands Parkway, Suite 300
Las Vegas, Nevada 89141
Phone: 702-220-6565 • Fax: 702-220-6566



Lant Leavitt, P.E.
NV Professional Engineer No. 18287

HYDROLOGIC CRITERIA AND DRAINAGE DESIGN MANUAL
DRAINAGE STUDY INFORMATION FORM

Name of Development: Skye Canyon – Phase 3 Infrastructure Date: October 18, 2017
Location of Development: a) Descriptive (Cross Streets): North/South: Grand Canyon Drive
East/West: Skye Canyon Park Drive
b) Section: 7 Township: 19 South Range: 60 East
c) APN: 125-07-210-003

Name of Owner/Developer: M F Land, LLC / Ninety-Five Management, LLC
Telephone No.: 702-220-6565 Fax No.: 702-220-6566 E-mail Address: bwilliamson@olympiacompanies.com
Address: 11411 Southern Highlands Parkway, Suite 300; Las Vegas, NV 89141

Contact Person – Name: Lant Leavitt, P.E. Telephone No.: 702-284-5300
*E-mail Address: lleavitt@shg-inc.com Fax No.: 702-284-5399
Firm: Slater Hanifan Group
Address: 5740 S. Arville Street, Suite 216; Las Vegas, NV 89118

Type of Land Development/Land Disturbance Process:

☐ Rezoning	☐ Subdivision Map	☐ Clearing and grading Only
☐ Parcel Map	☐ Planned Unit Development	☒ Other (Please specify below)
☐ Large Parcel Map	☐ Building Permit	☐ Roadway & Storm Drain Infrastructure

1. Total Owned Land Area: At Site: 37.5 Acres Being Developed/Disturbed: 3.4 Acres +/-

2. Is a portion or all of the subject property located in a FEMA Flood Hazard Area? ☐ Yes** ☒ No

3. Is the property bordered or crossed by an existing or proposed Clark County Regional Flood Control District Master Planned Facility? ☐ Yes** ☒ No

4. Proposed type of development (Residential, Commercial, Etc.): Roadway


5. Approximate upstream land area which drains to the subject site: 1.6 sq. miles +/-

6. Has the site drainage been evaluated in the past? ☒ Yes** ☐ No If yes, please identify documentation: Master Drainage Study for Skye Canyon (SHG, DS4420)

Technical Drainage Study for Skye Canyon Phase 3 Infrastructure (SHG DS4796)

7. If known, please briefly identify the proposed discharge point(s) of runoff from the site: East into ephemeral wash that crosses Grand Canyon approximately 700-ft north of Skye Canyon Park Drive

8. Briefly describe your proposed schedule for the subject project: ASAP. Phase 3 is divided into 2 phases:
Roadways – Infrastructure TDS; Commercial Subdivision – Onsites TDS. Infrastructure is constructed. Onsites are in progress.



Engineer's Seal

Submit this form as part of the required drainage study to the local entity which has jurisdiction over The subject property. This form may provide sufficient information to serve as the Conceptual Drainage Study.

***Newly Required Field**

****Review and concurrence of the Clark County Regional Flood Control District is required**

Local Entity File No.	Revision	Date

REFERENCE: *SHG Job No. OLY1602.000*

STANDARD FORM 1

Updated 05/01/2008



OLY1602.000

October 17, 2017

Albert Sung, P.E.
Flood Control Project Engineer
City of Las Vegas Department of Public Works
333 N. Rancho Drive
Las Vegas, Nevada 89106

Subject: Technical Drainage Study Update No. 1 for Skye Canyon Phase 3 Infrastructure (DS 4796)

Mr. Sung:

Submitted for your review is this *Technical Drainage Study Update for Skye Canyon Phase 3 Infrastructure* (hereinafter referred to as the Update Study). The original *Technical Drainage Study for Skye Canyon Phase 3 Infrastructure* (hereinafter referred to as the Original Study) was prepared by Slater Hanifan Group (SHG) and approved on September 22, 2016. The City of Las Vegas (CLV) approval letter has been provided in Appendix B.

Since the approval of the Original Study, the infrastructure improvements have been constructed and onsite commercial development grading (DS 4812) is being performed. The original Grand Canyon Drive culvert (see Original Study Hydraulic Summary Map, Appendix B) was constructed with an interim 14' x 7' RCB entrance to convey flow from the existing wash crossing the site. This interim culvert entrance is not needed now that onsite commercial improvements are being constructed, and the height of the culvert entrance interferes with the improvements proposed by the onsite developer.

Purpose: It is proposed to remove a portion of the interim culvert entrance at Grand Canyon Drive to facilitate onsite development. Revised improvement plans (Appendix D) show the extent of removal of the interim culvert entrance. To accomplish the removal, the connection of the existing 72" RCP storm drain lateral is also proposed to be revised. The 72" RCP will transition to a 6'x5' RCB and then discharge into the existing 14'x5' RCB. The purpose of this Update Study is to present the revised culvert configuration and provide updated hydraulic modeling of the crossing.

Hydraulic Analysis

The Grand Canyon Drive culvert crossing was modeled in the original study using WSPG (Appendix B). An updated model has been prepared to model the revised geometry of the culvert crossing (Appendix A.) No changes that would affect project hydrology have been made, and the revised model retains the original flow rates. Comparison of results of the updated WSPG model are shown in the following table:

WATER SURFACE COMPARISON TABLE

FACILITY / LOCATION	INVERT	ORIGINAL WSE (ft)	UPDATED WSE (ft)	UPDATED DEPTH (ft)	FG ELEV (ft)
72" RCP					
@ TRANS to 6'x5' RCB	2749.66	n/a	2753.31	3.65	2758.2
6'x5' RCB					
@ TRANS to 72" RCP	2749.60	n/a	2752.54	2.94	2757.9
@ ANGLE PT	2749.50	n/a	2752.49	2.99	2757.4
@ EXIT TO 14'X5' RCB	2749.34	n/a	2752.40	3.06	2757.5
14'x5' RCB					
WSPG STA 1059.43	2749.34	2750.64	2750.60	1.26	2757.5
WSPG STA 1033.50	2749.24	2750.59	2750.58	1.33	2757.9
WSPG STA 1017.00	2749.19	2751.24	2751.21	2.02	2757.5
30.5'x5' RCB					
WSPG STA 1007.00	2749.09	2753.93	2753.87	4.78	2757.5

As shown in the above table, water surface elevations in the proposed facilities are generally a few hundredths of a foot less than the original facility. No adverse impacts to culvert hydraulics are introduced by the proposed revisions.

Conclusion

Through evaluation of the proposed improvements and the supporting calculations and reference materials provided, it has been concluded that this Update Study and the proposed improvements are in conformance with the original *Technical Drainage Study for Skye Canyon Phase 3 Infrastructure*.

- This project is in compliance with all the applicable drainage laws as recognized by the state of Nevada as well as all the applicable design standards stipulated in the CCRFCD "Hydrologic Criteria and Drainage Design Manual".
- This project is in compliance with the 2008/2013 CCRFCD "Master Plan Update," and is not directly bordered and/or traversed by any existing or future CCRFCD master planned facilities.
- The entire project site is located outside of the FEMA designated Special Flood Hazard Area (SFHA). The site and the proposed improvements are located within a FEMA flood Zone "X" (unshaded). Therefore, notification and/or coordination with FEMA will not be required for this project.
- The changes proposed in this update are in compliance with the previously approved Original Study. The proposed changes do not alter the previously established offsite flow rates.

The revised improvement plan set has been included in Appendix D to support the conclusions detailed in this study. If you have any questions or require additional information, please do not hesitate to contact us at (702) 284-5300.

Respectfully Submitted,

SLATER HANIFAN GROUP



Lant Leavitt, P.E.
Flood Control Division

pc: Mark Failla, P.E., CFM – SHG
Jerry Slater, P.E. – SHG
Jerrod Ratcliffe, P.E. – SHG

LIST OF APPENDICIES

Appendix A	Revised WSPG Model
Appendix B	Reference Material ▪ Previous Skye Canyon Phase 3 Approval Letter ▪ Previously Approved Skye Canyon Phase 3 Hydraulic Summary Map ▪ Previously Approved Skye Canyon Phase 3 Grand Canyon WSPG Model
Appendix C	Electronic Copy of Study (CD)
Appendix D	Revised Storm Drain Plan and Profile

APPENDIX A

Revised WSPG Model

[illegible]

FILE: futr.WSW

W S P G W - EDIT LISTING - Version 14.06

Date: 10- 9-2017

Time:10:36:30

WATER SURFACE PROFILE - CHANNEL DEFINITION LISTING

PAGE 1

[illegible]

CD	1	1	0	.000	4.000	20.000	1.000	1.000	.00
CD	1	1	0	.000	5.000	6.000	.000	.000	.00
CD	2	3	0	.000	5.000	14.000	.000	.000	.00
CD	3	3	0	.000	5.000	20.000	3.000	3.000	.00
CD	4	1	0	.000	5.000	30.500	10.000	10.000	.00
CD	5	1	0	.000	5.000				.00
CD	54	4	1		4.500				.00
CD	60	4	1		5.000				.00
CD	66	4	1		5.500				.00
CD	72	4	1		6.000				.00

W S P G W

W S P G W

WATER SURFACE PROFILE - TITLE CARD LISTING

SKYE CANYON PHASE 3 UPDATE OCT 2017

.....

STORM DRAIN SYSTEM AT GRAND CANYON TOW POINT (CULVERT CROSSIN

[illegible]

ING TO NATI

W S P C W

WATER SUPPLY PROJECTS - FI

	CUT RE	+	-	ELENT	+
	WATER SURFACE PROFILE -	+	+		

ETIOL

TA	STATION	INVERT	SECT
0000	0000	0740	000
0000	0000	0740	000

398.000 2/48.380

	E
	C
*	E
	A
	E
	N
	S
*	M
	G
	H
	E
	E
	C
	F

TA	STATION	INVERT	SECT.
0000	0000	07.10	0000

999.000 2/48.980 I

FUNCTION

* * *

TA STATION INVERT SECT

1007.000 2749.090 5

NC
*
*
*

STA	STATION	INVERT	SECT
1	1+00.00	100.00	1
2	2+00.00	200.00	2
3	3+00.00	300.00	3
4	4+00.00	400.00	4
5	5+00.00	500.00	5
6	6+00.00	600.00	6
7	7+00.00	700.00	7
8	8+00.00	800.00	8
9	9+00.00	900.00	9
10	10+00.00	1000.00	10
11	11+00.00	1100.00	11
12	12+00.00	1200.00	12
13	13+00.00	1300.00	13
14	14+00.00	1400.00	14
15	15+00.00	1500.00	15
16	16+00.00	1600.00	16
17	17+00.00	1700.00	17
18	18+00.00	1800.00	18
19	19+00.00	1900.00	19
20	20+00.00	2000.00	20
21	21+00.00	2100.00	21
22	22+00.00	2200.00	22
23	23+00.00	2300.00	23
24	24+00.00	2400.00	24
25	25+00.00	2500.00	25
26	26+00.00	2600.00	26
27	27+00.00	2700.00	27
28	28+00.00	2800.00	28
29	29+00.00	2900.00	29
30	30+00.00	3000.00	30
31	31+00.00	3100.00	31
32	32+00.00	3200.00	32
33	33+00.00	3300.00	33
34	34+00.00	3400.00	34
35	35+00.00	3500.00	35
36	36+00.00	3600.00	36
37	37+00.00	3700.00	37
38	38+00.00	3800.00	38
39	39+00.00	3900.00	39
40	40+00.00	4000.00	40
41	41+00.00	4100.00	41
42	42+00.00	4200.00	42
43	43+00.00	4300.00	43
44	44+00.00	4400.00	44
45	45+00.00	4500.00	45
46	46+00.00	4600.00	46
47	47+00.00	4700.00	47
48	48+00.00	4800.00	48
49	49+00.00	4900.00	49
50	50+00.00	5000.00	50
51	51+00.00	5100.00	51
52	52+00.00	5200.00	52
53	53+00.00	5300.00	53
54	54+00.00	5400.00	54
55	55+00.00	5500.00	55
56	56+00.00	5600.00	56
57	57+00.00	5700.00	57
58	58+00.00	5800.00	58
59	59+00.00	5900.00	59
60	60+00.00	6000.00	60
61	61+00.00	6100.00	61
62	62+00.00	6200.00	62
63	63+00.00	6300.00	63
64	64+00.00	6400.00	64
65	65+00.00	6500.00	65
66	66+00.00	6600.00	66
67	67+00.00	6700.00	67
68	68+00.00	6800.00	68
69	69+00.00	6900.00	69
70	70+00.00	7000.00	70
71	71+00.00	7100.00	71
72	72+00.00	7200.00	72
73	73+00.00	7300.00	73
74	74+00.00	7400.00	74
75	75+00.00	7500.00	75
76	76+00.00	7600.00	76
77	77+00.00	7700.00	77
78	78+00.00	7800.00	78
79	79+00.00	7900.00	79
80	80+00.00	8000.00	80
81	81+00.00	8100.00	81
82	82+00.00	8	

1017.000 2749.190 5

EXIT

TA STATION INVERT SECT

1017.000 2749.190 3

*
*
*

TA	STATION	INVERT	SECT
1	1+00	100.00	1
2	2+00	200.00	2
3	3+00	300.00	3
4	4+00	400.00	4
5	5+00	500.00	5
6	6+00	600.00	6
7	7+00	700.00	7
8	8+00	800.00	8
9	9+00	900.00	9
10	10+00	1000.00	10
11	11+00	1100.00	11
12	12+00	1200.00	12
13	13+00	1300.00	13
14	14+00	1400.00	14
15	15+00	1500.00	15
16	16+00	1600.00	16
17	17+00	1700.00	17
18	18+00	1800.00	18
19	19+00	1900.00	19
20	20+00	2000.00	20
21	21+00	2100.00	21
22	22+00	2200.00	22
23	23+00	2300.00	23
24	24+00	2400.00	24
25	25+00	2500.00	25
26	26+00	2600.00	26
27	27+00	2700.00	27
28	28+00	2800.00	28
29	29+00	2900.00	29
30	30+00	3000.00	30
31	31+00	3100.00	31
32	32+00	3200.00	32
33	33+00	3300.00	33
34	34+00	3400.00	34
35	35+00	3500.00	35
36	36+00	3600.00	36
37	37+00	3700.00	37
38	38+00	3800.00	38
39	39+00	3900.00	39
40	40+00	4000.00	40
41	41+00	4100.00	41
42	42+00	4200.00	42
43	43+00	4300.00	43
44	44+00	4400.00	44
45	45+00	4500.00	45
46	46+00	4600.00	46
47	47+00	4700.00	47
48	48+00	4800.00	48
49	49+00	4900.00	49
50	50+00	5000.00	50
51	51+00	5100.00	51
52	52+00	5200.00	52
53	53+00	5300.00	53
54	54+00	5400.00	54
55	55+00	5500.00	55
56	56+00	5600.00	56
57	57+00	5700.00	57
58	58+00	5800.00	58
59	59+00	5900.00	59
60	60+00	6000.00	60
61	61+00	6100.00	61
62	62+00	6200.00	62
63	63+00	6300.00	63
64	64+00	6400.00	64
65	65+00	6500.00	65
66	66+00	6600.00	66
67	67+00	6700.00	67
68	68+00	6800.00	68
69	69+00	6900.00	69
70	70+00	7000.00	70
71	71+00	7100.00	71
72	72+00	7200.00	72
73	73+00	7300.00	73
74	74+00	7400.00	74
75	75+00	7500.00	75
76	76+00	7600.00	76
77	77+00	7700.00	77
78	78+00	7800.00	78
79	79+00	7900.00	79
80	80+00	8000.00	80
81	81+00	8100.00	81
82	82+00	8200.00	82
83	83+00	8300.00	83
84	84+00	8400.00	84
85	85+00	8500.00	85
86	86+00	8600.00	86
87	87+00	8700.00	

1033.500 2749.240 3

NO

STATION INVERT SECT

1033	500	2749	240	3
------	-----	------	-----	---

THE ABOVE ELEMENT CONTAINED AN INVERT ELEV WHICH WAS NOT GREATER THAN THE PREVIOUS INVERT ELEV -WARNING
 THE ABOVE ELEMENT CONTAINED AN INVERT ELEV WHICH WAS NOT GREATER THAN THE PREVIOUS INVERT ELEV -WARNING

ELEMENT NO	8	IS A REACH	U/S DATA	STATION	1059.430	INVERT	2749.340	SECT	3	N	.013	RADIUS	.000	ANGLE	.000	ANG PT	MAN H
																.000	0

ELEMENT NO	9	IS A WALL EXIT	U/S DATA	STATION	1059.430	INVERT	2749.340	SECT	2								

PAGE NO 3

WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	10	IS A REACH	U/S DATA	STATION	1079.430	INVERT	2749.500	SECT	2	N	.013	RADIUS	.000	ANGLE	.000	ANG PT	MAN H
																11.000	0

ELEMENT NO	11	IS A REACH	U/S DATA	STATION	1091.430	INVERT	2749.600	SECT	2	N	.013	RADIUS	.000	ANGLE	.000	ANG PT	MAN H
																22.000	0

ELEMENT NO	12	IS A TRANSITION	U/S DATA	STATION	1098.430	INVERT	2749.660	SECT	72	N	.013	RADIUS	.000	ANGLE	.000		

ELEMENT NO	13	IS A REACH	U/S DATA	STATION	1112.550	INVERT	2749.880	SECT	72	N	.013	RADIUS	.000	ANGLE	.000	ANG PT	MAN H
																.000	0

*

ELEMENT NO	14	IS A SYSTEM HEADWORKS	U/S DATA	STATION	1112.550	INVERT	2749.880	SECT	72								

W S ELEV
 2753.500

Date: 10- 9-2017 Time: 10:36:37

WATER SURFACE PROFILE LISTING

SKYE CANYON PHASE 3 UPDATE OCT 2017

STORM DRAIN SYSTEM AT GRAND CANYON LOW POINT (CULVERT CROSSING)
14'W x 5'H RCB DISCHARGING TO NATURAL WASH (FUTURE CONDITION)

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Width	Top Height/Dia.	Base Wt/FT	ZL	No Wth Prs/Pip
L/Elem	Ch Slope					SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch
998.000	2748.980	3.168	2752.148	695.00	9.47	1.39	2753.54	.00	3.17	26.34	4.000	20.000	1.00	0 .0
.887	.0000	-	-	-	-	.0133	.01	-	3.17	1.00	.035	.00	1.00	TRAP
998.887	2748.980	3.326	2752.306	695.00	8.96	1.25	2753.55	.00	3.17	26.65	4.000	20.000	1.00	0 .0
.113	.0000	-	-	-	-	.0122	.00	-	3.33	.93	.035	.00	1.00	TRAP
999.000	2748.980	3.335	2752.315	695.00	8.93	1.24	2753.55	.00	3.17	26.67	4.000	20.000	1.00	0 .0
TRANS STR	.0138	-	-	-	-	.0090	.07	-	.92		.042	.00	1.00	TRAP
1007.000	2749.090	4.779	2753.869	695.00	1.86	.05	2753.92	.00	2.01	126.07	5.000	30.500	****	0 .0
JUNCT STR	.0100	-	-	-	-	.0001	.00	-	.19		.015	.00	****	TRAP
1017.000	2749.190	4.682	2753.872	671.00	1.85	.05	2753.93	.00	1.98	124.13	5.000	30.500	****	0 .0
HYDRAULIC JUMP		-	-	-	-	-	-	-	-	-	-	-	-	-
1017.000	2749.190	2.021	2751.211	671.00	23.72	8.74	2759.95	.00	4.15	14.00	5.000	14.000	.00	0 .0
16.500	.0030	-	-	-	-	.0245	.40	-	2.94	4.06	.013	.00	.00	BOX
1033.500	2749.240	1.976	2751.216	671.00	24.25	9.13	2760.35	.00	4.15	14.00	5.000	14.000	.00	0 .0
JUNCT STR	.0000	-	-	-	-	.0360	.00	-	3.04		.013	.00	.00	BOX
1033.500	2749.240	1.336	2750.576	499.00	26.67	11.05	2761.62	.00	3.40	14.00	5.000	14.000	.00	0 .0
3.759	.0039	-	-	-	-	.0473	.18	-	1.34	4.07	.013	.00	.00	BOX
1037.259	2749.254	1.326	2750.580	499.00	26.88	11.22	2761.80	.00	3.40	14.00	5.000	14.000	.00	0 .0
22.171	.0039	-	-	-	-	.0517	1.15	-	1.33	4.11	.013	.00	.00	BOX

APPENDIX B

Reference Material

Previous Skye Canyon Phase 3 Approval Letter

Previously Approved Skye Canyon Phase 3 Hydraulic Summary Map

Previously Approved Skye Canyon Phase 3 Grand Canyon WSPG Model

**TECHNICAL DRAINAGE STUDY
ADDENDUM No. 2**

**Skye Canyon
Phase 3 Infrastructure**
City of Las Vegas, Nevada

Job No.: OLY1602.000
Date: August 2016

Prepared By:

Slater Hanifan Group, Inc.
5740 S. Arville Street, Suite 216
Las Vegas, Nevada 89118
Phone: 702-284-5300 • Fax: 702-284-5399

Prepared For:

Ninety-Five Management, LLC
11411 Southern Highlands Parkway, Suite 300
Las Vegas, NV 89141
Phone: 702-220-6565 • Fax: 702-220-6566



Steve Jones, P.E.
NV Professional Engineer No. 19638

Assisted by: Cameron Bencini, E.I.

CITY OF LAS VEGAS		DATE:
INTER-OFFICE MEMORANDUM		September 22, 2016
TO: Land Development Services Department of Building & Safety		FROM: Albert Sung, P.E. Flood Control Project Engineer Department of Public Works
SUBJECT:	Drainage Study for:	COPIES TO:
	Skye Canyon – Phase 3 Infrastructure	Slater Hanifan Group
Cross Streets:	NWC of Grand Canyon & Skye Canyon Park	MF Land / Ninety Five Management
File Number:	F:\Depot\DSMemos\DS4796C.doc	Bart Anderson, P.E., DevCo
Parcel Number:	125-07-201-003	
Zoning Action:	MOD-62679; SUP-63594; SUP-63597; SDR-63598; VAR-63963 & GPA-64013	
FEMA Flood Zone	YES NO X	
Proposed Storm Drain	YES X NO	

HISTORY	DATE RECEIVED	DATE REVIEWED	COMMENTS	REVIEW FEES	FEES PAID Payment Trn #
1 st Submittal	4/28/2016	5/24/2016 & 6/28/2016	Not Approved	\$400.00	442241: \$400
2 nd Submittal & Supplement	7/21/2016 & 7/25/2016	8/18/2016	Not Approved	\$400.00	452170: \$400
3 rd Submittal	8/31/2016 & 9/16/2016	9/22/2016	See Comments Below	\$400.00	456806: \$400
TOTAL FEES (LDDRS):				\$1,200.00	----

REMARKS: Infrastructure necessary for the 38 acre Commercial Development known as Phase 3.

The Drainage Study for the subject project has been reviewed and:

	is approved subject to conformance to all City standards and the following conditions:
	must be resubmitted or supplemented including the following:
	is conditionally approved subject to Clark County Regional Flood Control District concurrence.
X	is conditionally approved subject to the satisfaction of the following conditions:

- The **Phase 3 Infrastructure** drainage study addresses the included street improvements of *Grand Canyon Drive, Skye Park Drive, Street "D"*, a local minor detention basin, culvert crossings and storm drain systems within the perimeter streets. A separate technical drainage study will be required for the future onsite commercial developments.
- The proposed local detention basin near concentration point "CPN" is a minor and temporary facility which will be removed by the developer upon the construction of the ultimate upstream *Regional Flood Control* facilities. This detention basin is to be privately owned and privately maintained by the master developer. The developer shall provide maintenance access to the public storm drain outfall and shall provide a public drainage easement, to be privately maintained. The public drainage easement (privately maintained) must be dedicated and recorded prior to the final approval of the improvement plans.


3. The proposed debris/sediment basins at concentration points "CPN" and "CPS" shall be privately owned and privately maintained by the master developer. These facilities are considered to be temporary in nature and the City understands that the future development and the ultimate *Regional Flood Control* facilities will require that these facilities may be removed by the developer upon the City's approval of a Technical Drainage Study that addresses the impacts of those improvements.
4. The proposed culvert crossings at the concentration points "CPN", "CPS" and "WC9" are oversized interim facilities that are not required in the ultimate condition. All drainage facilities proposed in this **Phase 3 Infrastructure Study** are considered interim facilities and must be maintained by the Master Developer until the upstream ultimate facilities are completed and accepted by the *City of Las Vegas*. *The City of Las Vegas* will not maintain the culverts during all interim conditions. Interim facilities will require an Encroachment Agreement for those facilities within public right-of-way.
5. Future development of the site will require storm drain extensions from "CPN" and "CPS" and the corresponding public drainage easements (privately maintained) traversing the *Skye Canyon Village* site. Dedication shall be provided using the mapping process or by separate legal description and must be approved by *Flood Control* prior to recordation. The easements must be recorded prior to the final approval of the subject improvement plans.
6. The provided Phase 3 Infrastructure plans only show the proposed drainage facilities. The complete improvement plans will require additional review for impacts with other needed infrastructure; i.e. sanitary sewer, water, gas, etc. Any changes to the proposed storm drain system shall require a drainage study update.
7. Since the streets network and the associated storm drain facilities will eventually be accepted by the City, the engineer must coordinate with *City of Las Vegas Streets & Sanitation Department* for their review and approval prior to the final approval of the improvement plans.
8. Structural plans for the storm drain improvements must be submitted for review. Provide a soil report, structural calculations and specifications, wet stamped structural sets and a grading plan to the *City of Las Vegas Building Department* for processing (call *Building Department* to confirm their submittal requirements). The engineer must provide a copy of *Building Department* approval of the structures to *City Flood Control Section* prior to the final acceptance of the improvement plans.
9. The project proposes to build temporary drainage facilities including; detention basins, debris/sediment basins, drainage berms/swales over the *Phase 3* site. Prior to final plan approval the developer must complete a **Maintenance and Liability Agreement** for the interim drainage improvements and post a minimum maintenance bond of \$50,000 or 50-percent of the construction cost for the improvements, whichever is greater. The engineer must submit an estimate of the quantities for construction the facility and an exhibit that adequately shows the location and limits of the drainage facility to *City Flood Control* for approval. Once the drainage study is conditionally approved, the engineer/developer should contact the *City's Land Development Section* (702-229-6371) to begin the agreement process.

In order for the maintenance bond to be released in the future, a drainage update/letter will be required to justify that the berms/swales are no longer necessary and can be removed.

NOTE: Please be advised that all land surface area disturbances over 1 acre or any area adjacent to a water way must submit to the *Nevada Division of Environmental Protection* a "Notice of Intent" to discharge that certifies a stormwater pollution prevention plan has been developed and is maintained on site; for inclusion in the Stormwater General Permit No. NVR100000. A phased construction unit in a contiguous subdivision is considered under construction until all stripped or disturbed surface areas have been covered by paving, building construction or planting. For more information, including forms and applications see <http://ndep.nv.gov/bwpc/storm01.htm> or call (775) 687-9429.

END OF REMARKS
ays

T/R/S: T19S/R60E/07
AREA G-07



\\s01602-000 sky canyon phase 3\drainage\technical study\addendum2\figures\oly1602-000 tds add1 facilities map.dwg 8/26/2016 2:38 PM Collin Alcantara

Existing Flood Control Facilities			
Facility ID	Facility Description	Phase 1 Design Flow (cfs)	Phase 3 Revised Flow (cfs)
X1	5'6" Type CM2 Inlet	3	3
X2	24" RCP	6	6
X3A	36" RCP	45	0
X3B	36" RCP	47	47
X4	42" RCP	92	47
X5A	15'0" Type CM2 Inlet	15	Nuisance
X5B	12'5" Type CM2 Inlet	15	Remove DI
X6C	36" RCP	30	Abandoned
X6D	24" RCP	6.5	6.5
X6E	42" RCP	128.5	53.5
X7A	Total 32'5" Type CM2 Inlets	17.5	12
X7B	24" RCP	17.5	12
X7C	36" RCP	45	45
X7D	24" RCP	6	6
X8	6W x 5H RCB	123.5	53.5
X9	6W x 5H RCB	127	121

Grand Canyon Flood Control Facilities			
Facility ID	Facility Description	Hydrologic Condition	Contributing Source
GC1	Interim 14W x 7H RCB Inlet	Proposed	WCBA
GC2	Proposed 72" RCP Stub (Capped for Onsite Commercial)	Future	N/A
GC3	Proposed 14W X5H RCB	Proposed	WCBA
GC4	Proposed 14W X5H RCB	Proposed	WCBA
GC5	Proposed 66" RCP Stub (Capped for Onsite Commercial)	Proposed	WCBA
GC6	Proposed 66" RCP	Proposed	WCBA
GC7	Proposed 66" RCP	Proposed	WCBA
GC8	Proposed 10' Type CM2 SDOI & 24" RCP SD Lateral	Proposed	WCBA
GC9	Proposed 24" RCP Stub (Capped for Others)	Proposed	WCBA
GC10	Proposed 66" RCP Stub (Capped for Others)	Proposed	WCBA
GC11	6W x 5H RCB	Proposed	WCBA
GC12	Proposed 7.5' Type CM2 SDOI & 24" RCP SD Lateral	Proposed	WCBA
GC13	Proposed 24" RCP Stub	Proposed	WCBA
GC14	Existing Wash	Proposed	WCBA

Skye Park Drive Flood Control Facilities			
Facility ID	Facility Description	Hydrologic Condition	Contributing Source
SPD1a	Proposed 12" Type CM2 Inlet & 24" RCP Lateral	Proposed	SPD1a
SPD1b	Proposed 12" Type CM2 Inlet & 24" RCP Lateral	Proposed	SPD1a
SPD2	Proposed 36" RCP	Proposed	SPD1a
SPD3	Proposed 72" RCP	Proposed	SPD1a
SPD4	Proposed 72" RCP	Proposed	SPD1a
SPD5	Emergency Overflow 30' Wide Channel w/ 3' High Berm	Proposed	SPD1a

Street D Flood Control Facilities			
Facility ID	Facility Description	Hydrologic Condition	Contributing Source
D1	Proposed 54" RCP	Proposed	DBH
D3	Proposed 60" RCP	Proposed	DBH
D4a	Proposed 18" RCP	Proposed	DBH
D4b	Proposed 5" Type CM2 Inlet	Proposed	DBH
D5	Secret 4 Detention Basin with a 54" Outlet (Facility D1)	Proposed	DBH
D6	Proposed 60" RCP	Proposed	DBH
D7	Emergency Overflow 25' Wide Channel w/ 3' High Berm	Proposed	DBH

Hydraulic Analyses Flow Summary						
Cross Section	Section Type	Q (cfs)	Slope (%)	Depth (ft)	Velocity (ft/s)	DxV
D1	Full Street	2	3.50	0.23	3.0	0.7
SP1	Full Street	52	1.90	0.59	4.9	2.9
SP2	Full Street	37	1.90	0.54	4.4	2.4
SP4	Full Street	2.5	0.60	0.36	1.6	0.6
GC1 (10-Year)	Half Street	4	0.50	0.41	2.1	0.8
GC2 (100-Year)	Half Street	16	0.50	0.62	2.7	1.7
GC2 (10-Year)	Half Street	2	2.36	0.28	3.0	0.8
GC2 (100-Year)	Half Street	4	2.36	0.34	3.4	1.2

LEGEND

- FUTURE COMMERCIAL SITE BOUNDARY
- EXISTING DRAINAGE FACILITY
- PROPOSED DRAINAGE FACILITY
- ESTIMATED FUTURE DRAINAGE FACILITY
- FLOW DIRECTION
- FLOWMASTER SECTION
- △ ID FACILITY ID

SCALE

0 60 120

1"=60' FEET

EXHIBIT I

SHEET 1 OF 1

SLATER HANIFAN GROUP

CONSULTING ENGINEERS & PLANNERS

5740 S. ARVILLE STREET #216, LAS VEGAS, NV 89118

PHONE (702) 284-5300 FAX (702) 284-5399

NINETY-FIVE MANAGEMENT, LLC

SKYE CANYON PHASE 3 INFRASTRUCTURE

DRAINAGE FACILITIES & HYDRAULIC SUMMARY MAP

DATE: JULY 2016

DRAFTER: CWB

DESIGNER: CWB

CHECKED: SMJ

PROJECT NO. OLY1602.000

	T1 SKYE CANYON PHASE 3				T2 STORM DRAIN SYSTEM AT GRAND CANYON LOW POINT (CULVERT CROSSING)				T3 14' W X 5' H RCB DISCHARGING TO NATURAL WASH (FUTURE CONDITION)				T4 14' W X 5' H RCB DISCHARGING TO NATURAL WASH (FUTURE CONDITION)				FUT. WSW			
SO	998.000	2748.980	1		998.000	2748.980	1		998.000	2748.980	1		998.000	2748.980	1					
R	999.000	2749.000	1		999.000	2749.000	1		999.000	2749.000	1		999.000	2749.000	1					
TS	1007.000	2749.090	5		1007.000	2749.090	5		1007.000	2749.090	5		1007.000	2749.090	5					
JX	1017.000	2749.190	5		1017.000	2749.190	5		1017.000	2749.190	5		1017.000	2749.190	5					
WX	1017.00	2749.19	3		1017.00	2749.19	3		1017.00	2749.19	3		1017.00	2749.19	3					
R	1033.50	2749.24	3		1033.50	2749.24	3		1033.50	2749.24	3		1033.50	2749.24	3					
JX	1033.50	2749.24	3		1033.50	2749.24	3		1033.50	2749.24	3		1033.50	2749.24	3					
R	1081.00	2749.46	3		1081.00	2749.46	3		1081.00	2749.46	3		1081.00	2749.46	3					
TS	1094.00	2749.50	72		1094.00	2749.50	72		1094.00	2749.50	72		1094.00	2749.50	72					
R	1120.00	2749.89	72		1120.00	2749.89	72		1120.00	2749.89	72		1120.00	2749.89	72					
R	1189.00	2752.05	72		1189.00	2752.05	72		1189.00	2752.05	72		1189.00	2752.05	72					
R	2365.00	2787.32	72		2365.00	2787.32	72		2365.00	2787.32	72		2365.00	2787.32	72					
SH	2365.00	2787.32	72		2365.00	2787.32	72		2365.00	2787.32	72		2365.00	2787.32	72					
CD	1	1	0		1	1	0		1	1	0		1	1	0					
CD	2	3	0		2	3	0		2	3	0		2	3	0					
CD	3	3	0		3	3	0		3	3	0		3	3	0					
CD	4	1	0		4	1	0		4	1	0		4	1	0					
CD	5	1	0		5	1	0		5	1	0		5	1	0					
CD	54	4	1		54	4	1		54	4	1		54	4	1					
CD	60	4	1		60	4	1		60	4	1		60	4	1					
CD	66	4	1		66	4	1		66	4	1		66	4	1					
CD	72	4	1		72	4	1		72	4	1		72	4	1					
Q																				

CARD	SECT	CHN	NO	AVE	PIER	HEIGHT 1	BASE	ZL	ZR	INV	Y(1)	Y(2)	Y(3)	Y(4)	Y(5)	Y(6)	Y(7)	Y(8)	Y(9)	Y(10)
WATER SURFACE PROFILE - CHANNEL DEFINITION LISTING																				

	0	.000	4,000	20,000	1,000	1,000	.00
0000000000	1	.000	5,000	6,000	.000	.000	.00
0000000000	3	.000	5,000	14,000	.000	.000	.00
0000000000	3	.000	5,000	20,000	3,000	.000	.00
0000000000	4	.000	5,000	30,500	10,000	10,000	.00
0000000000	5	.000	4,500				.00
0000000000	54	.000	5,000				.00
0000000000	60	.000	5,500				.00
0000000000	66	.000	6,000				.00
0000000000	72	.000					.00

W S P G W
WATER SURFACE PROFILE - TITLE CARD LISTING

SKYE CANYON PHASE 3

STORM DRAIN SYSTEM AT GRAND CANYON LOW POINT (CULVERT CROSSING)

14'W x 5'H RCB DISCHARGING TO NATURAL WASH (FUTURE CONDITION)

WATER SURFACE PROFILE - ELEMENT CARD LISTING

[illegible][illegible]

	-WARNING
	-WARNING
	-WARNING
	.00
THE ABOVE ELEMENT CONTAINED AN INVERT ELEV WHICH WAS NOT GREATER THAN THE PREVIOUS INVERT ELEV -WARNING	
THE ABOVE ELEMENT CONTAINED AN INVERT ELEV WHICH WAS NOT GREATER THAN THE PREVIOUS INVERT ELEV -WARNING	
THE ABOVE ELEMENT CONTAINED AN INVERT ELEV WHICH WAS NOT GREATER THAN THE PREVIOUS INVERT ELEV -WARNING	

ELEMENT NO	IS A	REACH	U/S DATA	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H
9	IS A	TRANSITION	U/S DATA	1081.000	2749.460	3	.013	.000	.000	0	
9	IS A	TRANSITION	U/S DATA	1094.000	2749.500	72	.013	.000	.000		

FUT.EDT

ELEMENT NO	10 IS A REACH	U/S DATA	STATION	INVERT	SECT	W S P G W	WATER SURFACE PROFILE - ELEMENT CARD LISTING	RADIUS	ANGLE	ANG PT	MAN H	PAGE NO
ELEMENT NO 10	IS A REACH	U/S DATA	1120.000	2749.890	72	*	N .013	.000	.000	-45.000	0	3
ELEMENT NO 11	IS A REACH	U/S DATA	1189.000	2752.050	72	*	N .013	.000	.000	-37.000	0	
ELEMENT NO 12	IS A REACH	U/S DATA	2365.000	2787.320	72	*	N .013	.000	.000	.000	0	
ELEMENT NO 13	IS A SYSTEM HEADWORKS	U/S DATA	2365.000	2787.320	72	*						
			2365.000	2787.320	72							

W S ELEV
.000

SKYE CANYON PHASE 3

STORM DRAIN SYSTEM AT GRAND CANYON LOW POINT (CULVERT CROSSING)
14' W X 5' H RCB DISCHARGING TO NATURAL WASH (FUTURE CONDITION)

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT or I.D.	Base Wt	ZL	NO Wth Prs/Pip
L/Elem	Ch Slope						HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch
*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****
998.000	2748.980	3.071	2752.051	695.00	9.81	1.49	2753.55	.00	3.17	26.14	4.000	20.000	1.00	0 .0
1.000	.0200					.0152	.02	3.07	1.05	2.87	.035	.00	1.00	TRAP
999.000	2749.000	3.168	2752.168	695.00	9.47	1.39	2753.56	.00	3.17	26.34	4.000	20.000	1.00	0 .0
TRANS STR	.0113					.0107	.09	3.17	1.00		.042	.00	1.00	TRAP
1007.000	2749.090	4.840	2753.930	695.00	1.82	.05	2753.98	.00	2.01	127.29	5.000	30.500	****	0 .0
JUNCT STR	.0100					.0001	.00	4.84	.19		.015	.00	****	TRAP
1017.000	2749.190	4.743	2753.933	671.00	1.82	.05	2753.98	.00	1.98	125.35	5.000	30.500	****	0 .0
HYDRAULIC JUMP														
1017.000	2749.190	2.048	2751.238	671.00	23.40	8.50	2759.74	.00	4.15	14.00	5.000	14.000	.00	0 .0
16.500	.0030					.0235	.39	2.05	2.88	4.06	.013	.00	.00	BOX
1033.500	2749.240	2.004	2751.244	671.00	23.92	8.88	2760.13	.00	4.15	14.00	5.000	14.000	.00	0 .0
JUNCT STR	.0000					.0347	.00	2.00	2.98		.013	.00	.00	BOX
1033.500	2749.240	1.352	2750.592	499.00	26.37	10.80	2761.39	.00	3.40	14.00	5.000	14.000	.00	0 .0
3.015	.0046					.0455	.14	1.35	4.00	2.86	.013	.00	.00	BOX
1036.515	2749.254	1.343	2750.597	499.00	26.53	10.93	2761.53	.00	3.40	14.00	5.000	14.000	.00	0 .0
22.907	.0046					.0496	1.14	1.34	4.03	2.86	.013	.00	.00	BOX
1059.423	2749.360	1.281	2750.641	499.00	27.83	12.02	2762.67	.00	3.40	14.00	5.000	14.000	.00	0 .0
21.577	.0046					.0576	1.24	1.28	4.33	2.86	.013	.00	.00	BOX

SKYE CANYON PHASE 3

STORM DRAIN SYSTEM AT GRAND CANYON LOW POINT (CULVERT CROSSING)
14' W X 5' H RCB DISCHARGING TO NATURAL WASH (FUTURE CONDITION)

Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT or I.D.	Base Wt	ZL	NO Wth Prs/Pip
L/Elem	Ch Slope						HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch
*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****

1081.000	2749.460	1.221	2750.681	499.00	29.19	13.23	FUT OUT 2763.91	.00	3.40	14.00	5.000	14.000	.00	0	.0
TRANS STR	-.0031	-	-	-	-	-.0453	.59	1.22	4.65	-	.013	.00	.00	BOX	
1094.000	2749.500	3.679	2753.179	499.00	27.46	11.71	2764.88	.00	5.67	5.84	6.000	.000	.00	1	.0
26.000	.0150	-	-	-	-	.0295	.77	3.68	2.74	-	.013	.00	.00	PIPE	
1120.000	2749.890	3.623	2753.513	499.00	27.96	12.14	2765.65	.00	5.67	5.87	6.000	.000	.00	1	.0
69.000	.0313	-	-	-	-	.0300	2.07	3.62	2.83	-	.013	.00	.00	PIPE	
1189.000	2752.050	3.635	2755.685	499.00	27.85	12.04	2767.73	.00	5.67	5.86	6.000	.000	.00	1	.0
331.528	.0300	-	-	-	-	.0297	9.83	3.64	2.81	-	.013	.00	.00	PIPE	
1520.528	2761.993	3.651	2765.644	499.00	27.70	11.91	2777.56	.00	5.67	5.86	6.000	.000	.00	1	.0
421.307	.0300	-	-	-	-	.0278	11.70	3.65	2.78	-	.013	.00	.00	PIPE	
1941.835	2774.628	3.802	2778.430	499.00	26.41	10.83	2789.26	.00	5.67	5.78	6.000	.000	.00	1	.0
153.967	.0300	-	-	-	-	.0246	3.79	3.80	2.57	-	.013	.00	.00	PIPE	
2095.802	2779.246	3.963	2783.209	499.00	25.18	9.85	2793.06	.00	5.67	5.68	6.000	.000	.00	1	.0
89.426	.0300	-	-	-	-	.0219	1.96	3.96	2.38	-	.013	.00	.00	PIPE	
2185.228	2781.928	4.135	2786.063	499.00	24.01	8.95	2795.01	.00	5.67	5.55	6.000	.000	.00	1	.0
60.059	.0300	-	-	-	-	.0195	1.17	4.14	2.19	-	.013	.00	.00	PIPE	
2245.287	2783.729	4.320	2788.050	499.00	22.89	8.14	2796.19	.00	5.67	5.39	6.000	.000	.00	1	.0
42.914	.0300	-	-	-	-	.0175	.75	4.32	2.01	-	.013	.00	.00	PIPE	3

W S P G W - CIVILDESIGN Version 1704
 Program Package Serial Number: 1704

SKYE CANYON PHASE 3
 WATER SURFACE PROFILE LISTING

Date: 8-29-2016 Time: 8:11:54

STORM DRAIN SYSTEM AT GRAND CANYON LOW POINT (CULVERT CROSSING)
 14' W X 5' H RCB DISCHARGING TO NATURAL WASH (FUTURE CONDITION)

***** (FUTURE CONDITION) *****															*****	
Station	Invert Elev	Depth (FT)	Water Elev	Q (CFS)	Vel (FPS)	Vel Head	Energy Grd.El.	Super Elev	Critical Depth	Flow Top Width	Height/Dia.-FT or I.D.	Base Wt	ZL	No Wth Prs/Pip		
L/Elem	Ch Slope					SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	X-Fall	ZR	Type Ch		
*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****	*****		
2288.201	2785.017	4.522	2789.539	499.00	21.83	7.40	2796.94	.00	5.67	5.17	6.000	.000	.00	1 .0		
31.502	.0300	-	-	-	-	.0157	.49	4.52	1.83	3.63	.013	-	-	PIPE		
2319.703	2785.961	4.744	2790.706	499.00	20.81	6.73	2797.43	.00	5.67	4.88	6.000	.000	.00	1 .0		
22.942	.0300	-	-	-	-	.0142	.33	4.74	1.65	3.63	.013	-	-	PIPE		
2342.645	2786.649	4.993	2791.643	499.00	19.84	6.11	2797.76	.00	5.67	4.48	6.000	.000	.00	1 .0		
15.521	.0300	-	-	-	-	.0130	.20	4.99	1.48	3.63	.013	-	-	PIPE		
2358.166	2787.115	5.285	2792.400	499.00	18.92	5.56	2797.96	.00	5.67	3.89	6.000	.000	.00	1 .0		

X = CURVES CROSSING OVER
B = BRIDGE ENTRANCE OR EXIT
Y = WALL ENTRANCE OR EXIT

2. STATIONS FOR POINTS AT A JUMP MAY NOT BE PLOTTED EXACTLY

FUT.OUT

APPENDIX C

Electronic Copy of Study (CD)

APPENDIX D

Revised Storm Drain Plan & Profile