

TECHNICAL DRAINAGE STUDY
ADDENDUM #2

Skye Canyon Infrastructure Phase 3A
City of Las Vegas, Nevada


Job No.: OLY1609.000
Date: August 2018

Prepared By:

Slater Hanifan Group, Inc.
5740 S. Arville Street, Suite 216
Las Vegas, Nevada 89118
Phone: 702-284-5300 • Fax: 702-284-5399

Prepared For:

Ninety-Five Management, LLC
11411 Southern Highlands Parkway, Suite 300
Las Vegas, NV 89141
Phone: 702-220-6565 • Fax: 702-220-6566



Lant Leavitt, P.E.
NV Professional Engineer No. 18287

Assisted by: Erick Mata, E.I.

HYDROLOGIC CRITERIA AND DRAINAGE DESIGN MANUAL
DRAINAGE STUDY INFORMATION FORM

Name of Development: Skye Canyon – Phase 3A Infrastructure (Addendum #2) Date: August 2018
Location of Development: a) Descriptive (Cross Streets): North/South: Skye Village Road
East/West: Grand Canyon Drive
b) Section: 7 Township: 19 South Range: 60 East
c) APN: 125-07-201-007 and a portion of 125-07-101-009


Name of Owner/Developer: M F Land, LLC / Ninety-Five Management, LLC
Telephone No.: 702-220-6565 Fax No.: 702-220-6566 E-mail Address: mbolduc@olympiacompanies.com
Address: 11411 Southern Highlands Parkway, Suite 300; Las Vegas, NV 89141

Contact Person – Name: Lant Leavitt, P.E. Telephone No.: 702-284-5300
*E-mail Address: lleavitt@shg-inc.com Fax No.: 702-284-5399
Firm: Slater Hanifan Group
Address: 5740 S. Arville Street, Suite 216; Las Vegas, NV 89118

Type of Land Development/Land Disturbance Process:

☐ Rezoning	☐ Subdivision Map	☐ Clearing and grading Only
☐ Parcel Map	☐ Planned Unit Development	☒ Other (Please specify below)
☐ Large Parcel Map	☐ Building Permit	☐ Roadway & Storm Drain Infrastructure

1. Total Owned Land Area: At Site: 665 Acres Being Developed/Disturbed: 20 Acres +/-
2. Is a portion or all of the subject property located in a FEMA Flood Hazard Area? ☐ Yes** ☒ No
3. Is the property bordered or crossed by an existing or proposed Clark County Regional Flood Control District Master Planned Facility? ☒ Yes** ☐ No
4. Proposed type of development (Residential, Commercial, Etc.): Roadway & Storm Drain Infrastructure
5. Approximate upstream land area which drains to the subject site: 1800 acre +/-
6. Has the site drainage been evaluated in the past? ☒ Yes** ☐ No If yes, please identify documentation: Master Drainage Study for Skye Canyon Update #4 (SHG, DS4420)
7. If known, please briefly identify the proposed discharge point(s) of runoff from the site: Skye Village Road thru MOHU 0036, And Minor flows thru local facilities discharging to desert shrub east of the project site.
8. Briefly describe your proposed schedule for the subject project: ASAP Upon Substantial Completion of Detention Basin 2 Facilities Phase 3A – Roadway Infrastructure per this TDS; Future Phase 3A Residential Subdivisions to follow by separate TDS.



Engineer's Seal

Submit this form as part of the required drainage study to the local entity which has jurisdiction over The subject property. This form may provide sufficient information to serve as the Conceptual Drainage Study.

***Newly Required Field**

**Review and concurrence of the Clark County Regional Flood Control District is required

Revision	Date

Local Entity File No. _____

REFERENCE: **SHG Job No. OLY1609.000**

STANDARD FORM 1

Updated 05/01/2008



OLY1609.000

August 1, 2018

Albert Sung, P.E.
Flood Control Project Engineer
City of Las Vegas Department of Public Works
333 N. Rancho Drive
Las Vegas, Nevada 89106

Subject: Addendum No.2 to the Technical Drainage Study for Skye Canyon Infrastructure Phase 3A (CLV DS4931)

Dear Mr. Sung:

This letter is submitted in response to comments contained in the May 24, 2018 review memorandum, regarding the above referenced project. A copy of the City of Las Vegas (CLV) Department of Public Works comment letter has been provided in Appendix A.

The comments have been individually addressed as follows:

1. **Comment:** *The site is adjacent to or crosses an existing or proposed Clark County Regional Flood Control District (CCRFCD) master planned facility. Therefore, CCRFCD concurrence is required prior to final approval of the drainage study.*

Response: Noted. The study will be submitted for concurrence to CCRFCD upon conditional approval from the city.

2. **Comment:** *The subject Skye Canyon Phase 3A Infrastructure Drainage Study will not be approved prior to the approval of the Skye Canyon Detention Basin 2 Technical Drainage Study.*

Response: Conditional approval of Skye Canyon Detention Basin 2 was received by the City on June 14, 2018. Construction is expected to begin August 2018.

3. **Comment:** *Skye Canyon Phase 3A onsite developments are to be flood protected by Detention Basin 2. No occupancy permits within onsite Phase 3A will be issued prior to the substantial completion of Detention Basin 2.*

Response: Noted.

4. **Comment:** *The future MPU facility within Skye Village Road north of the Skye Village/Grand Canyon/Iron Mountain intersection to the proposed MPU facility at the Kyle Canyon interchange area shall be substantially complete before occupancy of residential Units beyond Phase 3A, 3B and 3C. This includes residential development within Phases 4 & 6 and the development of Phase 5 as shown on the Development Phasing Exhibit dated 12/4/2017.*

Response: Noted.

5. **Comment:** *Revise the Phase 3A Exhibits I & G to reflect the proposed interim MPU facility interception Berm/Levee shown on the Moccasin Rd. CCRFCD Flood Control Facility — US95/Kyle Canyon Rd Interchange to Moccasin Rd. (Skye Canyon Developer Funded) plans. Show the connection between the Grand Canyon improvements and this facility design. Provide access road and gate to the berm/levee improvements. Coordinate design between these two facilities.*

Response: Exhibit I is revised to show interim Moccasin Berm facility, see Appendix B. Exhibit G is also revised to show facility, and flow arrows/text are added to clarify that once berm is constructed, all flow at this location will be routed north to the Moccasin Facility. Access road and gate are provided, see Sheet D-04.

6. **Comment:** *Exhibit I shows the future abandonment of Phase 3A storm drain improvements (P15 & P33A) once the Ultimate MPU facilities are in place. The City requires that facilities be removed from the roadway if they are no longer needed. These facilities will need included in the Maintenance Bond.*

Response: Noted.

7. **Comment:** *Flood Control understands that the new Skye Canyon Master Plan Amendment (MPA) is being included as a part of the 2018 MPU process. Any changes not incorporated in the 2018 MPU must be approved by City of Las Vegas and Clark County Regional Flood Control District (CCRFCD) and shall be adopted by the City of Las Vegas City Council prior to the final approval of the subject improvement plans.*

Response: Noted.

8. **Comment:** *The Design Report for Moccasin Road CCRFCD Flood Control Facility (US95 / Kyle Canyon Road Interchange to CCRFCD Facility LVUP 1076/1077) must be conditionally approved (90% submittal) prior to the final approval of the subject improvement plans. The connection to these MPU facilities shall be shown on the Grand Canyon Improvement plans.*

Response: Noted. The Moccasin Facility catcher's mitt is shown on Sheet D-04. Access is provided to the facility via a fenced access road from Grand Canyon Drive.

9. **Comment:** *The subject Phase 3A Infrastructure Drainage Study addresses the included street improvements of Skye Village Road, Skye Park Drive, Street "E", Grand Canyon Drive, culvert crossings and storm drain systems with the streets. Technical drainage studies will be required for the future onsite parcels as they develop.*

Response: Acknowledged.

10. **Comment:** *Since the streets network and the associated storm drain facilities will eventually be accepted by the City of Las Vegas, the engineer/developer must coordinate with City of Las Vegas Streets & Sanitation Department for their review and approval prior to the final approval of the improvement plans.*

Response: Noted. Coordination with CLV Streets & Sanitation has taken place and the access road along the west side of the improvements is designed accordingly.

11. **Comment:** *The proposed storm drain system in Grand Canyon does not show a connection between Skye Park Drive (P1) and the storm drain at the linear park (P2) as per **Exhibit I**. These flows are shown as combining and the system shall be extended to accommodate the flow. Review and revise the storm drain segment to account for the flow and update the WSPG analysis accordingly.*

Response: The system in Skye Canyon Park Drive (P1) and the linear park (P2) are not intended to connect and will remain as separate models. This matches the concept approved in the master drainage study (MDS). Facilities Map Exhibit I shows the future facility (green linework, label F1) on the north half of Grand Canyon Drive from Skye Park Drive to the linear park and the ultimate connection east to US 95. In addition to matching the MDS, these flow patterns are necessary to avoid increasing flows at Brent Lane in the interim condition.

12. **Comment:** *Structural plans for the storm drain improvements must be submitted for review by Flood Control and the Building Department. Provide a soil report, structural calculations and specifications, wet stamped structural sets and a grading plan to the City of Las Vegas Building Department for processing (call Building Department to confirm their submittal requirements). The engineer must provide a copy of Building Department approval of the structures to City Flood Control Section prior to the final acceptance of the improvement plans. The structural approval is also required to be submitted to CCRFCD prior to concurrence. Flood Control recommends that the Structural Plans be included with the next submittal.*

Response: Acknowledged. A copy of structural plans is included with this submittal.

13. **Comment:** *Provide a junction structure detail for the RCA & 72" RCP that also includes the RCA Plug detail.*

Response: RCA junction structure is shown on Structural Sheet S1.13. Plug detail is shown on Structural Sheet S3.10.

14. **Comment:** *Provide connection details for lateral and main line structures connection the RCA's and RCB's as a part of the Structural details.*

Response: Connection details are provided, see overall plan on Structural Sheet S2.10 for reference to individual details.

15. **Comment:** *The proposed RCA's shall provide the required 5-foot minimum stem wall height before the arch section. Flood Control requests that the RCA plans be included with the next submittal.*

Response: RCA structural plans are included with this submittal. The proposed RCA's provide the required 5-foot minimum stem wall height. See detailed sections on Structural Sheet S4.10.

16. **Comment:** *The project proposed to build temporary drainage facilities including drainage berms/swales over the Phase 3A site and along the west side of Skye Village Road. Prior to the final plans approval, the developer must complete a **Maintenance and Liability Agreement** for the interim drainage improvements and post a minimum maintenance bond of \$50,000 or 50-percent of the construction cost for the improvements, whichever is greater. The engineer must submit an estimate of the quantities for construction the facility and an*

exhibit that adequately shows the location and limits of the drainage facilities to City Flood Control for approval. Once the drainage study is conditionally approved, the engineer/developer should contact the City's Land Development Section (702-229-6371) to begin the agreement process.

In order for the maintenance bond to be released in the future, a drainage update/letter will be required to justify that the berms/swales are no longer necessary and can be removed.

Response: Noted. Client may consider breaking maintenance bond up into two or more separate bonds so release isn't held up by a parcel that is anticipated to be slower to develop.

17. **Comment:** *Exhibit G: "DIV1" incorrectly shows only 40 cfs. Per "CP3" and "Facility P15", the flow is 422 cfs. Review and revise accordingly.*

Response: DIV1 represents 40 cfs entering the MPU facility at this location via a lateral from the west. The majority of mainline flow at this location comes from the south in a 60" RCP/ 8'x5' RCB conveying flow from CP8 (366 cfs) and PARK (36 cfs). The combination of these flows is the mainline flow at this location (CP3) of 422 cfs.

18. **Comment:** *Include utility crossings on the storm drain plans. Provide a complete set of Phase 3A improvement plans that include the Utility and Roadway plans for review to verify improvement and separation requirements.*

Response: Utility crossings are included on the storm drain plans. Utility and roadway plans will be provided at the improvement plan review level. Note that although proposed sewer and storm drain have similar profiles in Grand Canyon Drive, proposed sewer stubs are shown and do not conflict with proposed storm drain.

19. **Comment:** *The interim channels adjacent to the infrastructure roadways are the Maintenance responsibility of the Master Developer.*

Response: Noted.

20. **Comment:** *The area grading shown on Sheet GR-02 adjacent to Grand Canyon Drive appears to show the interim channel draining directly towards Grand Canyon Drive. Review and revise the grading to provide positive drainage away from the road improvements and toward the "Catcher's Mitt" Berm/Levee with the MPU improvements.*

Response: A riprap berm is provided at end of earthen channel to direct water away from Grand Canyon Drive and toward the Moccasin Catcher's Mitt Berm. See HEC-RAS analysis included in Appendix C.

21. **Comment:** *Review and revise the Lateral Sheets to show the proposed pipe material. Some profiles show multiple pipe materials being used.*

Response: Proposed pipe materials are called out on lateral sheets. All storm drain laterals are reinforced concrete pipe, except where the water district requires PVC 900 pipe due to water line crossings.

22. **Comment:** *The lateral profiles need to specify the required separation mitigation between sewer, water, and storm drain facilities.*

Response: Vertical clearances are called out where sewer and water lines cross storm drain facilities. For water lines beneath storm drains, a minimum vertical separation of six inches is required and storm drain is constructed of water quality pipe, per UDACS 2.22.02 B2 and B3a. For sewer lines beneath storm drain, a minimum vertical separation of six inches is required per DCSWCS SD-21. These clearances/mitigations are consistent with recent projects SHG has coordinated with utilities.

23. **Comment:** *Provide cut-off wall at the headwall structures and at the end of the concrete aprons.*

Response: Cutoff walls are provided on both upstream and downstream sides of concrete apron to protect against erosion. The cutoff wall on the downstream lines up with proposed culvert headwall/end section to protect culvert against erosion.

24. **Comment:** **Grand Canyon Drive Improvement Plans:**

Sheet D-03: Second Request. *Provide a nominal drop inlet to the proximity of SDMH #6.*

Sheet D-03 and D-04: *Extend the storm drain system between Skye Park Drive and linear park.*

Sheet D-05: *Show the proposed catcher's mitt channel/berm on the plan.*

Sheet D-06: *Response to previous comment was to upsize the original storm drain to 8'x4' RCB. However, the City requires 5'-min height in RCB for maintenance purpose. Consider 7'x5' or 8'x5' RCB.*

Response: Sheet D-03: Nominal drop inlet added that discharges to SDMH #6.

Sheet D-03 and D-04: Per the master drainage study, these facilities are not intended to be connected, see additional information in response to Comment #11.

Sheet D-05: Proposed catcher's mitt ties in east of Sheet D-05 and is shown on Sheet D-04.

Sheet D-06: 8'x4' RCB in Iron Mountain Road is revised to a 7'x5' RCB to provide the required 5' minimum height. See Appendix C for updated WSPG model.

25. **Comment:** **Sheet D-19: Lateral Profile 6:** *The slope of the access road (0.6% shown) and the riprap pad size ($D_{50} = 8"$ and $T = 16"$) does not match Sheet D-04. Review and revise accordingly.*

Response: Access road slope (0.8%) and Riprap size/thickness ($D_{50}=8"$, $T=16"$) revised to match between plan and profile.

The revised plan, profile and detail sheets adopting the revisions addressed in this letter have been included in Appendix D. If you have any questions or require additional information, please do not hesitate to contact us at 702-284-5300.

Respectfully Submitted,

SLATER HANIFAN GROUP



Lant Leavitt, P.E.
Flood Control Division

cc: Mark Failla, P.E., CFM – SHG
Jerrod Ratcliffe, P.E. – SHG

APPENDIX

Appendix A CLV Comment Letter

Appendix B Revised Drainage Exhibits

Appendix C Hydraulic Computations

Appendix D CD of Electronic Files & Revised Improvement Plans

APPENDIX A

CLV Comment Letter

CITY OF LAS VEGAS		DATE:
INTER-OFFICE MEMORANDUM		May 24, 2018
TO: Land Development Services Department of Building & Safety		FROM: Albert Sung, P.E. Flood Control Project Engineer Department of Public Works
SUBJECT:	Drainage Study for:	COPIES TO:
	Skye Canyon – Phase 3A Infrastructure	Slater Hanifan Group
Cross Streets:	Skye Village Road & Grand Canyon Drive	M F Land LLC / Ninety-Five Management LLC
File Number:	F:\Depot\DSMemos\DS4931B.doc	Bart Anderson, P.E., DevCo
Parcel Number:	125-07-201-007 & Portion of 125-07-101-009	CCRFC
Zoning Action:		
FEMA Flood Zone	YES	NO X
Proposed Storm Drain	YES X	NO

HISTORY	DATE RECEIVED	DATE REVIEWED	COMMENTS	REVIEW FEES	FEES PAID Payment Trn #
1 st Submittal	11/6/2017	1/22/2018	Not Approved	\$400.00	491017: \$400
2 nd Submittal	4/18/2018	5/24/2018	See Comments Below	\$400.00	495171: \$400
TOTAL FEES (LDDRS):				\$800.00	----

REMARKS: The complex nature of these storm drain infrastructure improvement plans needs to include a complete set of plans with the next submittal.

The Drainage Study for the subject project has been reviewed and:

	is approved subject to conformance to all City standards and the following conditions:
X	must be resubmitted or supplemented including the following:
	is conditionally approved subject to Clark County Regional Flood Control District concurrence.
	is conditionally approved subject to Clark County Public Works Department concurrence.

1. The site is adjacent to or crosses an existing or proposed *Clark County Regional Flood Control District* (CCRFC) master planned facility. Therefore, CCRFC concurrence is required prior to final approval of the drainage study.
2. The subject *Skye Canyon Phase 3A Infrastructure Drainage Study* will not be approved prior to the approval of the *Skye Canyon Detention Basin 2 Technical Drainage Study*.
3. *Skye Canyon Phase 3A* onsite developments are to be flood protected by *Detention Basin 2*. No occupancy permits within onsite *Phase 3A* will be issued prior to the substantial completion of *Detention Basin 2*.
4. The future MPU facility within Skye Village Road north of the Skye Village/Grand Canyon/Iron Mountain intersection to the proposed MPU facility at the Kyle Canyon interchange area shall be substantially complete before occupancy of residential Units beyond Phase 3A, 3B and 3C. This includes residential development within Phases 4 & 6 and the development of Phase 5 as shown on the Development Phasing Exhibit dated 12/4/2017.

5. Revise the Phase 3A **Exhibits I & G** to reflect the proposed interim MPU facility interception Berm/Levee shown on the *Moccasin Rd. CCRFCD Flood Control Facility – US95/Kyle Canyon Rd Interchange to Moccasin Rd. (Skye Canyon Developer Funded) plans*. Show the connection between the Grand Canyon improvements and this facility design. Provide access road and gate to the berm/levee improvements. Coordinate design between these two facilities.
6. **Exhibit I** shows the future abandonment of Phase 3A storm drain improvements (P15 & P33A) once the Ultimate MPU facilities are in place. The City requires that facilities be removed from the roadway if they are no longer needed. These facilities will need included in the Maintenance Bond.
7. Flood Control understands that the new *Skye Canyon Master Plan Amendment (MPA)* is being included as a part of the 2018 MPU process. Any changes not incorporated in the 2018 MPU must be approved by *City of Las Vegas* and *Clark County Regional Flood Control District (CCRFCD)* and shall be adopted by the *City of Las Vegas City Council* prior to the final approval of the subject improvement plans.
8. The *Design Report for Moccasin Road CCRFCD Flood Control Facility (US95 / Kyle Canyon Road Interchange to CCRFCD Facility LVUP 1076/1077)* must be conditionally approved (90% submittal) prior to the final approval of the subject improvement plans. The connection to these MPU facilities shall be shown on the Grand Canyon Improvement plans.
9. The subject *Phase 3A Infrastructure Drainage Study* addresses the included street improvements of *Skye Village Road, Skye Park Drive, Street "E", Grand Canyon Drive*, culvert crossings and storm drain systems with the streets. Technical drainage studies will be required for the future onsite parcels as they develop.
10. Since the streets network and the associated storm drain facilities will eventually be accepted by the **City of Las Vegas**, the engineer/developer must coordinate with *City of Las Vegas Streets & Sanitation Department* for their review and approval prior to the final approval of the improvement plans.
11. The proposed storm drain system in Grand Canyon does not show a connection between Skye Park Drive (P1) and the storm drain at the linear park (P2) as per **Exhibit I**. These flows are shown as combining and the system shall be extended to accommodate the flow. Review and revise the storm drain segment to account for the flow and update the WSPG analysis accordingly.
12. Structural plans for the storm drain improvements must be submitted for review by Flood Control and the Building Department. Provide a soil report, structural calculations and specifications, wet stamped structural sets and a grading plan to the *City of Las Vegas Building Department* for processing (call *Building Department* to confirm their submittal requirements). The engineer must provide a copy of *Building Department* approval of the structures to *City Flood Control Section* prior to the final acceptance of the improvement plans. The structural approval is also required to be submitted to CCRFCD prior to concurrence. Flood Control recommends that the Structural Plans be included with the next submittal.
13. Provide a junction structure detail for the RCA & 72" RCP that also includes the RCA Plug detail.
14. Provide connection details for lateral and main line structures connection the RCA's and RCB's as a part of the Structural details.
15. The proposed RCA's shall provide the required 5-foot minimum stem wall height before the arch section. Flood Control requests that the RCA plans be included with the next submittal.
16. The project proposed to build temporary drainage facilities including drainage berms/swales over the *Phase 3A* site and along the west side of *Skye Village Road*. Prior to the final plans approval the developer must complete a **Maintenance and Liability Agreement** for the interim drainage

improvements and post a minimum maintenance bond of \$50,000 or 50-percent of the construction cost for the improvements, whichever is greater. The engineer must submit an estimate of the quantities for construction the facility and an exhibit that adequately shows the location and limits of the drainage facilities to *City Flood Control* for approval. Once the drainage study is conditionally approved, the engineer/developer should contact the *City's Land Development Section* (702-229-6371) to begin the agreement process.

In order for the maintenance bond to be released in the future, a drainage update/letter will be required to justify that the berms/swales are no longer necessary and can be removed.

17. **Exhibit G:** "DIV1" incorrectly shows only 40 cfs. Per "CP3" and "Facility P15", the flow is 422 cfs. Review and revise accordingly.
18. Include utility crossings on the storm drain plans. Provide a complete set of Phase 3A improvement plans that include the Utility and Roadway plans for review to verify improvement and separation requirements.
19. The interim channels adjacent to the infrastructure roadways are the Maintenance responsibility of the Master Developer.
20. The area grading shown on Sheet GR-02 adjacent to Grand Canyon Drive appears to show the interim channel draining directly towards Grand Canyon Drive. Review and revise the grading to provide positive drainage away from the road improvements and toward the "Catchers Mitt" Berm/Levee with the MPU improvements.
21. Review and revise the Lateral Sheets to show the proposed pipe material. Some profiles show multiple pipe materials being used.
22. The lateral profiles need to specify the required separation mitigation between sewer, water, and storm drain facilities.
23. Provide cut-off wall at the headwall structures and at the end of the concrete aprons.

24. Grand Canyon Drive Improvement Plans:

Sheet D-03: *Second Request*: Provide a nominal drop inlet to the proximity of SDMH #6.

Sheet D-03 and D-04: Extend the storm drain system between Skye Park Drive and linear park.

Sheet D-05: Show the proposed catcher's mitt channel/berm on the plan.

Sheet D-06: Response to previous comment was to upsize the original storm drain to 8'x4' RCB. However, the City requires 5'-min height in RCB for maintenance purpose. Consider 7'x5' or 8'x5' RCB.

25. **Sheet D-19: Lateral Profile 6:** The slope of the access road (0.6% shown) and the riprap pad size ($D_{50} = 8"$ and $T = 16"$) does not match Sheet D-04. Review and revise accordingly.

NOTE: Please be advised that all land surface area disturbances over 1 acre or any area adjacent to a water way must submit to the *Nevada Division of Environmental Protection* a "Notice of Intent" to discharge that certifies a stormwater pollution prevention plan has been developed and is maintained on site; for inclusion in the Stormwater General Permit No. NVR100000. A phased construction unit in a contiguous subdivision is considered under construction until all stripped or disturbed surface areas have been covered by paving, building construction or planting. For more information, including forms and applications see <http://ndep.nv.gov/bwpc/storm01.htm> or call (775) 687-9429.

END OF REMARKS

ays

T/R/S: T19S/R60E/07

AREA G-07

APPENDIX B

Revised Drainage Exhibits

Proposed Condition Flow Rate Summary			
Concentration Points			
Basin/Concentration Point ID	Area (m ²)	Q _{10s} (cfs)	Q ₁₅ (cfs)
CP1			
Q = IRDEB + OF1 + OF2 + OF3 - DIV2 + OF4 - DIV1 + SVRT + SVR2	1.5	521	240
CP2a			
Q = 2.055 + STR1 + 2.048 + DIV2	<0.1	95	38
CP3			
Q = CB + *FARK + DIV1	1.1	422	211
CP3a			
Q = CP3 + Q26	1.2	458	226
CP4			
Q = STR2 + STR3 + 2.03 + 2.04b	1.1	68	33
CP5			
Q = CN4 + STR2 + STR3 + STR4	<0.1	127	62
CP6			
Q = IRDEB1 + WP20 + *WFF4 + *W5B4.4	0.9	156	100
CP7			
Q = CP6 + *W6.4A + *ON1D	1.0	208	122
CP8			
Q = CP7 + OF5	1.1	366	189
DBN			
Q = OUTFLOW	<0.1	87	34
WC5a			

Q = CP3a + DEN + ³ WSP3B + ³ WG3C + ³ WSP3D	1.2	588	285
CP10 Q = CP1 + 2.05A + OFF11	1.5	588	271
CP11 Q = OFF12 + CP5	<0.1	148	70
CP12 Q = WG3B + ³ WC7 + ³ WGRC1A	1.3	697	330
Refenced Concentration Points			

¹Referenced from the "Master Drainage Study Update No.4"

¹Referenced from the "Master Drainage Study Update No.4"


Subbasin ID	Q ₁₀₀ (cfs)	Area (acres)	100-yr Unit Flow (cfs/acre)
2.02a	43	14.39	3.0
2.02b	10	3.45	3.0
TOTAL	53	17.84	

1 (Q = 1/2 (SVR1))	5	0.58	0.35	1.96	0.7
2 (Q = 1/2 (SVR1) + Facility P18 Bypass)	7	0.58	0.38	2.14	0.8
3 (Q = 1/2 (SVR2) + Facility P20 Bypass)	13	0.58	0.46	2.38	1.1
4 (Q = 1/2 (SVR2) + Facility P23 Bypass)	17	0.58	0.51	2.43	1.2
5 (Q = STR2)	5	3.24	0.3	4.01	1.2
		1.56	0.33	2.94	1.0
6 (Q = 2.05b + STR1-Half Street Capacity)	9	2.3	0.42	4.44	1.9
*6 (Half Street Capacity)	22	2.3	0.56	4.78	2.7
*GC1 - (Q = STR2 + STR3)	14	2.73	0.46	5.15	2.4
*GC2 (Q = STR2 + STR3 + 1/3 (STR4))	16	1.48	0.53	4.03	2.1
*GC3 (Q = Facility P5 Bypass + 2/3 (STR4))	15	1.48	0.52	4.0	2.1

10YR (Q = SVR1 + SVR2)	15	0.58	0.48	2.4	1.2	21.5
---------------------------	----	------	------	-----	-----	------

Conservative Flow Utilized to represent the Entire Skive Village Road Alignment.

SEE EXHIBIT F FOR EXTENTS OF OFFSITE BASINS

[illegible]

DATE:	JULY 2018
DRAFTER:	ETM
DESIGNER:	ETM
CHECKED:	LL
PROJECT NO.	OLY1609.000

EXHIBIT G
SHEET 1 OF 1


APPENDIX C

Hydraulic Computations

Iron Mountain Road 7'x5' RCB

NOMOGRAPH - INLET CONTROL BOX CULVERT

FACILITY P31: Q=364 CFS



D	5.0
B	7.0
Q	364
Q/B	52
HW/D	1.5
HW	7.5

Revision	Date

T2 BY OLYMPIA COMPANIES

SO	1000.0002824.890	10	.013	2835.800
----	------------------	----	------	----------

R 1094.0002830.230 10 .013

CD	5	3	0	.000	9.000	18.000	.000	.000	.00
----	---	---	---	------	-------	--------	------	------	-----

CD	7	3	0	.000	4.000	8.000	.000	.000	.00
----	---	---	---	------	-------	-------	------	------	-----

CD	9	3	0	.000	9.000	15.000	.000	.000	.00
----	---	---	---	------	-------	--------	------	------	-----

CD	18	4	1	.000	1.500	.000	.000	.000	.00
----	----	---	---	------	-------	------	------	------	-----

CD	30	4	1	.000	2.500	.000	.000	.000	.00
----	----	---	---	------	-------	------	------	------	-----

CD	42	4	1	.000	3.500	.000	.000	.000	.00
----	----	---	---	------	-------	------	------	------	-----

CD	54	4	1	.000	4.500	.000	.000	.000	.00
----	----	---	---	------	-------	------	------	------	-----

CD	72	4	1	.000	6.000	.000	.000	.000	.00
----	----	---	---	------	-------	------	------	------	-----

CD	2	6	0	0.0	0.0	0.0	0.0	0.0	0.0
----	---	---	---	-----	-----	-----	-----	-----	-----

CD	4	6	0	0.0	0.0	0.0	0.0	0.0	0.0
----	---	---	---	-----	-----	-----	-----	-----	-----

PTS	9.000	7.280	8.500	7.500	8.000	7.630	7.520	7.740	7.000	7.840
-----	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

PTS	2.000	7.630	1.500	7.500	1.000	7.280	.510	6.870	.000	5.500
-----	-------	-------	-------	-------	-------	-------	------	-------	------	-------

PTS	221	.000	.000	8.000	.000	8.000	.010	8.000	5.000	7.900	5.570
-----	-----	------	------	-------	------	-------	------	-------	-------	-------	-------

PTS	5.000	6.950	4.000	7.000	3.000	6.950	2.000	6.800	1.000	6.530
-----	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

PTS	.000	.010
-----	------	------

PTS	9.000	8.280	8.500	8.500	8.000	8.630	7.520	8.740	7.000	8.840
-----	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

PTS	2.000	8.630	1.500	8.500	1.000	8.280	.510	7.870	.000	6.500
-----	-------	-------	-------	-------	-------	-------	------	-------	------	-------

PTS	421	.000	.000	8.000	.000	8.000	.010	8.000	6.000	7.900	6.570
-----	-----	------	------	-------	------	-------	------	-------	-------	-------	-------

PTS	5.000	7.950	4.000	8.000	3.000	7.950	2.000	7.800	1.000	7.530
-----	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

	000	010	020	030	040	050	060	070	080	090	100	110	120	130	140	150	160	170	180	190	200	210	220	230	240	250	260	270	280	290	300	310	320	330	340	350	360	370	380	390	400	410	420	430	440	450	460	470	480	490	500	510	520	530	540	550	560	570	580	590	600	610	620	630	640	650	660	670	680	690	700	710	720	730	740	750	760	770	780	790	800	810	820	830	840	850	860	870	880	890	900	910	920	930	940	950	960	970	980	990	1000	1010	1020	1030	1040	1050	1060	1070	1080	1090	1100	1110	1120	1130	1140	1150	1160	1170	1180	1190	1200	1210	1220	1230	1240	1250	1260	1270	1280	1290	1300	1310	1320	1330	1340	1350	1360	1370	1380	1390	1400	1410	1420	1430	1440	1450	1460	1470	1480	1490	1500	1510	1520	1530	1540	1550	1560	1570	1580	1590	1600	1610	1620	1630	1640	1650	1660	1670	1680	1690	1700	1710	1720	1730	1740	1750	1760	1770	1780	1790	1800	1810	1820	1830	1840	1850	1860	1870	1880	1890	1900	1910	1920	1930	1940	1950	1960	1970	1980	1990	2000	2010	2020	2030	2040	2050	2060	2070	2080	2090	2100	2110	2120	2130	2140	2150	2160	2170	2180	2190	2200	2210	2220	2230	2240	2250	2260	2270	2280	2290	2300	2310	2320	2330	2340	2350	2360	2370	2380	2390	2400	2410	2420	2430	2440	2450	2460	2470	2480	2490	2500	2510	2520	2530	2540	2550	2560	2570	2580	2590	2600	2610	2620	2630	2640	2650	2660	2670	2680	2690	2700	2710	2720	2730	2740	2750	2760	2770	2780	2790	2800	2810	2820	2830	2840	2850	2860	2870	2880	2890	2900	2910	2920	2930	2940	2950	2960	2970	2980	2990	3000	3010	3020	3030	3040	3050	3060	3070	3080	3090	3100	3110	3120	3130	3140	3150	3160	3170	3180	3190	3200	3210	3220	3230	3240	3250	3260	3270	3280	3290	3300	3310	3320	3330	3340	3350	3360	3370	3380	3390	3400	3410	3420	3430	3440	3450	3460	3470	3480	3490	3500	3510	3520	3530	3540	3550	3560	3570	3580	3590	3600	3610	3620	3630	3640	3650	3660	3670	3680	3690	3700	3710	3720	3730	3740	3750	3760	3770	3780	3790	3800	3810	3820	3830	3840	3850	3860	3870	3880	3890	3900	3910	3920	3930	3940	3950	3960	3970	3980	3990	4000	4010	4020	4030	4040	4050	4060	4070	4080	4090	4100	4110	4120	4130	4140	4150	4160	4170	4180	4190	4200	4210	4220	4230	4240	4250	4260	4270	4280	4290	4300	4310	4320	4330	4340	4350	4360	4370	4380	4390	4400	4410	4420	4430	4440	4450	4460	4470	4480	4490	4500	4510	4520	4530	4540	4550	4560	4570	4580	4590	4600	4610	4620	4630	4640</
--	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	--------

x

HEC-RAS Analysis - Earthen Channel to Catcher Mitt Berm

HEC-RAS HEC-RAS 5.0.4 April 2018
U.S. Army Corps of Engineers
Hydrologic Engineering Center
609 Second Street
Davis, California

```

X      X  XXXXXX      XXXX      XXXX      XX      XXXX
X      X  X          X      X      X      X      X      X
X      X  X          X          X      X      X      X
XXXXXXXX XXXX      X          XXX XXXX      XXXXXX      XXXX
X      X  X          X          X      X      X      X      X
X      X  X          X      X      X      X      X      X
X      X  XXXXXX      XXXX      X      X      X      X      XXXXX

```

PROJECT DATA

Project Title: Skye 3A - Iron Mt Wash Downstream

Project File : IronMtWash.prj

Run Date and Time: 7/31/2018 5:12:23 PM

Project in English units

PLAN DATA

Plan Title: Plan 02

Plan File : J:\OLY1609-000 Skye Canyon Phase 3a 3b 3c\Drainage\Technical
Study\Addendum 2\Calcs\Iron Mt Wash HEC-RAS\IronMtWash.p02

Geometry Title: FG

Geometry File : J:\OLY1609-000 Skye Canyon Phase 3a 3b
3c\Drainage\Technical Study\Addendum 2\Calcs\Iron Mt Wash HEC-
RAS\IronMtWash.g02

Flow Title : Qproposed

Flow File : J:\OLY1609-000 Skye Canyon Phase 3a 3b
3c\Drainage\Technical Study\Addendum 2\Calcs\Iron Mt Wash HEC-
RAS\IronMtWash.f01

Plan Summary Information:

Number of:	Cross Sections =	11	Multiple Openings =	0
	Culverts =	0	Inline Structures =	0
	Bridges =	0	Lateral Structures =	0

Computational Information

Water surface calculation tolerance	=	0.01
Critical depth calculation tolerance	=	0.01
Maximum number of iterations	=	20
Maximum difference tolerance	=	0.3

Flow tolerance factor = 0.001

Computation Options

Critical depth computed only where necessary
Conveyance Calculation Method: At breaks in n values only
Friction Slope Method: Average Conveyance
Computational Flow Regime: Mixed Flow

FLOW DATA

Flow Title: Qproposed
Flow File : J:\OLY1609-000 Skye Canyon Phase 3a 3b 3c\Drainage\Technical
Study\Addendum 2\Calcs\Iron Mt Wash HEC-RAS\IronMtWash.f01

Flow Data (cfs)

River	Reach	RS	PF 1
Iron Mt Wash	Downstream Ph3A	383	521

Boundary Conditions

River	Reach	Profile	Upstream
Downstream			
Iron Mt Wash	Downstream Ph3A	PF 1	Normal S =
0.005	Normal S =	0.03	

GEOMETRY DATA

Geometry Title: FG
Geometry File : J:\OLY1609-000 Skye Canyon Phase 3a 3b
3c\Drainage\Technical Study\Addendum 2\Calcs\Iron Mt Wash HEC-
RAS\IronMtWash.g02

CROSS SECTION

RIVER: Iron Mt Wash
REACH: Downstream Ph3A RS: 383

INPUT

Description:

Station Elevation Data				num=	4		
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
-52.17	2836	-22.5	2824.22	22.5	2824.22	52.17	2836

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
-52.17	.025	-52.17	.025	52.17	.025

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.
Expan.							

	-52.17	52.17		83.68	83.68	83.68	.1
--	--------	-------	--	-------	-------	-------	----

.3

CROSS SECTION

RIVER: Iron Mt Wash

REACH: Downstream Ph3A RS: 300

INPUT

Description:

Station Elevation Data	num=	4					
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
-46.5	2832	-22.5	2824.01	22.5	2824.01	46.5	2832

Manning's n Values	num=	3					
Sta	n Val	Sta	n Val	Sta	n Val		
-46.5	.025	-46.5	.025	46.5	.025		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.
Expan.							

	-46.5	46.5		100	100	100	.1
--	-------	------	--	-----	-----	-----	----

.3

CROSS SECTION

RIVER: Iron Mt Wash

REACH: Downstream Ph3A RS: 200

INPUT

Description:

Station Elevation Data	num=	4					
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
-41.48	2830	-22.5	2823.76	22.5	2823.76	41.48	2830

Manning's n Values	num=	3					
Sta	n Val	Sta	n Val	Sta	n Val		
-41.48	.025	-41.48	.025	41.48	.025		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.
Expan.							

	-41.48	41.48		100	100	100	.1
--	--------	-------	--	-----	-----	-----	----

.3

CROSS SECTION

RIVER: Iron Mt Wash

REACH: Downstream Ph3A RS: 100

INPUT

Description:

Station Elevation Data				num=	4			
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	
-30.48	2826	-22.5	2823.5	22.5	2823.5	30.48	2826	

Manning's n Values				num=	3			
Sta	n Val	Sta	n Val	Sta	n Val			
-30.48	.025	-30.48	.025	30.48	.025			

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.
Expan.							
	-30.48	30.48		100	100	100	.1
	.3						

CROSS SECTION

RIVER: Iron Mt Wash

REACH: Downstream Ph3A RS: 0

INPUT

Description:

Station Elevation Data				num=	24				
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
-100	2823.188	-87.278	2823.647	-85.285	2823.741	-72.784	2824.111	-	
70.524	2824.008	-63.334	2823.786	-57.174	2824.05	-55.952	2824.206	-25.001	2824.9
23.497	2824.566	-21.582	2823.945	-18.463	2823.454	-17.801	2823.283	-15.083	2823.045
13.092	2822.829	-8.432	2822.657	-3.722	2822.582	-1.869	2822.493	.157	2823.048
10.567	2823.374	11.621	2823.37	22.5	2824	31.5	2827	43.5	2827

Manning's n Values				num=	3			
Sta	n Val	Sta	n Val	Sta	n Val			
-100	.042	-23.497	.042	22.5	.042			

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.
Expan.							
	-23.497	22.5		37.4	50	77.7	.1
	.3						

Left Levee Station= -25 Elevation= 2824.9

CROSS SECTION

RIVER: Iron Mt Wash

REACH: Downstream Ph3A RS: -50

Description:

[illegible]

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
-100	.042	-35.181	.042
		30.35	.042

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.
Expan.						
	-35.181	30.35		50.64	50	50.26
.3						.1

CROSS SECTION

RIVER: Iron Mt Wash
REACH: Downstream Ph3A RS: -100

INPUT

[illegible]

28.521 2818.55 28.712 2818.549 28.893 2818.556 34.431 2818.902 38.32
 2819
 47.32 2822 59.32 2822

Manning's n Values num= 3
 Sta n Val Sta n Val Sta n Val
 -100 .042 -43.205 .042 38.32 .042

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr.
 Expan.
 -43.205 38.32 52.24 50 49.99 .1
 .3

CROSS SECTION

RIVER: Iron Mt Wash
 REACH: Downstream Ph3A RS: -150

INPUT

Description:

Station Elevation Data num= 40
 Sta Elev Sta Elev Sta Elev Sta Elev Sta
 Elev
 -100 2820.049 -82.331 2819.802 -79.277 2819.848 -76.348 2819.88 -
 72.563 2819.797
 -69.435 2819.824 -63.015 2819.75 -61.593 2819.699 -55.617 2820.497 -
 54.674 2820.521
 -52.992 2820.786 -52.566 2820.8 -49.712 2821.012 -47.808 2821.239 -
 43.427 2821.104
 -36.791 2820.976 -31.554 2818.707 -29.605 2818.08 -14.991 2817.664 -
 13.283 2817.897
 -12.005 2818.097 -11.196 2818.31 -9.797 2818.841 -9.039 2819.121 -
 1.496 2818.023
 -.013 2817.942 1.063 2818.08 3.548 2818.443 4.106 2818.538
 8.847 2818.333
 13.912 2818.172 16.591 2817.854 20.537 2817.249 24.563 2816.591
 31.542 2816.643
 35.316 2816.709 36.169 2817.608 37.3 2818.2 46.3 2821.2 58.3
 2821.2

Manning's n Values num= 3
 Sta n Val Sta n Val Sta n Val
 -100 .042 -36.791 .042 37.3 .042

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr.
 Expan.
 -36.791 37.3 52.42 50 46.95 .1
 .3

CROSS SECTION

RIVER: Iron Mt Wash

REACH: Downstream Ph3A RS: -200

INPUT

Description:

Station Elevation Data		num=		84					
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
-100	2817.492	-99.299	2817.483	-96.351	2817.468	-93.228	2817.345	-	
88.532	2818.095								
-87.685	2818.199	-83.732	2819.021	-80.746	2819.069	-76.384	2819.221	-	
67.339	2819.491								
-66.462	2819.491	-53.868	2819.713	-48.518	2819.215	-41.216	2818.904	-	
39.209	2818.733								
-36.395	2817.253	-34.942	2816.415	-30.592	2816.266	-28.802	2816.223	-	
27.809	2816.446								
-26.302	2816.797	-24.447	2817.211	-24.313	2817.23	-23.008	2817.248	-	
21.572	2817.248								
-17.71	2816.84	-17.371	2816.89	-15.818	2817.19	-15.665	2817.228	-	
15.091	2817.235								
-13.707	2817.248	-10.264	2817.248	-9.812	2817.282	-4.961	2817.248	-	
3.229	2817.248								
-2.675	2817.212	-.528	15.953	-.286	2815.755	0	2815.75		
.126	2815.748								
2.879	2815.684	5.858	2816.195	8.986	2815.443	10.896	2815.583		
11.604	2815.936								
11.743	2815.955	11.895	2815.924	13.157	2815.583	16.283	2815.403		
20.267	2815.139								
20.578	2815.115	22.07	2814.82	22.178	2814.805	22.447	2814.804		
26.826	2814.826								
28.004	2815.222	28.493	2815.396	30.446	2815.528	31.656	2816.193		
33.131	2817.116								
33.606	2817.116	36.284	2817.208	39.834	2817.377	48.858	2817.828		
48.974	2817.835								
49.103	2817.841	49.298	2817.845	61.577	2817.817	61.908	2817.796		
63.891	2817.723								
64.849	2817.712	68.551	2818.154	69.404	2818.193	81.243	2818.721		
83	2818.809								
86.624	2818.942	87.124	2818.771	88.389	2818.402	89.063	2818.559		
89.915	2818.842								
90.306	2818.925	92.028	2818.977	97.984	2819.057	100	2819.12		

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
-100	.042	-39.209	.042	48.858	.042

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.
Expan.							
	-39.209	48.858		52.47	50	46.93	.1
	.3						

CROSS SECTION

RIVER: Iron Mt Wash

REACH: Downstream Ph3A RS: -250

INPUT

Description:

Station	Elevation	Data	num=	76					
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
-100	2816.575	-95.182	2816.836	-91.027	2816.856	-75.206	2816.806	-	
69.465	2817.165								
-69.243	2817.178	-68.593	2817.062	-63.501	2816.51	-53.286	2816.617	-	
45.017	2816.648								
-44.68	2816.66	-40.786	2816.8	-40.076	2816.819	-39.931	2816.816	-	
39.684	2816.709								
-35.982	2814.394	-34.671	2814.291	-30.492	2814.323	-28.466	2814.619	-	
26.661	2814.958								
-22.825	2815.326	-22.212	2815.341	-21.088	2815.254	-18.163	2814.958	-	
16.752	2814.784								
-11.513	2815.073	-11.032	2815.103	-10.853	2815.112	-10.138	2815.121	-3.997	
2814.75									
-3.315	2814.678	-.027	2814.354	.136	2814.375	3.079	2814.534		
3.192	2814.542								
5.948	2814.06	7.492	2813.501	9.231	2813.392	10.847	2813.263		
16.082	2813.492								
21.128	2813.651	22.171	2814.304	22.442	2814.518	23.135	2814.5		
29.516	2814.518								
30.674	2814.558	31.484	2814.351	32.603	2814.23	35.762	2814.426		
37.674	2814.607								
38.949	2814.825	39.488	2814.883	40.293	2814.975	40.712	2815.025		
44.049	2815.376								
46.367	2815.911	51.403	2816.5	56.694	2816.967	59.872	2817.182		
64.334	2817.238								
70.779	2817.449	71.239	2817.456	71.985	2817.533	73.773	2817.592		
74.219	2817.602								
75.982	2817.904	79.529	2817.767	82.629	2817.733	83.793	2817.628		
87	2817.393								
90.372	2817.697	92.663	2817.821	93.677	2817.904	94.254	2817.947		
98.857	2818.194								
100	2818.128								

Manning's n	Values	num=	3
Sta	n Val	Sta	n Val
-100	.042	-39.931	.042
51.403			

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.
Expan.							
	-39.931	51.403		52.47	50	48.07	.1
.3							

CROSS SECTION

RIVER: Iron Mt Wash

REACH: Downstream Ph3A RS: -300

INPUT

Description:

Station Elevation Data		num=		79					
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
Elev									
-100	2814.417	-99.197	2814.403	-96.966	2814.341	-96.315	2814.319	-	
93.484	2814.249								
-83.476	2814.225	-74.848	2814.273	-67.353	2814.22	-58.211	2815.23	-	
51.991	2815.834								
-51.322	2815.9	-49.482	2815.604	-47.257	2815.252	-44.738	2814.9	-	
39.374	2814.706								
-34.428	13.809	-34.116	2813.75	-33.922	2813.668	-30.154	2812.543	-	
29.899	2812.528								
-29.362	2812.597	-29.126	2812.669	-28.717	2812.786	-26.524	2813.512	-	
24.497	2812.996								
-23.877	2812.586	-23.304	2812.198	-22.722	2812.037	-22.028	2811.841	-	
10.177	2811.787								
-3.008	2811.818	-2.276	2812.591	-1.027	2813.149	3.129	2813.045		
6.812	2812.968								
8.735	2813.572	11.825	2813.93	12.269	2813.898	12.492	2813.864		
15.456	2813.495								
19.065	2813.038	20.791	2812.839	21.678	2812.699	23.207	2812.711		
27.538	2812.799								
29.231	2813.358	30.341	2813.672	30.484	2813.766	31.722	2814.013		
34.292	2814.825								
34.709	2814.879	37.562	2814.934	40.048	2815.261	40.872	2815.275	41.727	
2815.32									
48.194	2815.432	50.155	2815.652	54.818	2815.962	57.457	2815.855		
60.544	2815.887								
64.979	2816.234	65.852	2816.234	70.415	2816.455	74.349	2815.98		
74.768	2815.944								
75.189	2815.978	79.697	2816.401	83.151	2816.456	86.009	2816.531		
87.885	2816.546								
88.602	2816.236	91.143	2815.401	93.611	2815.668	93.722	2815.67		
93.873	2815.683								
94.201	2815.709	98.465	2816.058	99.622	2816.333	100	2816.413		

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
-100	.042	-39.374	.042	41.727	.042

Bank Sta:	Left	Right	Coeff	Contr.	Expan.
	-39.374	41.727		.1	.3

SUMMARY OF MANNING'S N VALUES

River:Iron Mt Wash

Reach	River Sta.	n1	n2	n3
Downstream Ph3A	383	.025	.025	.025
Downstream Ph3A	300	.025	.025	.025

Downstream Ph3A	200	.025	.025	.025
Downstream Ph3A	100	.025	.025	.025
Downstream Ph3A	0	.042	.042	.042
Downstream Ph3A	-50	.042	.042	.042
Downstream Ph3A	-100	.042	.042	.042
Downstream Ph3A	-150	.042	.042	.042
Downstream Ph3A	-200	.042	.042	.042
Downstream Ph3A	-250	.042	.042	.042
Downstream Ph3A	-300	.042	.042	.042

SUMMARY OF REACH LENGTHS

River: Iron Mt Wash

Reach	River Sta.	Left	Channel	Right
Downstream Ph3A	383	83.68	83.68	83.68
Downstream Ph3A	300	100	100	100
Downstream Ph3A	200	100	100	100
Downstream Ph3A	100	100	100	100
Downstream Ph3A	0	37.4	50	77.7
Downstream Ph3A	-50	50.64	50	50.26
Downstream Ph3A	-100	52.24	50	49.99
Downstream Ph3A	-150	52.42	50	46.95
Downstream Ph3A	-200	52.47	50	46.93
Downstream Ph3A	-250	52.47	50	48.07
Downstream Ph3A	-300			


SUMMARY OF CONTRACTION AND EXPANSION COEFFICIENTS

River: Iron Mt Wash

Reach	River Sta.	Contr.	Expan.
Downstream Ph3A	383	.1	.3
Downstream Ph3A	300	.1	.3
Downstream Ph3A	200	.1	.3
Downstream Ph3A	100	.1	.3
Downstream Ph3A	0	.1	.3
Downstream Ph3A	-50	.1	.3
Downstream Ph3A	-100	.1	.3
Downstream Ph3A	-150	.1	.3
Downstream Ph3A	-200	.1	.3
Downstream Ph3A	-250	.1	.3
Downstream Ph3A	-300	.1	.3


Skye 3A - Iron Mt Wash Downstream

RS = 383




Skye 3A - Iron Mt Wash Downstream

RS = 300




Skye 3A - Iron Mt Wash Downstream

RS = 200




Skye 3A - Iron Mt Wash Downstream

RS = 100




Skye 3A - Iron Mt Wash Downstream

RS = 0




Skye 3A - Iron Mt Wash Downstream

RS = -50




Skye 3A - Iron Mt Wash Downstream

RS = -100




Skye 3A - Iron Mt Wash Downstream

RS = -150




Skye 3A - Iron Mt Wash Downstream

RS = -200




Skye 3A - Iron Mt Wash Downstream

RS = -250



Skye 3A - Iron Mt Wash Downstream

RS = -300



APPENDIX D

CD of Electronic Files & Revised Improvement Plans