



**LAS VEGAS
CITY COUNCIL**

CAROLYN G. GOODMAN
Mayor

BRIAN KNUDSEN
Mayor Pro Tem

VICTORIA SEAMAN
OLIVIA DIAZ
FRANCIS ALLEN-PALENSKE
CEDRIC CREAR
NANCY E. BRUNE

JORGE CERVANTES
City Manager

DEPARTMENT OF
COMMUNITY DEVELOPMENT

SETH T. FLOYD
DIRECTOR

CITY HALL
495 S. MAIN ST.
3RD FLOOR
LAS VEGAS, NV 89101
702.229.6301 | VOICE
702.464.2545 | FAX
711 | TTY



cityoflasvegas
lasvegasnevada.gov

January 11, 2023

Vincent Esposito
Howard Hughes Company LLC
10845 Griffith Peak Suite 160
Las Vegas, Nevada 89135

**RE: 22-0560-TMP1
PLANNING COMMISSION MEETING OF JANUARY 10, 2023**

Dear Applicant:

The Planning Commission at a regular meeting held on *January 10, 2023* voted to **APPROVE** the following Land Use Entitlement project request FOR AN 81-LOT SINGLE-FAMILY RESIDENTIAL SUBDIVISION on 78.08 acres on the north side of the Lake Mead Boulevard alignment, 740 feet west of Reverence Parkway (Portion of Book 169 Page 038), P-C (Planned Community) Zone [ER (Estate Residential) Summerlin Land Use Designation], Ward 2 (Seaman)

This approval is subject to the following conditions:

Planning

1. Approval of the Tentative Map shall be for no more than four (4) years. If a Final Map is not recorded on all or a portion of the area embraced by the Tentative Map within four (4) years of the approval of the Tentative Map, this action is void.
2. Street names must be provided in accordance with the City's Street Naming Regulations.
3. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.
4. In conjunction with creation, declaration and recordation of the subject common-interest community, and prior to recordation of the Covenants, Codes and Restrictions ("CC&R"), or conveyance of any unit within the community, the Developer is required to record a Declaration of Private Maintenance Requirements ("DPMR") as a covenant on all associated properties, and on behalf of all current and future property owners. The DPMR is to include a listing of all privately owned and/or maintained infrastructure improvements, along with assignment of maintenance responsibility for each to the common interest community or the respective individual property

owners, and is to provide a brief description of the required level of maintenance for privately maintained components. The DPMR must be reviewed and approved by the City of Las Vegas Department of Field Operations prior to recordation, and must include a statement that all properties within the community are subject to assessment for all associated costs should private maintenance obligations not be met, and the City of Las Vegas be required to provide for said maintenance. Also, the CC&R are to include a statement of obligation of compliance with the DPMR. Following recordation, the Developer is to submit copies of the recorded DPMR and CC&R documents to the City of Las Vegas Department of Field Operations.

5. All development is subject to the conditions of City Departments and State Subdivision Statutes.


Public Works

6. Private streets must be granted and labeled on the Final Map for this site as Public Utility Easements (P.U.E.), Public Sewer Easements, and Public Drainage Easements to be privately maintained by the Homeowner's Association.
7. All City of Las Vegas maintained underground infrastructure shall meet standard minimum horizontal separations unless otherwise approved by the City Engineer.
8. Grant a minimum 40-foot wide Public Sewer and Public Drainage Easement to be privately maintained for the public sewer and storm drain within Common Element "I", COS-4, Common Element "F", between lots 74 and 75, and between lots 53 and 54. Easement widths between lots 65 and 66 as well as over DC-2 will be determined through construction plan review. Any easements that are outside the boundary of this Tentative Map must record by separate document prior to or concurrent with the recordation of a Final Map for this site.
9. No walls, signs, lights, parking area, buildings or other structures, or permanent landscaping having a mature height of greater than 3-feet shall be placed anywhere in any Public Sewer Easement or in the vehicle ingress or egress pathways to such easements.
10. Prior to the submittal of construction drawings for this site, submit a pedestrian circulation plan to identify nearby pedestrian attractors and recommend measures to accommodate pedestrians, such as but not limited to pedestrian access, crosswalk, pedestrian activated flashers and temporary sidewalks. Comply with the recommendation of the approved pedestrian circulation plan.
11. A Drainage Plan and Technical Drainage Study must be submitted to and approved by the Department of Public Works prior to the issuance of any building or grading permits or submittal of any construction drawings, whichever may occur first. Provide and improve all drainageways recommended in the approved drainage plan/study. The developer of this site shall be responsible to construct such neighborhood or local drainage facility improvements as are recommended by the City of Las Vegas Neighborhood Drainage Studies and approved Drainage Plan/Study concurrent with development of this site.

12. As per Unified Development Code (UDC) 19.16.060.G, all requirements must be complied with or such future compliance must be guaranteed by an approved performance security method in accordance with UDC sections 19.02.130.
13. The approval of all Public Works related improvements shown on this Tentative Map is in concept only. Specific design and construction details relating to size, type and/or alignment of improvements, including but not limited to street, sewer and drainage improvements, shall be resolved prior to approval of the construction plans by the City. A deviation from Standards is hereby approved for the non-standard street termini as shown on the approved Tentative Map. No other deviations from adopted City Standards shall be allowed unless specific written approval for such is received from the City Engineer prior to the recordation of a Final Map or the approval of subdivision-related construction plans, whichever may occur first. Approval of this Tentative Map does not constitute approval of any deviations. If such approval cannot be obtained, a revised Tentative Map must be submitted showing elimination of such deviations

This action by the Planning Commission on January 10, 2023 is final unless a written appeal is filed with the City Clerk within seven days of the date of the Planning Commission's decision as allowed by code or there is a review action filed by the City Council within the same time period. For additional information on appeals or review requests submitted please access <https://www.lasvegasnevada.gov/Business/Permits-Licenses/Building-Permits/Permit-Application-Status>, or contact the Department of Planning and Development at 702.229.6301 after January 18, 2023. No building permits or business licenses related to these items shall be issued prior to the expiration of the required seven day waiting period, or until any filed appeal is resolved pursuant to LVMC Title 19.18.

Sincerely,



Nicole Eddowes
Community Development Coordinator
Case Planning Division

NE:ew

cc:

Jennifer Veras
GCW Inc
1555 South Rainbow Boulevard
Las Vegas, Nevada 89146