



**LAS VEGAS
CITY COUNCIL**

CAROLYN G. GOODMAN
Mayor

BRIAN KNUDSEN
Mayor Pro Tem

CEDRIC CREAR
VICTORIA SEAMAN
OLIVIA DIAZ

FRANCIS ALLEN-PALENSKE
NANCY E. BRUNE

JORGE CERVANTES
City Manager

DEPARTMENT OF
COMMUNITY DEVELOPMENT

SETH T. FLOYD
DIRECTOR

CITY HALL
495 S. MAIN ST.
1ST FLOOR
LAS VEGAS, NV 89101
702.229.6301 | VOICE
702.464.2545 | FAX
711 | TTY



July 26, 2023

Clark County School Board of Trustees
1180 Military Tribute Place
Henderson, Nevada 89074

**RE: 23-0242 [VAR1 AND SDR1]
SPECIAL PLANNING COMMISSION MEETING OF JULY 25, 2023**

Dear Applicant:

The Planning Commission at a special meeting held on *July 25, 2023* voted to **APPROVE** the following Land Use Entitlement project requests on 18.19 acres at the northeast corner of Smoke Ranch Road and Maverick Street (APN 138-14-802-005), C-V (Civic) Zone, Ward 5 (Crear).

23-0242-VAR1 - VARIANCE - TO ALLOW DEVIATIONS FROM TITLE 19.10 C-V (CIVIC) DEVELOPMENT STANDARDS

23-0242-SDR1 - SITE DEVELOPMENT PLAN REVIEW - FOR A PROPOSED TWO-STORY, 143,316 SQUARE-FOOT PRIMARY PUBLIC SCHOOL DEVELOPMENT

This approval is subject to the following conditions:

23-0242-VAR1 CONDITIONS

Planning

1. Approval of and conformance to the Conditions of Approval for Site Development Plan Review (23-0242-SDR1) shall be required, if approved.
2. This approval shall be void two years from the date of final approval, unless exercised pursuant to the provisions of LVMC Title 19.16. An Extension of Time may be filed for consideration by the City of Las Vegas.
3. All City Code requirements and design standards of all City departments must be satisfied, except as modified herein.

23-0242-SDR1 CONDITIONS

Planning

1. Approval of and conformance to the Conditions of Approval for Variance (23-0242-VAR1) shall be required, if approved.
2. This approval shall be void two years from the date of final approval, unless exercised pursuant to the provisions of LVMC Title 19.16. An Extension of Time may be filed for consideration by the City of Las Vegas.
3. All development shall be in conformance with the site plan, landscape plan, and building elevations, date stamped 05/17/23, except as amended by conditions herein.
4. The existing Master Sign Plan for this school site shall be amended prior to installation of new animated signage.
5. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.
6. The applicant shall obtain written verification by the FAA and/or the Clark County Department of Aviation of the following:
 - a. Applicant is required to file a valid FAA Form 7460-1, "Notice of Proposed Construction or Alteration" with the FAA, in accordance with 14 CFR Part 77, or submit to the Clark County Director of Aviation a "Property Owner's Shielding Determination Statement" and request written concurrence from the Clark County Department of Aviation.
 - b. No Building Permit or other construction permit shall be issued for any structure greater than 35 feet above the surface of land that, based upon the FAA's 7460 airspace determination (the outcome of filing the FAA Form 7460-1) would (a) constitute a hazard to air navigation, (b) would result in an increase to minimum flight altitudes during any phase of flight (unless approved by the Department of Aviation), or (c) would otherwise be determined to pose a significant adverse impact on airport or aircraft operations.
 - c. Applicant is advised that FAA's airspace determinations are dependent on petitions by any interested party and the height that will not present a hazard as determined by the FAA may change based on these comments.
 - d. Applicant is advised that the FAA's airspace determinations include expiration dates and that the separate airspace determinations will be needed for construction cranes or other temporary equipment.

7. All City Code requirements and design standards of all City Departments must be satisfied, except as modified herein.


Public Works

8. In accordance with Section 2.2 of the City's Vision Zero Action Plan, the sidewalk adjacent to this site shall meet Public Right-of-Way Accessibility Guidelines (PROWAG) in accordance with code requirements of Title 13.56.040 to the satisfaction of the City Engineer concurrent with development of this site. Grant any Pedestrian Access Easement needed to complete this requirement.
9. Coordinate sewer connection at a size, depth, and location acceptable to the Sanitary Sewer Engineering Section of the Department of Public Works. The existing school is currently connected to public sewer. The new buildings may utilize the existing connections, but if new connections are needed, they must connect to public sewer on Smoke Ranch Road.
10. Landscape and maintain all unimproved right-of-way adjacent to this site. All landscaping and private improvements installed with this project shall be situated and maintained so as to not create sight visibility obstructions for vehicular traffic at all development access drives and abutting street intersections.
11. Unless otherwise allowed by the City Engineer, construct sidewalk on at least one side of all access drives connecting this site to the adjacent public streets concurrent with development of this site. The connecting sidewalk shall extend from the sidewalk on the public street to the first intersection of the on-site roadway network and shall be terminated on-site with a handicap ramp.
12. Queues for the school shall not extend into the public right-of-way as a result of the pick up or drop off operations on this site.
13. A Traffic Impact Analysis must be submitted to and approved by the Department of Public Works prior to the issuance of any building or grading permits, submittal of any construction drawings or the recordation of a Map subdividing this site, whichever may occur first. The Traffic Impact Analysis shall also include a pedestrian circulation/access plan, in accordance with Section 2.2 of the City's Vision Zero Action Plan, to identify nearby pedestrian attractors and recommend measures to accommodate pedestrians, such as but not limited to pedestrian access, crosswalk, pedestrian activated flashers and temporary sidewalks. Comply with the recommendations of the approved Traffic Impact Analysis prior to occupancy of the site. Phased compliance will be allowed if recommended by the approved Traffic Impact Analysis. No recommendation of the approved Traffic Impact Analysis, nor compliance therewith, shall be deemed to modify or eliminate any condition of approval imposed by the Planning Commission or the City Council on the development of this site.

14. A Drainage Plan and Technical Drainage Study must be submitted to and approved by the Department of Public Works prior to the issuance of any building or grading permits or submittal of any construction drawings, whichever may occur first. Provide and improve all drainageways recommended in the approved drainage plan/study. The developer of this site shall be responsible to construct such neighborhood or local drainage facility improvements as are recommended by the City of Las Vegas Neighborhood Drainage Studies and approved Drainage Plan/Study concurrent with development of this site.

This action by the Special Planning Commission on **July 25, 2023** is final unless a written appeal is filed with the City Clerk within ten days of the date of the Planning Commission's decision as allowed by code or there is a review action filed by the City Council within the same time period. For additional information on appeals or review requests submitted please access <https://www.lasvegasnevada.gov/Business/Permits-Licenses/Building-Permits/Permit-Application-Status>, or contact the Department of Community Development at 702.229.6301 after **August 7, 2023**. No building permits or business licenses related to these items shall be issued prior to the expiration of the required ten day waiting period, or until any filed appeal is resolved pursuant to LVMC Title 19.18.

Sincerely,



Nicole Eddowes
Community Development Coordinator
Case Planning Division

NE:nl

cc:

Clark County School District - Facilities Services
1180 Military Tribute Place
Henderson, Nevada 89074

Paulette Marshall
Clark County School District - Real Property Management
1180 Military Tribute Place
Henderson, Nevada 89074