



**LAS VEGAS
CITY COUNCIL**

CAROLYN G. GOODMAN
Mayor

BRIAN KNUDSEN
Mayor Pro Tem

CEDRIC CREAR
VICTORIA SEAMAN

OLIVIA DÍAZ

FRANCIS ALLEN-PALENSKE

NANCY E. BRUNE

MIKE JANSSEN
City Manager

DEPARTMENT OF
COMMUNITY DEVELOPMENT

SETH T. FLOYD

DIRECTOR

CITY HALL

495 S. MAIN ST., 3RD FLOOR
LAS VEGAS, NV 89101

702.229.6011 | VOICE
711 | TTY

September 13, 2023

Brian Walsh
Howard Hughes Company LLC
10845 Griffith Peak Drive, Ste. 160
Las Vegas, Nevada 89135

**RE: 23-0336-TMP1
PLANNING COMMISSION MEETING OF SEPTEMBER 12, 2023**

Dear Applicant:

The Planning Commission at a regular meeting held on *September 12, 2023* voted to **APPROVE** a request FOR A 53-LOT SINGLE-FAMILY RESIDENTIAL SUBDIVISION on 11.02 acres at the northwest corner of Park Bluff Lane and Redpoint Drive (APN 137-22-310-001), P-C (Planned Community) Zone [SFSD (Single Family Special Lot Development) Summerlin Special Land Use Designation], Ward 2 (Seaman).

This approval is subject to the following conditions:

Planning

1. Approval of the Tentative Map shall be for no more than four (4) years. If a Final Map is not recorded on all or a portion of the area embraced by the Tentative Map within four (4) years of the approval of the Tentative Map, this action is void.
2. Street names must be provided in accordance with the City's Street Naming Regulations.
3. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.



cityoflasvegas | lasvegasnevada.gov

4. In conjunction with creation, declaration and recordation of the subject common-interest community, and prior to recordation of the Covenants, Codes and Restrictions ("CC&R"), or conveyance of any unit within the community, the Developer is required to record a Declaration of Private Maintenance Requirements ("DPMR") as a covenant on all associated properties, and on behalf of all current and future property owners. The DPMR is to include a listing of all privately owned and/or maintained infrastructure improvements, along with assignment of maintenance responsibility for each to the common interest community or the respective individual property owners, and is to provide a brief description of the required level of maintenance for privately maintained components. The DPMR must be reviewed and approved by the City of Las Vegas Department of Field Operations prior to recordation, and must include a statement that all properties within the community are subject to assessment for all associated costs should private maintenance obligations not be met, and the City of Las Vegas be required to provide for said maintenance. Also, the CC&R are to include a statement of obligation of compliance with the DPMR. Following recordation, the Developer is to submit copies of the recorded DPMR and CC&R documents to the City of Las Vegas Department of Field Operations.
5. All development is subject to the conditions of City Departments and State Subdivision Statutes.

Public Works

6. Private streets must be granted and labeled on the Final Map for this site as Public Utility Easements (P.U.E.), Public Sewer Easements, and Public Drainage Easements to be privately maintained by the Homeowner's Association. Additionally grant equivalent public easements by separate document across Common Lot 78 of Book 165, Page 7 of Plats at the entry for this site.
7. Design of horizontal and vertical distance separations for public sewer and flood control infrastructure must meet the City of Las Vegas' design criteria prior to the issuance of permits for this site, unless otherwise allowed by the City Engineer.
8. No walls, signs, lights, parking area, buildings or other structures, or permanent landscaping having a mature height of greater than 3-feet shall be placed anywhere in any Public Sewer Easement or in the vehicle ingress or egress pathways to such easements.


9. Prior to the submittal of construction drawings for this site, submit a pedestrian circulation plan to identify nearby pedestrian attractors and recommend measures to accommodate pedestrians, such as but not limited to pedestrian access, crosswalk, pedestrian activated flashers and temporary sidewalks. Comply with the recommendation of the approved pedestrian circulation plan. The applicant is responsible for all required modifications, if any, to Fox Hill Drive as a result of this required pedestrian analysis.
10. Prior to the release of a Final Map, the property owner must contact the Special Improvement District Section of the Department of Public Works (702-229-2136). The City shall prepare an apportionment report for the per lot assessment of all lots following recordation of the Final Map.
11. A Drainage Plan and Technical Drainage Study must be submitted to and approved by the Department of Public Works prior to the issuance of any building or grading permits or submittal of any construction drawings, whichever may occur first. Provide and improve all drainageways recommended in the approved drainage plan/study. The developer of this site shall be responsible to construct such neighborhood or local drainage facility improvements as are recommended by the City of Las Vegas Neighborhood Drainage Studies and approved Drainage Plan/Study concurrent with development of this site.
12. As per Unified Development Code (UDC) 19.16.060.G, all requirements must be complied with or such future compliance must be guaranteed by an approved performance security method in accordance with UDC sections 19.02.130.
13. The approval of all Public Works related improvements shown on this Tentative Map is in concept only. Specific design and construction details relating to size, type and/or alignment of improvements, including but not limited to street, sewer and drainage improvements, shall be resolved prior to approval of the construction plans by the City. A deviation for non-standard streets with 90 degree bends is hereby approved. No other deviations from adopted City Standards shall be allowed unless specific written approval for such is received from the City Engineer prior to the recordation of a Final Map or the approval of subdivision-related construction plans, whichever may occur first. Approval of this Tentative Map does not constitute approval of any deviations. If such approval cannot be obtained, a revised Tentative Map must be submitted showing elimination of such deviations.

Fire and Rescue

14. Applicant shall install an approved fire sprinkler system in all dwelling units in accordance with 2021 IFC Section 903 & the Memo of Understanding for R-3 as amended.

This action by the Planning Commission on **September 12, 2023** is final unless a written appeal is filed with the City Clerk within seven days of the date of the Planning Commission's decision as allowed by code or there is a review action filed by the City Council within the same time period. For additional information on appeals or review requests submitted please access <https://www.lasvegasnevada.gov/Business/Permits-Licenses/Building-Permits/Permit-Application-Status>, or contact the Department of Community Development at 702.229.6301 after **September 20, 2023**. No building permits or business licenses related to these items shall be issued prior to the expiration of the required seven day waiting period, or until any filed appeal is resolved pursuant to LVMC Title 19.18.

Sincerely,



Nicole Eddowes
Community Development Coordinator
Case Planning Division

NE:nl

cc:

Mina Maleki
Tri Pointe Homes
4675 West Teco Avenue, Ste. 115
Las Vegas, Nevada 89118

Tanya Steadham
Westwood Professional Services
5725 West Badura Avenue, Ste. 100
Las Vegas, Nevada 89118