



**LAS VEGAS
CITY COUNCIL**

CAROLYN G. GOODMAN
Mayor

BRIAN KNUDSEN
Mayor Pro Tem

CEDRIC CREAR
VICTORIA SEAMAN

OLIVIA DÍAZ
FRANCIS ALLEN-PALENSKE
NANCY E. BRUNE

MIKE JANSSEN
City Manager

DEPARTMENT OF
COMMUNITY DEVELOPMENT

SETH T. FLOYD
DIRECTOR

CITY HALL
495 S. MAIN ST., 3RD FLOOR
LAS VEGAS, NV 89101

702.229.6011 | VOICE
711 | TTY

December 13, 2023

Joseph Riggs
3000 M W LLC
3065 North Rancho Drive, Suite #132
Las Vegas, Nevada 89130

**RE: 23-0309-SDR1
PLANNING COMMISSION MEETING OF DECEMBER 12, 2023**

Dear Applicant:

The Planning Commission at a regular meeting held on *December 12, 2023* voted to recommend **APPROVAL** of a Land Use Entitlement project request FOR A TWO-STORY, 136-UNIT MULTI-FAMILY RESIDENTIAL DEVELOPMENT WITH WAIVERS OF THE PERIMETER LANDSCAPE BUFFER REQUIREMENTS on 9.96 acres located on the east side of Michael Way, approximately 444 feet south of Cheyenne Avenue (APNs 138-13-512-009 and 010), R-3 (Medium Density Residential) Zone, Ward 5 (Crear).

This approval is subject to the following conditions:

Planning

1. This approval shall be void two years from the date of final approval, unless exercised pursuant to the provisions of LVMC Title 19.16. An Extension of Time may be filed for consideration by the City of Las Vegas.
2. All development shall be in conformance with the site plan, date stamped 11/21/23, landscape plan, date stamped 11/15/23 and building elevations, date stamped 09/27/23, except as amended by conditions herein.
3. Waivers from Title 19.06.110 are hereby approved, to allow five-foot wide landscape buffer widths along portions of the north and east property lines where six feet is required.
4. All necessary building permits shall be obtained and final inspections shall be completed in compliance with Title 19 and all codes as required by the Building and Safety Division.
5. These Conditions of Approval shall be affixed to the cover sheet of any plan set submitted for building permit.



6. The applicant shall coordinate with the City Surveyor and other city staff to determine the most appropriate mapping action necessary to consolidate the existing lots. The mapping action shall be completed and recorded prior to the issuance of any building permits.
7. Pursuant to LVMC Title 19.08.040.G for commercial and industrial properties, a perimeter wall shall be constructed adjacent to any residential zoning district or property used solely for residential purposes. The wall or fence is intended to screen the commercial or industrial activity from the residential property, and shall be of a solid decorative material that is a minimum of six feet in height measured from the side of the commercial or industrial property. In no case shall the wall or fence exceed the overall height limitation applicable to the adjacent zoning district or property unless approved through a Variance or other applicable means. The overall height of a wall or fence shall be measured from the side with the greatest vertical exposure above finished grade.
8. Prior to or at the time of submittal for any building permit, the applicant shall provide written verification by the FAA and/or the Clark County Department of Aviation of the following:
 - a. Applicant is required to file a valid FAA Form 7460-1, "Notice of Proposed Construction or Alteration" with the FAA, in accordance with 14 CFR Part 77, or submit to the Clark County Director of Aviation a "Property Owner's Shielding Determination Statement" and request written concurrence from the Clark County Department of Aviation.
 - b. No Building Permit or other construction permit shall be issued for any structure greater than 35 feet above the surface of land that, based upon the FAA's 7460 airspace determination (the outcome of filing the FAA Form 7460-1) would (a) constitute a hazard to air navigation, (b) would result in an increase to minimum flight altitudes during any phase of flight (unless approved by the Department of Aviation), or (c) would otherwise be determined to pose a significant adverse impact on airport or aircraft operations.
 - c. Applicant is advised that FAA's airspace determinations are dependent on petitions by any interested party and the height that will not present a hazard as determined by the FAA may change based on these comments.
 - d. Applicant is advised that the FAA's airspace determinations include expiration dates and that the separate airspace determinations will be needed for construction cranes or other temporary equipment.
9. A technical landscape plan, signed and sealed by a Registered Architect, Landscape Architect, Residential Designer or Civil Engineer, must be submitted prior to or at the same time application is made for a building permit. A permanent underground sprinkler system is required, which shall be permanently maintained in a satisfactory manner; the landscape plan shall include irrigation specifications. Installed landscaping shall not impede visibility of any traffic control device. The technical landscape plan shall include the following changes from the conceptual landscape plan:


One 24-inch box tree shall be planted within each parking lot island.

One 24-inch box tree per 20 linear feet shall be planted within the required perimeter landscape buffer areas with four five-gallon shrubs for each required tree.

10. All City Code requirements and design standards of all City Departments must be satisfied, except as modified herein.

This item will be considered by the City Council on January 17, 2024. This meeting will be held at 9:00 A.M. at the Council Chambers of City Hall, 495 South Main Street, Las Vegas, Nevada. ***The Council requires that you or your representative be present at this meeting.*** If you or your representative chooses not to attend, the City Council may act in your absence without your input.

Sincerely,



Nicole Eddowes
Community Development Coordinator
Case Planning Division

NE:bp

cc:

Jeffrey Armstrong
VTN-NEVADA
2727 South Rainbow Boulevard
Las Vegas, Nevada 89146