

# PLANNING & DEVELOPMENT



DEVELOPMENT SERVICES CENTER

731 S Fourth Street  
Las Vegas, NV 89101

Voice 702-229-6301  
Fax 702-474-0352  
TTY 702-386-9108

[www.lasvegasnevada.gov](http://www.lasvegasnevada.gov)

February 29, 2008

Abrar Management  
Craig 95, LLC  
5419 Hollywood Boulevard, Suite C-745  
Los Angeles, California 90027

**RE: ABEYANCE - SDR-25484 - SITE DEVELOPMENT PLAN REVIEW**

Dear Applicant:

Your request for a Major Amendment of an approved Site Development Plan Review (SDR-19643) FOR A PROPOSED 41,097 SQUARE FOOT SHOPPING CENTER on 3.53 acres adjacent to the south side of Craig Road, west of U.S. 95 (APN 138-03-701-003), U (Undeveloped) Zone [SC (Service Commercial) General Plan Designation] under Resolution of Intent to C-1 (Limited Commercial) Zone, Ward 4 (Brown), was considered by the Planning Commission on February 28, 2008.

The Planning Commission voted to **APPROVE** your request, subject to the following:

### Planning and Development

1. Conformance to the conditions for Site Development Plan Review (SDR-19643), except as amended herein.
2. This approval shall be void two years from the date of final approval, unless a building permit has been issued for the principal building on the site. An Extension of Time may be filed for consideration by the City of Las Vegas.
3. All development shall be in conformance with the site plan, landscape plans and building elevations date stamped 02/12/08, except as amended by conditions herein.
4. A technical landscape plan, signed and sealed by a Registered Architect, Landscape Architect, Residential Designer or Civil Engineer, must be submitted prior to or at the same time application is made for a building permit. A permanent underground sprinkler system is required, and shall be permanently maintained in a satisfactory manner; the landscape plan shall include irrigation specifications.

Mayor  
Oscar B. Goodman

City Council  
Gary Reese  
(Mayor Pro Tem)  
Larry Brown  
Steve Wolfson  
Lois Tarkanian  
Steven D. Ross  
Ricki Y. Barlow

City Manager  
Douglas A. Selby



096581



5. Pre-planting and post-planting landscape inspections are required to ensure the appropriate plant material, location, size of planters, and landscape plans are being utilized. The Planning and Development Department must be contacted to schedule an inspection prior to the start of the landscape installation and after the landscape installation is completed. A certificate of occupancy will not be issued or the final inspection will not be approved until the landscape inspections have been completed.
6. Reflective glazing at the pedestrian level is prohibited. Glazing above the pedestrian level shall be limited to a maximum reflectance rating of 22% (as defined by the National Institute of Standards and Technology).
7. All mechanical equipment, air conditioners and trash areas shall be fully screened in views from the abutting streets.
8. All utility boxes exceeding 27 cubic feet in size shall meet the standards of LVMC Title 19.12.040.
9. Parking lot lighting standards shall be no more than 30 feet in height and shall utilize downward-directed lights with full cut-off luminaries. Lighting on the exterior of buildings shall be shielded and shall be downward-directed. Non-residential property lighting shall be directed away from residential property or screened, and shall not create fugitive lighting on adjacent properties.
10. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.
11. All City Code requirements and design standards of all City Departments must be satisfied, except as modified herein.

**Public Works**


12. All private improvements and landscaping installed with this project shall be situated and maintained so as to not create sight visibility obstructions for vehicular traffic at all development access drives and abutting street intersections.
13. Delivery truck ingress and egress for vehicles defined as WB-50 in AASHTO Geometric Design Manual shall be exclusively from Tenaya Way. We note that a joint access agreement for the driveway accessing Craig Road and Tenaya Way is on file.

Abrar Management  
SDR-25484 - Page Three  
February 29, 2008

14. Construct a raised median island at the shared access driveway to this site from Craig Road to restrict left turns from the existing northerly most driveway on the west side of the shared access driveway.
15. Unless otherwise allowed by the City Engineer, construct sidewalk on at least one side of all access drives connecting this site to the adjacent public streets concurrent with development of this site. The connecting sidewalk shall extend from the sidewalk on the public street to the first intersection of the on-site roadway network and shall be terminated on-site with a handicap ramp.
16. Site development to comply with all applicable conditions of approval for Zoning Reclassification ZON-19647 and all other applicable site-related actions.

This action by the Planning Commission on **February 28, 2008** is final unless a written appeal is filed with the City Clerk within ten days of the date of the Planning Commission's decision or there is a review action filed by the City Council within the same time period. The Notice of Final Action was filed with the Las Vegas City Clerk on **February 29, 2008**.

Sincerely,



Andrew P. Reed, AICP  
Planning Supervisor  
Current Planning Division

AR:clb

cc: Mr. Ali Kaveh  
Platinum Realty and Development  
3824 South Jones Boulevard, Suite F  
Las Vegas, Nevada 89103

Ms. Kathryn Grider  
Southwest Engineering  
3610 North Rancho Drive  
Las Vegas, Nevada 89130