

PLANNING & DEVELOPMENT



DEVELOPMENT SERVICES CENTER

731 S Fourth Street
Las Vegas, NV 89101

Voice 702-229-6301

Fax 702-474-0352

TTY 702-386-9108

www.lasvegasnevada.gov

November 9, 2007

Rabbi Shea Harlig
Chabad Southern Nevada Inc.
1261 South Arville Street
Las Vegas, Nevada 89102

RE: TABLED - RENOTIFICATION - SDR-18342 - SITE DEVELOPMENT PLAN REVIEW

Dear Rabbi Harlig:

Your Request for a Site Development Plan Review FOR A PROPOSED 84,276 SQUARE FOOT, 44-FOOT TALL PRIVATE SCHOOL AND A WAIVER OF THE PERIMETER LANDSCAPE BUFFER REQUIREMENTS TO ALLOW NO LANDSCAPING ALONG THE NORTH AND EAST PROPERTY LINES AND ALONG PORTIONS OF THE SOUTH AND WEST PROPERTY LINES WHERE A MINIMUM EIGHT FOOT WIDE BUFFER IS REQUIRED on 4.01 acres adjacent to the west side of Vista Drive, approximately 530 feet south of Charleston Boulevard (APNs 162-06-510-007, 008, 009, and 017), R-E (Residence Estates) and P-R (Professional Office and Parking) Zones, Ward 1 (Tarkanian) NOTE: THIS APPLICATION HAS BEEN AMENDED TO 77,881 SQUARE FOOT, 35-FOOT HIGH PRIVATE SCHOOL WITH NO LANDSCAPE WAIVERS REQUESTED, was considered by the Planning Commission on November 8, 2007.

The Planning Commission voted to recommend **APPROVAL** of your request, subject to the following:

Planning and Development

1. No high school shall be constructed or operated on the site.
2. This approval shall be void two years from the date of final approval, unless a building permit has been issued for the principal building on the site. An Extension of Time may be filed for consideration by the City of Las Vegas.
3. Recordation of a reversionary parcel map or administrative joining consolidating the three adjoining parcels adjacent to Vista Drive (APNs 162-06-510-007, -008, and -009) on the site prior to issuance of any building or grading permits.

Mayor
Oscar B. Goodman

City Council
Gary Reese
(Mayor Pro Tem)

Larry Brown
Steve Wolfson
Lois Tarkanian
Steven D. Ross
Ricki Y. Barlow

City Manager
Douglas A. Selby



07101-001-06-07

4. Recordation of a shared parking agreement between the property located at 1253 Arville Street and the resulting parcel created from the remapping of the three adjoining parcels adjacent to Vista Drive to be filed with the City Attorney's Office prior to issuance of any building or grading permits.
5. All development shall be in conformance with the site plan, landscape plan, floor plans, and building elevations date stamped: 9/28/07, except as amended by conditions herein.
6. Pre-planting and post-planting landscape inspections are required to ensure the appropriate plant material, location, size of planters, and landscape plans are being utilized. The Planning and Development Department must be contacted to schedule an inspection prior to the start of the landscape installation and after the landscape installation is completed. A certificate of occupancy will not be issued or the final inspection will not be approved until the landscape inspections have been completed.
7. Reflective glazing at the pedestrian level is prohibited. Glazing above the pedestrian level shall be limited to a maximum reflectance rating of 22% (as defined by the National Institute of Standards and Technology).
8. All mechanical equipment, air conditioners and trash areas shall be fully screened in views from the abutting streets.
9. All utility boxes exceeding 27 cubic feet in size shall meet the standards of LVMC Title 19.12.040.
10. Parking lot lighting standards shall be no more than 30 feet in height and shall utilize downward-directed lights with full cut-off luminaries. Lighting on the exterior of buildings shall be shielded and shall be downward-directed. Non-residential property lighting shall be directed away from residential property or screened, and shall not create fugitive lighting on adjacent properties.
11. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.
12. All City Code requirements and design standards of all City Departments must be satisfied, except as modified herein.

Public Works


13. Coordinate with the City Surveyor to determine whether a Reversionary Map or other map is necessary; comply with the recommendations of the City Surveyor.
14. Construct all incomplete half-street improvements, including transition paving, on Vista Street adjacent to this site concurrent with development of this site. All existing paving damaged or removed by this development shall be restored at its original location and to its original width concurrent with development of this site. Extend all required underground utilities, such as electrical, telephone, etc., located within public rights-of-way, past the boundaries of this site prior to construction of hard surfacing (asphalt or concrete).
15. Remove all substandard public street improvements and unused driveway cuts adjacent to this site, if any, and replace with new improvements meeting current City Standards concurrent with development of this site.
16. Submit an application to the Land Development section of the Department of Public Works for a deviation from Standard Drawing #222a for all of the driveways accessing this site from Vista Drive and Arville Street. Pan driveways are acceptable on Arville Street.
17. Unless otherwise allowed by the City Engineer, construct sidewalk on at least one side of all access drives connecting this site to the adjacent public streets concurrent with development of this site. The connecting sidewalk shall extend from the sidewalk on the public street to the first intersection of the on-site roadway network and shall be terminated on-site with a handicap ramp.
18. All landscaping and private improvements installed with this project shall be situated and maintained so as to not create sight visibility obstructions for vehicular traffic at all development access drives and abutting street intersections.
19. Coordinate with the Collection System Planning Section of the Department of Public Works to determine an appropriate location for public sewer connection and the location for sewer stubs prior to the submittal of any construction drawings. Provide public sewer easements for all public sewers not located within existing public street right-of-way prior to the issuance of any permits as required by the Department of Public Works. Improvement Drawings submitted to the City for review shall not be approved for construction until all required public sewer easements necessary to connect this site to the existing public sewer system have been granted to the City.

20. A Traffic Impact Analysis must be submitted to and approved by the Department of Public Works prior to the issuance of any building or grading permits, submittal of any construction drawings or the recordation of a Map subdividing this site. Comply with the recommendations of the approved Traffic Impact Analysis prior to occupancy of the site. The Traffic Impact Analysis shall also include a section addressing Standard Drawings #234.1 #234.2 and #234.3 to determine additional right-of-way requirements for bus turnouts adjacent to this site, if any; dedicate all areas recommended by the approved Traffic Impact Analysis. All additional rights-of-way required by Standard Drawing #201.1 for exclusive right turn lanes and dual left turn lanes shall be dedicated prior to or concurrent with the commencement of on-site development activities unless specifically noted as not required in the approved Traffic Impact Analysis. If additional rights-of-way are not required and Traffic Control devices are or may be proposed at this site outside of the public right-of-way, all necessary easements for the location and/or access of such devices shall be granted prior to the issuance of permits for this site. Phased compliance will be allowed if recommended by the approved Traffic Impact Analysis. No recommendation of the approved Traffic Impact Analysis, nor compliance therewith, shall be deemed to modify or eliminate any condition of approval imposed by the Planning Commission or the City Council on the development of this site.
21. A Drainage Plan and Technical Drainage Study must be submitted to and approved by the Department of Public Works prior to the issuance of any building or grading permits, submittal of any construction drawings or the submittal of a Map subdividing this site, whichever may occur first. Provide and improve all drainageways recommended in the approved drainage plan/study. The developer of this site shall be responsible to construct such neighborhood or local drainage facility improvements as are recommended by the City of Las Vegas Neighborhood Drainage Studies and approved Drainage Plan/Study concurrent with development of this site. In lieu of constructing improvements, in whole or in part, the developer may agree to contribute monies for the construction of neighborhood or local drainage improvements, the amount of such monies shall be determined by the approved Drainage Plan/Study and shall be contributed prior to the issuance of any building or grading permits, or the recordation of a Map subdividing this site, whichever may occur first, if allowed by the City Engineer.

Rabbi Shea Harlig
SDR-18342 - Page Five
November 9, 2007

This item will be considered by the City Council on **December 5, 2007**, at 1:00 P.M. in the Council Chambers of City Hall, 400 Stewart Avenue, Las Vegas, Nevada. ***The Council requires that you or your representative be present at this meeting.*** If you or your representative chooses not to attend, the City Council may act in your absence without your input.

Sincerely,

A handwritten signature in black ink that reads "Andrew P. Reed". The signature is written in a cursive style with a large, stylized "R" at the end.

Andrew P. Reed, AICP
Planning Supervisor
Current Planning Division

AR:dm

cc: Ms. Sue Gray
Perlman Design Group
2230 Corporate Circle, Suite #200
Henderson, Nevada 89074