




LAS VEGAS CITY COUNCIL

OSCAR B. GOODMAN
MAYOR

GARY REESE
MAYOR PRO TEM

LARRY BROWN
LAWRENCE WEEKLY
STEVE WOLFSON
LOIS TARKANIAN
STEVEN D. ROSS

DOUGLAS A. SELBY
CITY MANAGER



063221

August 11, 2006

Ms. Terri Strum
Centennial Gateway, LLC
7448 West Sahara Avenue
Las Vegas, Nevada 89117

RE: ABEYANCE - SDR-14101 - SITE DEVELOPMENT PLAN REVIEW

Dear Ms. Strum:

Your request for a Site Development Plan Review FOR A PROPOSED COMMERCIAL DEVELOPMENT CONSISTING OF A 15,000 SQUARE-FOOT RETAIL DEVELOPMENT (DRUG STORE) AND A 2,463 SQUARE-FOOT RESTAURANT WITH DRIVE-THROUGH on 2.49 acres at the northeast corner of Centennial Center Boulevard and Ann Road (APN 125-27-411-010), T-C (Town Center) Zone [SC-TC (Service Commercial - Town Center) Town Center Special Land Use Designation], Ward 6 (Ross), was considered by the Planning Commission on August 10, 2006.

The Planning Commission voted to **APPROVE** your request, subject to the following:

Planning and Development

1. Conformance to all conditions of approval for the master development plan for the site, SDR-2208, except as amended by conditions herein.
2. The previously-approved Site Development Plan Review for the subject portion of the development site, SDR-5989, shall be expunged.
3. Approval of and conformance to the Conditions of Approval for Special Use Permit SUP-14774 and Site Development Plan Review SDR-14777 shall be required.
4. This approval shall be void two years from the date of final approval, unless a building permit has been issued for the principal building on the site. An Extension of Time may be filed for consideration by the City of Las Vegas.
5. All development shall be in conformance with the site plan, landscape plan, and building elevations, date stamped 07/31/06, except as amended by conditions herein.

CITY OF LAS VEGAS
400 STEWART AVENUE
LAS VEGAS, NEVADA 89101

VOICE 702.229.6011

TTY 702.386.9108

www.lasvegasnevada.gov

18112-001-06-05
CLV 7009



6. A technical landscape plan, signed and sealed by a Registered Architect, Landscape Architect, Residential Designer or Civil Engineer, must be submitted prior to or at the same time application is made for a building permit. A permanent underground sprinkler system is required, and shall be permanently maintained in a satisfactory manner; the landscape plan shall include irrigation specifications.
7. Pre-planting and post-planting landscape inspections are required to ensure the appropriate plant material, location, size of planters, and landscape plans are being utilized. The Planning and Development Department must be contacted to schedule an inspection prior to the start of the landscape installation and after the landscape installation is completed. A certificate of occupancy will not be issued or the final inspection will not be approved until the landscape inspections have been completed.
8. A revised site plan shall be submitted to and approved by the Planning and Development Department prior to the time application is made for a building permit to reflect gated and roofed trash enclosures and a loading zone for each building.
9. Reflective glazing at the pedestrian level is prohibited. Glazing above the pedestrian level shall be limited to a maximum reflectance rating of 22% (as defined by the National Institute of Standards and Technology).
10. All mechanical equipment, air conditioners and trash areas shall be fully screened in views from the abutting streets.
11. All utility boxes exceeding 27 cubic feet in size shall meet the standards of LVMC Title 19.12.040.
12. Parking lot lighting standards shall be no more than 30 feet in height and shall utilize downward-directed lights with full cut-off luminaries. Lighting on the exterior of buildings shall be shielded and shall be downward-directed. Non-residential property lighting shall be directed away from residential property or screened, and shall not create fugitive lighting on adjacent properties.
13. All signage shall be in conformance with the approved Master Sign Plan for the subject site.
14. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.

15. All City Code requirements and design standards of all City Departments must be satisfied, except as modified herein.


Public Works

16. An update to the previously approved Traffic Impact Analysis must be submitted to and approved by the Department of Public Works prior to the issuance of any building or grading permits, or the submittal of any construction drawings. Comply with the recommendations of the updated Traffic Impact Analysis prior to occupancy of the site. The Traffic Impact Analysis shall also include a section addressing Standard Drawings #234.1 #234.2 and #234.3 to determine additional right-of-way requirements for bus turnouts adjacent to this site, if any; dedicate all areas recommended by the approved Traffic Impact Analysis. All additional rights-of-way required by Standard Drawing #201.1 for exclusive right turn lanes and dual left turn lanes shall be dedicated prior to or concurrent with the commencement of on-site development activities unless specifically noted as not required in the approved Traffic Impact Analysis. Phased compliance will be allowed if recommended by the approved Traffic Impact Analysis. No recommendation of the approved Traffic Impact Analysis or compliance therewith, shall be deemed to modify or eliminate any condition of approval imposed by the Planning Commission or the City Council on the development of this site.
17. An update to the previously approved Drainage Plan and Technical Drainage Study must be submitted to and approved by the Department of Public Works prior to the issuance of any grading or building permits, or the submittal of any construction drawings, whichever may occur first. Provide and improve all drainageways as recommended in the approved drainage plan/study.
18. Site development to comply with all applicable conditions of approval for the Centennial Gateway Commercial Subdivision and all other site-related actions.

Ms. Terri Strum
SDR-14101 - Page Four
August 11, 2006

This action by the Planning Commission on *August 10, 2006* is final unless a written appeal is filed with the City Clerk within ten days of the date of the Planning Commission's decision or there is a review action filed by the City Council within the same time period. The Notice of Final Action was filed with the Las Vegas City Clerk on *August 11, 2006*.

Sincerely,



Douglas J. Rankin, Planning Supervisor
Planning and Development Department
Current Planning Division

DJR:dm

cc: Mr. Bruce Barton
Territory, Inc.
7448 West Sahara Avenue
Las Vegas, Nevada 89117

Ms. Jennifer Lazovich
KKR&F
3800 Howard Hughes Parkway, 7th Floor
Las Vegas, Nevada 89109