



MAYOR
OSCAR B. GOODMAN

CITY COUNCIL
GARY REESE
(MAYOR PRO-TEM)
LARRY BROWN
LYNETTE B. McDONALD
LAWRENCE WEEKLY
MICHAEL MACK
JANET MONCRIEF

CITY MANAGER
DOUGLAS A. SELBY



040944

January 8, 2004

Mr. Dave Grant
Dermody Properties
1200 Financial Boulevard
Reno, Nevada 89502

RE: SDR-3278 - SITE DEVELOPMENT PLAN REVIEW
CITY COUNCIL MEETING OF JANUARY 7, 2004
Related to ZON-3276 & WVR-3355

Dear Mr. Grant:

The City Council at a regular meeting held January 7, 2004 APPROVED the request for a Site Development Plan Review FOR A PROPOSED 92-LOT SINGLE-FAMILY RESIDENTIAL DEVELOPMENT on 8.32 acres between Martin L. King Boulevard and Shadow Lane, approximately 1,250 feet north of Alta Drive (APN: 139-33-102-020), C-1 (Limited Commercial) Zone [PROPOSED: R-PD11 (Residential Planned Development – 11 Units per Acre)]. The Notice of Final Action was filed with the Las Vegas City Clerk on January 8, 2004. This approval is subject to:

Planning and Development

1. A Rezoning [ZON-3276] to an R-PD11 (Residential Planned Development - 11 Units per Acre) Zoning District and a Waiver to certain Title 18 standards (WVR-3355) approved by the City Council.
2. This Site Development Plan Review shall expire two years from date of final approval unless it is exercised or an Extension of Time is granted by the City Council.
3. All development shall be in conformance with the site plan and building elevations, except as amended by conditions herein.
4. The standards for this development shall include the following: minimum lot size of 1,750 square feet, minimum distance between buildings of 6 feet, and building height shall not exceed three stories or 35 feet, whichever is less.
5. The setbacks for this development shall be a minimum of 18 feet to the front of the house, 18 feet to the front of the garage as measured from back of sidewalk or from back of curb if no sidewalk is provided, 3 feet on the side, 3 feet on the corner side, and 10 feet in the rear.

CITY OF LAS VEGAS
400 STEWART AVENUE
LAS VEGAS, NEVADA 89101

VOICE 702.229.6011
TTY 702.386.9108
www.ci.las-vegas.nv.us

6. Prior to the submittal of a building permit, the applicant shall meet with Planning and Development Department staff to develop a comprehensive address plan for the subject site. A copy of the approved address plan shall be submitted with any future building permit applications related to the site.
7. The landscape plan shall be revised and approved by Planning and Development Department staff, prior to the time application is made for a building permit, to reflect a sufficient number of minimum 24-inch box trees planted a maximum of 30 feet on-center and a minimum of four five-gallon shrubs for each tree within provided planters, to meet or exceed Code requirements.
8. A landscaping plan must be submitted prior to or at the same time application is made for a building permit.
9. Air conditioning units shall not be mounted on rooftops.
10. All utility boxes exceeding 27 cubic feet in size shall meet the standards of Title 19.12.050.
11. Any property line wall shall be a decorative block wall, with at least 20 percent contrasting materials. Wall heights shall be measured from the side of the fence with the least vertical exposure above the finished grade, unless otherwise stipulated.
12. A fully operational fire protection system, including fire apparatus roads, fire hydrants and water supply, shall be installed and shall be functioning prior to construction of any combustible structures.
13. All City Code requirements and design standards of all City departments must be satisfied.
14. The applicant shall ensure that a deed restriction is placed on the subject property which prevents any direct access from the site to Martin L. King Boulevard, other than emergency access. The City shall be party to this deed restriction.


Public Works

15. Prior to the issuance of any permits, coordinate with the northerly commercial property and the Collection Systems Section of the Department of Public Works to determine if any existing sewer lines remain on this site. If necessary, a sewer relocation and abandonment plan shall be approved by the City of Las Vegas and new sewer easements granted prior to or concurrent with the recordation of a Final Map for this site.

Mr. Dave Grant
SDR-3278 – Page Three
January 8, 2004

16. Meet with the Traffic Engineering Representative in Land Development for assistance in the possible redesign of the proposed driveway access, on site circulation and parking lot layout prior to the submittal of any construction plans or the issuance of any permits, whichever may occur first. Driveways shall be designed, located and constructed in accordance with Standard Drawing #222a.
17. Meet with the Fire Protection Engineering Section of the Department of Fire Services prior to submittal of a Tentative Map for this site. The design and layout of all onsite private circulation and access drives shall meet the approval of the Department of Fire Services.
18. A Homeowner's Association shall be established to maintain all perimeter walls, private roadways, landscaping and common areas created with this development. All landscaping shall be situated and maintained so as to not create sight visibility obstructions for vehicular traffic at all development access drives and abutting street intersections.
19. Site development to comply with all applicable conditions of approval for ZON-3276 and all other subsequent site-related actions.
20. The approval of all Public Works related improvements shown on this Site Development Plan Review is in concept only. Specific design and construction details relating to size, type and/or alignment of improvements, including but not limited to street, sewer and drainage improvements, shall be resolved prior to submittal of a Tentative Map or construction drawings, whichever may occur first. No deviations from adopted City Standards shall be allowed unless specific written approval for such is received from the City Engineer prior to the submittal of a Tentative Map or construction drawings, whichever may occur first.
21. The final layout of the subdivision shall be determined at the time of approval of the Tentative Map.

Sincerely,



Angela Crolli
Deputy City Clerk II for
Barbara Jo Ronemus, City Clerk

cc: See Attached List

Mr. Dave Grant
SDR-3278 – Page Four
January 8, 2004

cc: Planning and Development Dept.
Development Coordination-DPW
Dept. Of Fire Services

Mr. Bobby Lewis
Singature Homes
801 South Rancho Drive, Suite #E-4
Las Vegas, Nevada 89106

Ms. Katheryn Grider
Orion Engineering & Surveying
3068 East Sunset Road, Suite #9
Las Vegas, Nevada 89120