

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28

BILL NO. 2011-12

ORDINANCE NO. 6141

AN ORDINANCE TO ADOPT THE 2009 EDITION OF THE UNIFORM PLUMBING CODE, TOGETHER WITH AMENDMENTS THERETO, AND TO PROVIDE FOR OTHER RELATED MATTERS.

Sponsored by: Councilman Steven D. Ross

Summary: Adopts the 2009 Edition of the Uniform Plumbing Code, together with amendments thereto, as the City's Plumbing Code.

**THE CITY COUNCIL OF THE CITY OF LAS VEGAS DOES HEREBY ORDAIN
AS FOLLOWS:**

SECTION 1: Title 16, Chapter 28, Section 10, of the Municipal Code of the City of Las Vegas, Nevada, 1983 Edition, is hereby amended to read as follows:

16.28.010: Those certain documents, [three] copies of each being on file in the Office of the City Clerk, and designated as follows, are adopted by reference and made a part of this Code, to the same effect as if set out herein in full:

(A) Uniform Plumbing Code, [2006] 2009 Edition, including its Standards and Appendices, except as otherwise indicated, designated as Part 1 of this Chapter; and

(B) A document entitled ["Southern Nevada Amendments to the 2006 Uniform Plumbing Code,"] "Southern Nevada Amendments to the 2009 Uniform Plumbing Code." adding to, deleting from and amending the Uniform Plumbing Code, [2006] 2009 Edition, designated as Part 2 of this Chapter.

SECTION 2: The document entitled Southern Nevada Amendments to the 2009 Uniform Plumbing Code is attached hereto.

SECTION 3: The document entitled "Southern Nevada Amendments to the Uniform Plumbing Code, 2009 Edition," is amended by adding thereto the following language:

Section 313.4 of the Uniform Plumbing Code, 2009 Edition, is amended by adding thereto a new sentence, reading as follows:

All copper piping under the slab must be sleeved.

SECTION 4: The Uniform Plumbing Code, 2006 Edition, and the 2006 Southern

1 Nevada Plumbing Code Amendments, as amended, are hereby repealed in their entirety.

2 SECTION 5: This Ordinance shall become effective on July 5, 2011.

3 SECTION 6: If any section, subsection, subdivision, paragraph, sentence, clause or
4 phrase in this ordinance or any part thereof is for any reason held to be unconstitutional or invalid or
5 ineffective by any court of competent jurisdiction, such decision shall not affect the validity or
6 effectiveness of the remaining portions of this ordinance or any part thereof. The City Council of the
7 City of Las Vegas hereby declares that it would have passed each section, subsection, subdivision,
8 paragraph, sentence, clause or phrase thereof irrespective of the fact that any one or more sections,
9 subsections, subdivisions, paragraphs, sentences, clauses or phrases be declared unconstitutional,
10 invalid or ineffective.


11 SECTION 7: Whenever in this ordinance any act is prohibited or is made or declared
12 to be unlawful or an offense or a misdemeanor, or whenever in this ordinance the doing of any act is
13 required or the failure to do any act is made or declared to be unlawful or an offense or a
14 misdemeanor, the doing of such prohibited act or the failure to do any such required act shall
15 constitute a misdemeanor and upon conviction thereof, shall be punished by a fine of not more than
16 \$1,000.00 or by imprisonment for a term of not more than six months, or by any combination of such
17 fine and imprisonment. Any day of any violation of this ordinance shall constitute a separate offense.

18 SECTION 8: All ordinances or parts of ordinances or sections, subsections, phrases,
19 sentences, clauses or paragraphs contained in the Municipal Code of the City of Las Vegas, Nevada,
20 1983 Edition, in conflict herewith are hereby repealed.

21 PASSED, ADOPTED and APPROVED this 6th day of APRIL, 2011.

22 APPROVED:

23
24 By 
25 OSCAR B. GOODMAN, Mayor

24 ATTEST:
25 
26 BEVERLY K. BRIDGES, MMC
27 City Clerk

27 APPROVED AS TO FORM:
28 Val Steed 2-16-11
Date

1 The above and foregoing ordinance was first proposed and read by title to the City Council
2 on the 2nd day of March, 2011, and referred to a committee for recommendation; thereafter
3 the committee reported favorably on said ordinance on the 6th day of April, 2011, which as
4 a regular meeting of said Council; that at said regular meeting, the proposed ordinance
5 was read by title to the City Council as first introduced and adopted by the following vote:

6 VOTING "AYE": Mayor Goodman and Councilmembers Reese, Tarkanian, Ross,
Barlow and Anthony

7 VOTING "NAY": None

8 EXCUSED: None

9 ABSTAINED: None

10 DID NOT VOTE: Councilmember Wolfson

11
12 APPROVED:

13
14 
OSCAR B. GOODMAN, Mayor

15 ATTEST:

16 
17 BEVERLY K. BRIDGES, MMC City Clerk



Southern Nevada Building
Officials
o/o City of Las Vegas
Building & Safety Dept
713 S. 4th Street
Las Vegas, NV 89101

Phone: 702-229-6257

Fax: 702-382-1731

Email:

chknight@lasvegasnevada.gov

MEMBERS

Chris Knight, Chair
City of Las Vegas

Greg Blackburn
City of North Las Vegas

Ron Nybo
City of Boulder City

Ron Lynn
Clark County

Kurt Sawyer
City of Mesquite

Brent Steed
Pahrump Regional
Planning District
(Nye County)

Michael Bouse
City of Henderson

Lisa Conner
Clark County School District

SOUTHERN NEVADA AMENDMENTS

TO THE

2009

UNIFORM PLUMBING CODE

Approved by SNBO

July 23, 2010

Chapter 1 Administration.

Delete Chapter 1, with the exception of Sections 101.1, 101.2 and 103.1.3 and revise Section 103.1.3, as follows:

103.1.3 Plumbing Licensing Provision. Provision for licensing shall be determined by the Administration Provision of Authority Having Jurisdiction.

Section 205 Definitions.

Add a new definition to Section 205 to be placed in alphabetical order, as follows:

Combustible Construction - Combustible construction shall mean work within any building or structure classified as Type III, Type IV or Type V as defined in the Building Code. Plastic piping is not permitted in Type I and Type II buildings.

Section 311.4 Prohibited Fittings and Practices.

Revise Section 311.4 by deleting the second sentence and adding a new exception, as follows:

311.4 Except as hereinafter provided in Sections 908.0, 909.0 and 910.0, no vent pipe shall be used as a soil or waste pipe, nor shall any soil or waste pipe be used as a vent.

Exception: Single stack DWV systems may be used provided they are designed by a Nevada registered Mechanical Engineer and approved by the authority having jurisdiction.

Section 402.2 Water Closets.

Revise Section 402.2 in its entirety, as follows:

402.2 Water Closets. Water closets, either flush tank, flushometer tank, or flushometer valve operated, shall have an average consumption of 1.6 gallons (6.1 liters) of water per flush. A timing device or other mechanism which will automatically flush a water closet periodically or continually is prohibited.

Section 402.3 Urinals.

Revise Section 402.3 in its entirety, as follows:

402.3 Urinals. Urinals shall have an average water consumption of 1 gallon (3.8 liters) of water per flush. A timing device or other mechanism which will automatically flush a urinal periodically or continually is prohibited.

Section 411.2 Location of Floor Drains.

Add a new Section, 411.2.4, as follows:

411.2.4 All Fire Pump rooms shall be provided with a (3) inch (76 mm) minimum floor drain which must be connected to an approved trap primer.

Section 412.1 Minimum Number of required Fixtures.

Delete Sections 412.2 through 412.6 and Table 4-1 in their entirety and revise Section 412.1, as follows:

412.1 Minimum Number of Required Fixtures. Plumbing fixtures shall be provided for the type of occupancy and in the minimum number as required by the currently adopted Building Code.

Section 413.1 Limitation of Hot Water Temperature for Public Lavatories.

Add a new Exception to Section 413.1, as follows:

413.1 Limitation of Hot Water Temperature for Public Lavatories. Hot water delivered from public use lavatories shall be limited to a maximum temperature of 120°F (49°C) by a device that conforms to ASSE 1070 or CSA B125.3. The water heater thermostat shall not be considered a control for meeting this provision.

Exception: An ASSE 1017 listed device may be acceptable when the maximum temperature setting for the device is 120°F.

Section 414.5 The Limitation of Hot Water in Bathtubs and Whirlpool Bathtubs.

Add a new Exception to Section 414.5, as follows:

414.5 The Limitation of Hot Water in Bathtubs and Whirlpool Bathtubs. The maximum hot water temperature discharging from the bathtub and whirlpool bathtub filler shall be limited to 120°F (49°C) by a device that conforms to ASSE 1070 or CSA B125.3. The water heater thermostat shall not be considered a control for meeting this provision.

Exception: An ASSE 1017 listed device may be acceptable when the maximum temperature setting for the device is 120°F.

Section 416.3 Limitation of Water Temperature in Bidets.

Add a new Exception to Section 416.3, as follows:

416.3 Limitation of Water Temperature in Bidets. The maximum hot water temperature discharging from a bidet shall be limited to 110°F (43°C) by a device that conforms to ASSE 1070 or CSA B125.3. The water heater thermostat shall not be considered a control for meeting this provision.

Exception: An ASSE 1017 listed device may be acceptable when the maximum temperature setting for the device is 120°F. In no case shall the setting for the bidet exceed 110°F.

Section 509.3.1 Access to Appliances on Roofs.

Revise Section 509.3.1, as follows:

509.3.1 Gas utilization appliances located on roofs or other elevated locations shall be accessible by permanent roof access ladders, as follows:

- (1) Each ladder shall have side railings which extend at least thirty (30) inches (762 mm) above the roof or parapet wall.
- (2) Each ladder shall be a minimum of fourteen (14) inches (356 mm) in width.
- (3) Each ladder rung shall be spaced at a maximum of fourteen (14) inches (356 mm) on center.
- (4) Each ladder shall have a minimum of a six (6) inch (152 mm) toe space.
- (5) Each ladder shall have intermediate horizontal landings whenever the ladder height exceeds eighteen feet (5486 mm) above finished grade. Landings shall be placed at eighteen foot (5486 mm) intervals, maximum.

Exceptions:

1. Permanent exterior ladders providing roof access need not extend closer than eight (8) feet (2438 mm) to the finish grade.
2. A portable ladder may be used for access for Group R Division 3 and 4 and U occupancies.

3. Permanent ladders for equipment access need not be provided at parapets or walls less than thirty (30) inches (762mm) in height.

Section 510.6 Gas vents.

Add a new Exception to Section 510.6.2, item #1, as follows:

510.6.2 A gas vent shall terminate in accordance with one of the following:

- (1) Above the roof surface with a listed cap or listed roof assembly. Gas vents twelve (12) inches (300 mm) in size or smaller with listed caps shall be permitted to be terminated in accordance with Figure 5-2, provided they are at least eight (8) feet (2.4 m) from a vertical wall or similar obstruction. Other gas vents shall terminate not less than two (2) feet (0.6 m) above the highest point where they pass through the roof and at least two (2) feet (0.6 m) exceeding any portion of a building within ten (10) feet (3.1 m).

Exception: A single-family residence having gas vents twelve (12) inches (300 mm) in size or smaller with listed caps shall be permitted to be terminated in accordance with Figure 5-2, provided they are at least four (4) feet (1.2 m) from a vertical wall or similar obstruction.

Items (2) through (6) remain unchanged.

Section 603.3 General Requirements.

Revise Section 603.3.3, as follows:

603.3.3 The premise owner or responsible person shall have the backflow prevention assembly tested by a certified backflow assembly tester at the time of installation, repair, or relocation and not less than on an annual schedule thereafter, or more often when required by the Authority Having Jurisdiction. The certified tester shall leave a copy of their backflow certification on site along with a copy of the certification of each device tested. These documents shall be recorded into the permanent record at the time of installation. The periodic testing shall be performed in accordance with the procedures referenced in Table 14-1 by a tester qualified in accordance with those standards.

Section 603.4.12 Potable Water Supply to Carbonators.

Revise Section 603.4.12, as follows:

603.4.12 Potable Water Supply to Carbonators. Potable water supply to carbonators shall be protected by a listed reduced pressure principle backflow preventer as approved by the authority having jurisdiction.

Section 604.0 Materials.

Add a new Section 604.1.1, as follows:

604.1.1 Plastic piping shall be limited to buildings defined as combustible construction by this code.

Section 608.5 Relief Valves.

Revise Section 608.5 Relief Valves, as follows:

608.5 Relief Valves. Relief valves located inside a building shall be provided with a drain, not smaller than the relief valve outlet, of galvanized steel, hard-drawn copper piping and fittings, CPVC, flexible corrugated connectors complying with 604.12, or listed relief valve drain tube with fittings that will not reduce the internal bore of the pipe or tubing (straight lengths as opposed to coils) and shall extend from the valve to the outside of the building with the end of the pipe not more than two (2) feet (610 mm) nor

less than six (6) inches (152 mm) above the ground or the flood level of the area receiving the discharge and pointing downward. Temperature and Pressure Relief (T & P) drains shall discharge to the exterior of the building unless structural conditions or the manufacturers listing prevent this termination. T & P drains may discharge through an air gap into a secondary clothes washer port, or through an air gap in a floor sink or a floor drain provided they are located in normally unoccupied areas. No part of such drain pipe shall be trapped or subject to freezing. The terminal end of the drain pipe shall not be threaded.

Section 701.0 Materials.

Revise Section 701.0 by adding a new Section 701.1.2.1 Materials, as follows:

701.1.2.1 Materials. Plastic piping used for drainage waste and vent systems shall be limited to buildings defined as combustible construction by this code.

Section 704.3 Fixture Connections (Drainage)

Revise Section 704.3, as follows:

704.3 Pot sinks, scullery sinks, dishwashing sinks, silverware sinks, commercial dishwashing machines and other similar fixtures shall be indirectly connected to the drainage systems by means of an air gap.

Section 707.10 Cleanouts

Add a new Exception to Section 707.10, as follows:

707.10 Cleanout fittings shall be not less in size than those given in Table 7-6.

Exception: Where a 2-1/2" (inch) cleanout is required, a 2" (inch) cleanout may be used for horizontal branch waste lines.

Section 710.1 Drainage of Fixtures Located Below the Next Upstream Manhole or Below the Main Sewer level.

Delete Section 710.1, in its entirety and replace, as follows:

710.1 Drainage Piping servicing fixtures which have flood level rims located below the elevation of the next upstream manhole cover of the public or private sewer serving such drainage piping shall be protected from backflow of sewage by installing an approved type backwater valve; Other than a single dwelling unit served by an individual sewer, fixtures above such elevation shall not discharge through the backwater valve.

Section 801.2.2 Food and Beverage Handling Establishments.

Revise Section 801.2.2, as follows:

801.2.2 For walk-in coolers, floor drains shall be permitted to be connected to a separate drainage line discharging into an outside receptor. The flood level rim of the receptor shall be not less than six (6) inches (152 mm) lower than the lowest floor drain. Such floor drains shall be trapped and individually vented. Cleanouts shall be provided at every ninety (90) degree (1.6 rad) turn and shall be accessibly located. Such waste shall discharge through an airgap into a trapped and vented receptor, except that full-size airgap is required where the indirect waste pipe may be under vacuum.

Section 801.2.4 Floor Sinks.

Revise Section 801.2 by adding a new Section 801.2.4 Floor Sinks, as follows:

801.2.4 Floor Sinks. Floor sinks shall be installed flush with the finished floor and shall be accessible for cleaning.

Section 804.1 Indirect Waste Receptors.

Revise Section 804.1 by adding a new second paragraph, as follows:

When any indirect waste piping other than the discharge from the clothes washer is terminated into a washer box, a double port clothes washer box shall be used. The second port shall be permanently connected to the vertical receptor standpipe via a wye branch fitting or a listed multiport clothes washer box may be used. The clothes washer shall discharge through an air break into the primary receptor standpipe. All other indirect waste piping shall discharge into the secondary port through an air gap.

Section 903.0 Materials.

Revise Section 903.1 by adding a new section 903.1.2.1, as follows:

903.1.2.1 Plastic piping used for drainage waste and vent systems shall be limited to buildings defined as combustible construction by this code.

1009.0 Gravity Grease Interceptors.

Delete Sections 1009.0 through 1017.2, retain Table 10-3 and add new Sections 1009.0, 1010.0, 1011.0, 1012.0 and 1013.0, as follows:

1009.0 - Gravity Grease interceptors

1009.1 General. A grease interceptor shall be provided for proper handling of liquid wastes containing grease. A grease interceptor as described in these standards shall be installed in any business establishment with kitchen facilities including restaurants, cafes, lunch counters, cafeterias, supermarkets, convenience stores, bakeries, bars and clubs, hotels, hospitals, sanitariums, factory or school kitchens, or any other commercial establishment where grease may be introduced into the sewer system.

Special consideration shall be given to every fish, fowl and animal slaughterhouse or establishment; every fish, fowl and meat packing or curing establishment; every soap factory, tallow rendering, fat rendering and hide curing establishment; or any other establishment from which considerable amounts of grease are likely to be discharged into the sewer system. Written application describing exact operation and anticipated volumes of grease shall be made to the Sanitation Authority Having Jurisdiction to determine the standards for such systems.

1009.2 Fixtures. The waste discharge from fixtures and equipment which may contain grease from the businesses set out previously shall be drained through a grease interceptor or grease interceptors. Fixtures such as, but not limited to, the following are included: scullery sinks, pot and pan sinks, dishwashing machines, soup kettles and similar cooking equipment, trash compactors, floor drains in grease generating areas, and trash can wash areas.

1009.3 Prohibited fixtures. The waste lines from toilets, urinals, and other similar fixtures shall not drain through a grease interceptor.

1009.4 Location.

- (1) Grease interceptors shall be so installed and connected that they shall be at all times easily accessible for inspection, cleaning and removal of the intercepted grease.
- (2) Grease interceptors shall be placed as close as practical to the fixtures served.

- (3) Grease interceptors shall be located on the exterior of buildings unless specifically approved otherwise in writing by the health district.
- (4) Grease interceptors shall be so located as to be accessible for service without the use of ladders or the removal of bulky equipment.
- (5) Location of all grease interceptors shall be shown on the approved plans.
- (6) Each grease interceptor shall serve only one business establishment. Multiple business connections to a single interceptor are not permitted. Unless approved by the sanitation authority in writing.
- (7) An accessible hose bib shall be located within 25 feet (7620 mm) of every grease interceptor.

1009.5 Size.

- (1) Grease interceptors shall be sized in accordance with Table 10-3. Interceptors shall not be more than one size larger than required in Table 10-3.

NOTE: For situations not covered by Table 10-3, a submittal showing the interceptor size and calculations shall be approved by the sanitation authority prior to building official plan approval. For business establishments other than commercial restaurants, a specific submittal shall be approved by the sanitation authority prior to building official plan approval. Such designs shall be prepared by a Nevada Registered Engineer.

- (2) All grease interceptors shall have a minimum of two compartments with a minimum of 3 inch (76.2 mm) diameter fittings designed for grease retention. The fittings shall be installed in the following manner: A sanitary tee shall be installed at the inlet, a sanitary tee on the inlet side of the interceptor baffle, and a sanitary tee installed at the outlet.
- (3) There shall be adequate access for cleaning all areas of the separator. A minimum of one access point into each compartment within the separator shall be provided. In addition, no access points shall be further apart than 10 feet (3048 mm) regardless of the number of compartments. Separator covers shall be of gas-tight construction. Interceptor covers shall have a minimum opening dimension of twenty (20) inches (508 mm) in diameter.
- (4) All waste shall enter the grease interceptor through the inlet pipe.
- (5) Grease interceptors shall be so designed that they will not become air bound. Each interceptor shall be properly vented with a relief vent located on the outlet side of the interceptor.
- (6) Cleanouts shall be installed in the drainage piping inlet and outlet side of each grease interceptor and the outlet side of each sample box.
- (7) Each fixture discharging into a grease interceptor shall be individually trapped and vented in an approved manner.
- (8) Each grease interceptor shall have an approved water seal of not less than two (2) inches (50.8 mm) in depth or the diameter of its outlet whichever is greater.
- (9) When grease interceptors are located in areas of pedestrian or vehicle travel, the design of the interceptor shall be adequate to support the imposed load. Structural calculations to verify its adequacy may be required.
- (10) A sample box shall be provided on the outlet side of each grease interceptor down stream of the required cleanout and vent.

1009.6 Water Test. A water test shall be applied to the level of the top of the interceptor inlet opening through the outlet opening or discharge side of the sample box. Interceptors shall show no leakage from section seams, pinholes or other imperfections. Any leakage below this level is cause for rejection.

- (1) **Backfill.** Interceptors shall not be backfilled until the inspection has been made to verify there are no leaks.

1010.0 Sand/Oil Interceptors.

1010.1 Where Required. An interceptor shall be provided for the proper handling of liquid wastes containing oil (of petroleum origin), sand, inert solids or any other similar substances.

NOTE: A sand/oil interceptor is not intended for the disposal of hazardous waste or as a backup system for accidental spills.

Interceptors as described in these standards shall be installed in, but not limited to, the following locations: car washes, motor vehicle, boat or airplane storage yards, gasoline and diesel service stations, repair garages or any other similar facility which may introduce sand and oil into the sewer system.

Submittal of a written application describing the exact facility operation and the types and anticipated volumes of waste to be generated may be required by the building official.

1010.2 Fixtures. The waste discharge from fixtures and equipment which may contain sand, oil-based wastes and inert solids shall drain only through an interceptor. This requirement includes, but is not limited to, the following: floor drains, floor sinks, special processing equipment, trench drains, and area drains.

1010.3 Prohibited Fixtures. The waste line from toilets, urinals, lavatories and other similar fixtures, which discharge domestic wastes only, shall not drain through the interceptor.

1010.4 Location.

- (1) Sand/ oil interceptors shall be so installed and connected that they shall be at all times accessible for inspection, cleaning and removal of the intercepted waste.
- (2) Sand / oil interceptors shall be placed as close as practical to the fixtures served.
- (3) Sand/ oil interceptors shall be located on the exterior of buildings unless specifically approved otherwise in writing by the sanitation authority.
- (4) Sand/ oil interceptors shall be located as to be accessible for service without the use of ladders or the removal of bulky equipment.
- (5) Location of all sand/oil interceptors shall be shown on the approved plans.
- (6) Each sand/ oil interceptor shall serve only one business establishment. Multiple business connections to a single sand/ oil interceptor are not permitted unless approved by the sanitation authority in writing.

1010.5 Size and Design.

- (1) All sand/oil interceptors shall be a minimum of three hundred (300) gallons (40 cubic feet) (1136 l) of total liquid capacity with a minimum floating liquid capacity of 55 gallons (208 l).
- (2) All sand/oil interceptors shall have a minimum of two compartments with a minimum of 3 inch (76.2 mm) diameter fittings designed for retention. The fittings shall be installed in the following manner: a 90° long sweep shall be installed at the interceptor inlet, a sanitary tee shall be installed on the inlet side of the interceptor baffle, and a sanitary tee installed at the outlet.
- (3) There shall be adequate access for cleaning all areas of the separator. A minimum of one (1) access point into each compartment within the separator shall be provided. In addition, no access points shall be further apart than ten (10) feet (3048 mm) regardless of number of compartments. Access covers shall have a minimum opening dimension of twenty (20) inches (508 mm) in diameter. Separator covers shall be of gas-tight construction.
- (4) The sand/oil interceptor shall be properly vented and designed to prevent it from becoming air bound in accordance with this code.

- (5) Each business establishment for which a sand/oil interceptor is required shall be provided with an interceptor which shall serve that establishment only and no others. Separate owners or lessees within a large business or establishment shall require separate interceptors.
- (6) Each sand/oil interceptor shall have a water seal of not less than six (6) inches (152 mm).
- (7) When separators are located in areas of foot or vehicle traffic, the design of the separator shall be adequate for the imposed load. Structural calculations performed by a Nevada Registered Engineer to verify adequacy may be required.
- (8) Any private or public wash rack or slab used for cleaning machinery or machine parts, shall drain to a sand/oil separator, and shall be adequately protected against storm or surface water intrusion.
- (9) Design standards other than those listed above may be acceptable. Redwood baffles shall not be used for new or existing interceptors. Any alternate design shall be prepared by a Nevada Registered Engineer and submitted for review and approval by the sanitation authority and the building official.
- (10) Cleanouts shall be installed in the drainage piping inlet and outlet side of each sand/oil interceptor and the outlet side of each sample box.
- (11) A sample box shall be provided on the outlet side of the interceptor down stream of the required cleanout and vent.

1010.6 Water Test. A water test shall be applied to the level of the top of the interceptor inlet opening through the outlet opening or discharge side of the sample box. Interceptors shall show no leakage from section seams, pinholes or other imperfections. Any leakage below this level is cause for rejection.

- (1) **Backfill.** Interceptors shall not be backfilled until the inspection has been made to verify there are no leaks.

1011.0 Maintenance of interceptors.

1011.1 Grease and sand/oil interceptors shall be maintained in efficient operating condition by periodic removal of the accumulated grease or sand/oil. No such collected grease, sand/oil, or any material collected from the interceptor shall be introduced into any drainage piping, public or private sewers. The materials removed from interceptors shall be handled and disposed of in a proper manner in accordance with published health district and sanitation authority requirements. Illegal dumping of waste into the sewer shall not be allowed.

1011.2 Maintenance records for each installed interceptor shall be maintained on the premises at all times and presented to a duly authorized agent of the sanitation authority upon request.

1011.3 The Authority Having Jurisdiction shall have the authority to mandate the installation of additional equipment or devices and enforce a maintenance program.

1012.0 Abandoned interceptors. Abandoned interceptors shall be cleaned and filled as required by Section 722.0 of the Plumbing Code for abandoned sewers and sewage disposal facilities.

1013.0 Existing Buildings. Whenever an existing building has a change in use which requires an interceptor or whenever there is an increase in the total number of drainage fixture units served by an existing interceptor, one or more interceptors shall be installed in the drainage system serving the building meeting the requirements of Section 1009 and 1010.

Section 1101.3 Material Uses.

Revise Section 1101.3 by adding a new Section 1101.3.1, as follows:

1101.3.1 Plastic piping used for rainwater systems shall be limited to buildings defined as combustible construction by this code.

Section 1101.5.1 Subsoil Drains.

Revise Section 1101.5.1, as follows:

1101.5.1 Where required by the geotechnical engineer or the authority having jurisdiction, subsoil drains shall be provided around the perimeter of buildings having basements, cellars, or crawl spaces or floors below grade. Such subsoil drains may be positioned inside or outside of the footing, shall be of perforated, or open-jointed approved drain tile or pipe not less than three (3) inches (80 mm) in diameter, and shall be laid in gravel, slag, crushed rock, approved three-quarter (3/4) inch (19.1 mm) crushed recycled glass aggregate, or other approved porous material with a minimum of four (4) inches (102 mm) surrounding the pipe on all sides. Filter media shall be provided for exterior subsoil piping.

Delete Section 1101.9, Filling Stations and Motor Vehicle Washing Establishments, in its entirety.

Delete Section 1101.10, Paved Areas, in its entirety.

Delete Section 1103.0, Traps on Storm drains and Leaders, in its entirety.

Delete Section 1104.3, Combining Storm with Sanitary Drainage, in its entirety.

Section 1203.3 Fuel gas.

Revise Section 1203.3 by adding a new Section 1203.3.1, as follows:

1203.3.1 Dry Gas – A gas having a moisture and hydrocarbon dew point below any normal temperature to which the gas piping is exposed. Southern Nevada shall be considered a dry gas condition area unless specified by the local gas purveyor.

Section 1211.1.6 Piping Underground Beneath Buildings.

Delete Section 1211.1.6 in its entirety and replace, as follows:

1211.1.6 Piping Underground Beneath Buildings. No gas piping shall be installed in or on the ground under any building or structure unless installed in gastight conduit, and all exposed gas piping shall be kept at least six (6) inches (152 mm) above grade or structure. The term "building or structure" shall include structures such as porches and steps, whether covered or uncovered, breezeways, roofed porte-cocheres, roofed patios, carports, covered walks, covered driveways, and similar structures or appurtenances. All gas piping under a slab shall be capable of being removed and replaced.

The conduit shall be of material approved for installation underground beneath buildings and not less than Schedule 40 pipe. The interior diameter of the conduit shall be not less than one-half (1/2) inch (15 mm) larger than the outside diameter of the gas piping.

The conduit shall extend to a point at least (12) inches (305 mm) beyond any area where it is required to be installed or to the outside wall of a building, and the outer ends shall not be sealed. Where the conduit terminates within a building, it shall be readily accessible and the space between the conduit and the gas piping shall be sealed to prevent leakage of gas into the building.

Exception: Products listed for such use.

Section 1211.3.2 Connections.

Revise item (4) in Section 1211.3.2, as follows:

1211.3.2 Connections. Where gas piping is to be concealed, unions, tubing fittings, bushings, and compression couplings made by combinations of fittings shall not be used. Connections shall be of the following types:

- (1) Pipe fittings such as elbows, tees, and couplings.
- (2) Joining tubing by brazing (see Section 1209.5.8.2).
- (3) Fittings listed for use in concealed spaces that have been demonstrated to sustain, without leakage, any forces due to temperature expansion or contraction, vibration, or fatigue based on their geographic location, application or operation.
- (4) Where necessary to insert fittings in gas pipe that has been installed in a concealed location, the pipe shall be reconnected by welding, flanges, or with right and left couplings.

Section 1214.3 Test Pressure.

Delete Section 1214.3.1 in its entirety and replace, as follows:

1214.3.1 This inspection shall be made after all piping authorized by the permit has been installed and after all portions thereof which are to be covered or concealed are so concealed and before any fixtures, appliance, or shutoff valve has been attached thereto. This inspection shall include an air, CO₂ or nitrogen pressure test, at which time the gas piping shall stand a pressure of not less than ten (10) pounds per square inch (68.9 kPa) gauge pressure, or at the discretion of the Administrative Authority, the piping and valves may be tested at a pressure of at least six (6) inches (152 mm) of mercury, measured with a manometer or slope gauge. Test pressures shall be held for a length of time satisfactory to the Administrative Authority, but in no case for less than fifteen (15) minutes, with no perceptible drop in pressure. For welded piping, and for piping carrying gas at pressures in excess of fourteen (14) inches (356 mm) water column pressure, the test pressure shall not be less than sixty (60) pounds per square inch (413.4 kPa) and shall be continued for a length of time satisfactory to the Administrative Authority, but in no case for less than thirty (30) minutes. These tests shall be made using air, CO₂, or nitrogen pressure only and shall be made in the presence of the Administrative Authority. All necessary apparatus for conducting tests shall be furnished by the permit holder. Test gauges used in conducting tests shall comply with Section 319.0, Test Gauges.

Delete Chapter 13, Health Care Facilities and Medical Gas and Vacuum Systems, in its entirety.

Delete Chapter 15, Firestop Protection, in its entirety.

Delete Chapter 16, Part 1 - Gray Water Systems, Sections 1601 through 1612 in their entirety.

Section 1613.0 Reclaimed Water Systems - General.

Revise Section 1613.0 (A), as follows:

1613.0 Reclaimed Water Systems - General.

(A) The provisions of Part II of this chapter shall not be allowed in residential buildings and shall apply to the installation, construction, alteration, and repair of reclaimed water systems intended to supply uses such as water closets urinals, trap primers for floor drains, floor sinks, irrigation, industrial processes, water features and other uses approved by the Authority Having Jurisdiction. Potable water supplied as makeup water in these systems shall be protected against back-pressure and back-syphonage in accordance with Sections 602.0 and 603.0.

Delete Appendix F, Firefighter Breathing Air Replenishment Systems, in its entirety.

Delete Appendix K, Private Sewage Disposal Systems, in its entirety.

**BUSINESS IMPACT STATEMENT
BILL NO. 2011-12**

(Adopts the 2009 Edition of the Uniform Plumbing Code, together with amendments thereto, as the City's Plumbing Code)

This business impact statement was prepared pursuant to NRS 237.090 to address the impact of a proposed ordinance, Bill No. 2011-12, that will adopt the 2009 Edition of the Uniform Plumbing Code, together with amendments thereto, as the City's Plumbing Code.

1. The following constitutes a description of the manner in which comment was solicited from affected businesses, a summary of their responses and an explanation of the manner in which other interested persons may obtain a copy of the summary.

Notice of the proposed ordinance was published in the Las Vegas Review-Journal. In addition, a copy of the notice was provided to development-related and construction groups that are representative of affected industries. No written responses were received.

2. The estimated economic effect of the proposed rule on businesses, including, without limitation, both adverse and beneficial effects, and both direct and indirect effects:

Adverse effects:

Those proposing construction will need to plan for and adjust to any new or differing Code requirements

Beneficial effects:

Code provisions that are updated and that are consistent with other area jurisdictions

Direct effects:

See adverse and beneficial effects above

Indirect effects:

None identified

3. The following constitutes a description of the methods the local government considered to reduce the impact of the proposed rule on businesses and a statement regarding whether any, and if so which, of these methods were used:

Not applicable

4. The governing body estimates the annual cost to the local government for enforcement of the proposed rule is:

No additional cost

5. If the proposed rule provides for a new fee or increases an existing fee, the total annual amount expected to be collected is:

Not applicable

6. If the proposed rule provides for a new fee or increases an existing fee, the money generated by the new fee or increase in existing fee will be used by the local government to:

Not applicable

7. If the proposed rule includes provisions that duplicate or are more stringent than federal, state or local standards regulating the same activity, the following explains when such duplicative or more stringent provisions are necessary:

Not applicable

Date: February 16, 2011

AFFP DISTRICT COURT
Clark County, Nevada

AFFIDAVIT OF PUBLICATION

STATE OF NEVADA)
COUNTY OF CLARK) SS:

Stacey M. Lewis, being 1st duly sworn, deposes and says: That she is the Legal Clerk for the Las Vegas Review-Journal and the Las Vegas Sun, daily newspapers regularly issued, published and circulated in the City of Las Vegas, County of Clark, State of Nevada, and that the advertisement, a true copy attached for,

LV CITY CLERK 2296311LV 7069075

was continuously published in said Las Vegas Review-Journal and / or Las Vegas Sun in 1 edition(s) of said newspaper issued from 03/24/2011 to 03/24/2011, on the following days:


03/24/2011

BILL NO. 2011-12
AN ORDINANCE TO ADOPT THE 2009 EDITION OF THE UNIFORM PLUMBING CODE, TOGETHER WITH AMENDMENTS THERETO, AND TO PROVIDE FOR OTHER RELATED MATTERS.
Sponsored by: Councilman Steven D. Ross
Summary: Adopts the 2009 Edition of the Uniform Plumbing Code, together with amendments thereto, as the City's Plumbing Code.
At the City Council meeting of MARCH 2, 2011
BILL NO. 2011-12 WAS READ BY TITLE AND REFERRED TO A RECOMMENDING COMMITTEE
COPIES OF THE COMPLETE ORDINANCE ARE AVAILABLE FOR PUBLIC INFORMATION IN THE OFFICE OF THE CITY CLERK, 1ST FLOOR, 400 STEWART AVENUE, LAS VEGAS, NEVADA
PUB: March 24, 2011
LV Review-Journal

Signed: Stacey M. Lewis

SUBSCRIBED AND SWORN BEFORE ME THIS, THE
24th day of March, 2011.

Emily Gonzalez
Notary Public



AFFP DISTRICT COURT
Clark County, Nevada

AFFIDAVIT OF PUBLICATION

STATE OF NEVADA)
COUNTY OF CLARK) SS:

Stacey M. Lewis, being 1st duly sworn, deposes and says: That she is the Legal Clerk for the Las Vegas Review-Journal and the Las Vegas Sun, daily newspapers regularly issued, published and circulated in the City of Las Vegas, County of Clark, State of Nevada, and that the advertisement, a true copy attached for,

LV CITY CLERK 2296311LV 7108457

was continuously published in said Las Vegas Review-Journal and / or Las Vegas Sun in 1 edition(s) of said newspaper issued from 04/09/2011 to 04/09/2011, on the following days:

04/09/2011

Bill No. 2011-12
ORDINANCE NO. 6141

AN ORDINANCE TO ADOPT THE 2009 EDITION OF THE UNIFORM PLUMBING CODE, TOGETHER WITH AMENDMENTS THERETO, AND TO PROVIDE FOR OTHER RELATED MATTERS.

Sponsored by: Councilman Steven D. Ross

Summary: Adopts the 2009 Edition of the Uniform Plumbing Code, together with amendments thereto, as the City's Plumbing Code.

The above and foregoing ordinance was first proposed and read by title to the City Council on the 2nd day of March 2011 and referred to a committee for recommendation; thereafter the committee reported favorably on said ordinance on the 6th day of April 2011, which was a regular meeting of said City Council; and that at said regular meeting the proposed ordinance was read by title to the City Council as introduced and was adopted by the following vote:

VOTING "AYE": Mayor Goodman and Councilmembers Reese, Tarkanian, Ross, Barlow and Anthony
VOTING "NAY": NONE
EXCUSED: NONE
NOT VOTING: Councilman Wolfson

COPIES OF THE COMPLETE ORDINANCE ARE AVAILABLE FOR PUBLIC INFORMATION IN THE OFFICE OF THE CITY CLERK, 1ST FLOOR, 400 STEWART AVENUE, LAS VEGAS, NEVADA

PUB: April 9, 2011
LV Review-Journal

Signed Stacey M. Lewis

SUBSCRIBED AND SWORN BEFORE ME THIS, THE 11th day of April, 2011.

Emily Gonzalez
Notary Public

