

1 **BILL NO. 2018-32**

2 **ORDINANCE NO. 6637**

3 AN ORDINANCE TO ADOPT THE 2018 EDITION OF THE UNIFORM MECHANICAL CODE,
4 TOGETHER WITH AMENDMENTS THERETO, AND TO PROVIDE FOR OTHER RELATED
MATTERS.

5 Proposed by: Scott D. Adams, City Manager

Summary: Adopts the 2018 Edition of the
Uniform Mechanical Code, together with
amendments thereto.

7 THE CITY COUNCIL OF THE CITY OF LAS VEGAS DOES HEREBY ORDAIN AS
8 FOLLOWS:

9 SECTION 1: Title 16, Chapter 24, Section 10, of the Municipal Code of the City of Las
10 Vegas, Nevada, 1983 Edition, is hereby amended to read as follows:

11 **16.24.010:** Those certain documents, copies of each being on file in the office of the City Clerk, and
12 designated as follows, are adopted by reference and made a part of this Code, to the same effect as if set out
13 herein in full:

14 (A) Uniform Mechanical Code, [2012] 2018 Edition, designated as Part 1 of this
15 Chapter; and

16 (B) A document entitled [the] "Southern Nevada Amendments to the [2012] 2018
17 Uniform Mechanical Code," adding to, deleting from and amending the Uniform Mechanical Code, [2012]
18 2018 Edition, designated as Part 2 of this Chapter.

19 SECTION 2: The document entitled "Southern Nevada Amendments to the 2018 Uniform
20 Mechanical Code" is attached to this Ordinance.

21 SECTION 3: Ordinance No. 6354, the "Uniform Mechanical Code, 2012 Edition," and
22 the "Southern Nevada Amendments to the 2012 Uniform Mechanical Code" are hereby repealed in their
23 entirety.

24 SECTION 4: This Ordinance shall be effective as of February 4, 2019.

25 SECTION 5: If any section, subsection, subdivision, paragraph, sentence, clause or phrase
26 in this ordinance or any part thereof is for any reason held to be unconstitutional or invalid or ineffective by

1 any court of competent jurisdiction, such decision shall not affect the validity or effectiveness of the
2 remaining portions of this ordinance or any part thereof. The City Council of the City of Las Vegas hereby
3 declares that it would have passed each section, subsection, subdivision, paragraph, sentence, clause or phrase
4 thereof irrespective of the fact that any one or more sections, subsections, subdivisions, paragraphs,
5 sentences, clauses or phrases be declared unconstitutional, invalid or ineffective.


6 SECTION 6: Whenever in this ordinance any act is prohibited or is made or declared to
7 be unlawful or an offense or a misdemeanor, or whenever in this ordinance the doing of any act is required
8 or the failure to do any act is made or declared to be unlawful or an offense or a misdemeanor, the doing of
9 such prohibited act or the failure to do any such required act shall constitute a misdemeanor and upon
10 conviction thereof, shall be punished by a fine of not more than \$1,000.00 or by imprisonment for a term of
11 not more than six months, or by any combination of such fine and imprisonment. Any day of any violation
12 of this ordinance shall constitute a separate offense.

13 SECTION 7: All ordinances or parts of ordinances or sections, subsections, phrases,
14 sentences, clauses or paragraphs contained in the Municipal Code of the City of Las Vegas, Nevada, 1983
15 Edition, in conflict herewith are hereby repealed.

16 PASSED, ADOPTED and APPROVED this 15th day of August, 2018.

17 APPROVED:


18 By


CAROLYN G. GOODMAN, Mayor

19
20 ATTEST:

21 
22 LUANN D. HOLMES, MMC
City Clerk

23 APPROVED AS TO FORM:

24  7-9-18
25 Val Steed, Date
Deputy City Attorney

1 The above and foregoing ordinance was first proposed and read by title to the City Council
2 on the 18th day of July, 2018, and referred to a committee for recommendation; hereafter
3 the committee reported favorably on said ordinance on the 15th day of August, 2018,
4 which as a regular meeting of said Council; that at said regular meeting, the proposed
5 ordinance was read by title to the City Council as first introduced and adopted by the
6 following vote:

7 VOTING "AYE": Mayor Goodman and Councilmembers, Tarkanian, Anthony, Coffin
8 Fiore, Seroka and Crear

9 VOTING "NAY": None

10 EXCUSED: None

11 ABSTAINED: None

12
13
14 APPROVED:

15 
16 CAROLYN G. GOODMAN, Mayor

17 ATTEST:

18 
19 LUANN D. HOLMES, MMC City Clerk



**SOUTHERN NEVADA
AMENDMENTS
TO THE
2018 UNIFORM MECHANICAL CODE**

PREFACE

This document was developed by the Southern Nevada Building Officials' Uniform Mechanical Code (UMC) Committee and presents recommended amendments to the 2018 Uniform Mechanical Code as published by the International Association of Plumbing and Mechanical Officials (IAPMO)

Participation in the 2018 UMC Committee was open to all interested parties. However, voting on amendment proposals was limited to one vote each for six of Southern Nevada municipalities (Clark County, Henderson, Las Vegas, North Las Vegas, Boulder City, and Mesquite), the Clark County School District, and three industry representatives. All committee proceedings were conducted in accordance with Robert's Rules of Order.

The recommended amendments contained herein are not code unless adopted and codified by governmental jurisdictions. These amendments are not intended to prevent the use of any material or method of construction not specifically prescribed herein, provided any alternates have been approved and their use authorized by the Building Official. This document may be copied and used in whole or in part without permission or approval from the organizations listed on the cover page.

Table of Contents

Chapter1: Administration.....	4
Section 203 Definitions	
Section 304.3.1.2 Permanent Ladders	
Section 304.4 Appliances in Attics and Under-Floor Spaces	
Section 504.4 Clothes Dryers.....	5
Section 504.4.2.1 – Length Limitation	
Section 510.1.6.1 Bracing and Supports	
Section 511.2.2.1.1 Performance Test	
Section 603.4.1 Length Limitation.....	6
Section 603.13 Air Dispersion Systems	
Section 608.1 Automatic Shutoffs	
Section 802.6.1 Termination Requirements	
Section Chapter 10, Boilers and Pressure Vessels.....	7
Section 1301.2 Dry Gas	
Section 1310.1.6 Piping Underground Beneath Buildings	
Section 1701.1 Standards.....	8

Section Chapter 1: Administration

Delete Chapter 1 in its entirety, except for sections 101.1, 101.2 and 101.3.

Section 203.0

Revise Air Dispersion Systems definition as follows

Air Dispersion Systems: Any diffuser system designed to both convey air within a room, space or area and diffuse air into that space while operating under positive pressure. Systems are commonly constructed of, but not limited to, fabric or plastic film.

Section 304.3.1.2 Permanent Ladders

Revise section 304.3 1 2 to read as follows.

304.3.1.2 Permanent Ladders. Permanent ladders required by Section 304 3.1.1 or exterior ladders shall be constructed in accordance with the following:

- (1) Side railings shall extend not less than 30 inches (762 mm) above the roof or parapet wall.
- (2) Landings shall not exceed 18 feet (5486 mm) apart measured from the finished grade.
- (3) Width shall be not less than 14 inches (356 mm) on center.
- (4) Rungs spacing shall not exceed 12 inches (305 mm) on center, and each rung shall be capable of supporting a 300 pound (136 kg) load.
- (5) Toe space shall be not less than 6 inches (152 mm).

Exceptions:

- 1 Permanent ladders providing roof access need not extend closer than eight (8) feet (2438 mm) to the finish grade.
- 2 A portable ladder may be used for access for a Group R Division 3 and 4 and U occupancies.
- 3 Permanent ladders for equipment access need not be provided at parapets or walls less than thirty (30) inches (762mm) in height.

Section 304.4 Appliances in Attics and Under-Floor Spaces

Revise Section 304 4 as follows:

304.4 Appliances in Attics and Under-Floor Spaces. An attic or under-floor space in which an appliance is installed shall be accessible through an opening and passage-way not less than the largest component of the appliance, and the rough-framed opening shall not be less than 22 inches by 30 inches (559 mm by 762mm).

Section 504.4 Clothes Dryers

Revise Section 504 4 by adding a new exception, as follows:

Exception: When moisture exhaust ducts terminate vertically through a roof, backdraft dampers are not required.

Section 504.4.2.1 – Length Limitation

Revise Section 504.4 2 1 a new exception, as follows

504.4.2.1 Length Limitation. Unless otherwise permitted or required by the dryer manufacturer's instructions and approved by the Authority Having Jurisdiction, domestic dryer moisture exhaust ducts shall not exceed a total combined horizontal and vertical length of 14 feet (4267 mm), including two 90 degree (1 57 rad) elbows. A length of 2 feet (610 mm) shall be deducted for each 90 degree (1 57 rad) elbow in excess of two

Exceptions:

- (1) Where an exhaust duct power ventilator, in accordance with Section 504 2 3, is used, the permitted length of the dryer exhaust duct shall be permitted to be in accordance with the dryer exhaust duct power ventilator manufacturer's installation instructions
- (2) Lengths may be increased when justified by calculations prepared by a Nevada Licensed Mechanical Engineer

Section 510.1.6.1 Bracing and Supports

Add a new Section 510 1 6 1, as follows:

510.1.6.1 Bracing and Supports. Unless specifically listed, the structural supports for a duct enclosure shall be outside the enclosure

Section 511.2.2.1.1 Performance Test

Add a new Section 511.2 2.1.1 as follows:

511.2.2.1.1 Performance Test. The permit holder shall provide the jurisdiction with an accurate, completed, and signed test report. The report shall be on a form supplied by the jurisdiction or on a form containing equivalent information. At the discretion of the building official, the performance test may be required to be witnessed by the Authority Having Jurisdiction, performed by an approved third party testing agency

Section 603.4.1 Length Limitation

Delete section 603 4.1

Section 603.13 Air Dispersion Systems

Revise section 603 13, as follows.

603.13 Air Dispersion Systems Where installed, air dispersion systems shall be completely installed in exposed locations operate under positive pressure, and not pass through or penetrate fire-resistant-rated construction Air dispersion systems shall be listed and labeled in accordance with UL 2518

Section 608.1 Automatic Shutoffs

Revise Section 608.1 by adding a new paragraph following the exceptions, as follows

Upon completion and before final approval of the air-moving system provided with the required smoke detectors, a performance test shall be performed to verify compliance of detector installation to manufacturer's instructions and system compatibility as specified in this chapter The permit holder shall furnish the necessary test equipment and devices required to perform the tests and shall provide the jurisdiction with an accurate, completed, and signed test report The report shall be on a form supplied by the jurisdiction or on a form containing equivalent information At the discretion of the building official, the performance test may be required to be witnessed by the Authority Having Jurisdiction, performed by an approved third party testing agency.

Section 802.6.1 Termination Requirements

Add an exception to 802.6.1 (1) to read as follows:

802.6.1 Termination Requirements. A gas vent shall terminate in accordance with one of the following:

- (1) Gas vents that are 12 inches (300 mm) or less in size and located not less than 8 feet (2438 mm) from a vertical wall or similar obstruction shall terminate above the roof in accordance with Figure 802.6 1 and Table 802 6 1

Exception: A single-family residence having gas vents twelve (12) inches (300 mm) in size or smaller with listed caps shall be permitted to be terminated in accordance with Figure 802 6 1, provided they are at least four (4) feet (1.2 m) from a vertical wall or similar obstruction

Items (2) through (7) remain unchanged

Section Chapter 10, Boilers and Pressure Vessels

Delete Chapter 10 in its entirety except Section 1001.1 and revise Section 1001 1, as follows

1001.1 Applicability. For boilers and water heaters less than 120 gallon capacity, or a BTU input rating less than 200,000, or less than 160 pounds per square inch of pressure, see Chapter 5 of the Uniform Plumbing Code For all other units, contact the Mechanical Section of the Nevada Division of Occupational Safety and Health, part of the Office of Business and Industrial Relations

Exceptions (1) through (8) remain unchanged

Section 1301.2 Dry Gas

Add a new section 1301 2, as follows

1301.2 Dry Gas. Southern Nevada shall be considered a dry gas condition having a moisture and hydrocarbon dew point below any normal temperature to which the gas piping is in an exposed area, unless specified by the local gas purveyor

Section 1310.1.6 Piping Underground Beneath Buildings

1310.1.6 Piping Underground Beneath Buildings. No gas piping shall be installed in or on the ground under any building or structure unless installed in gastight conduit, and all exposed gas piping shall be kept at least six (6) inches (152 mm) above grade or structure The term "building or structure" shall include structures such as porches and steps, whether covered or uncovered, breezeways, roofed porte-cocheres, roofed patios, carports, covered walks, covered driveways, and similar structures or appurtenances All gas piping under a slab shall be capable of being removed and replaced

The conduit shall be of material approved for installation underground beneath buildings and not less than Schedule 40 pipe The interior diameter of the conduit shall be not less than one-half (1/2) inch (15 mm) larger than the outside diameter of the gas piping

The conduit shall extend to a point at least (12) inches (305 mm) beyond any area where it is required to be installed or to the outside wall of a building, and the outer ends shall not be sealed. Where the conduit terminates within a building, it shall be readily accessible and the space between the conduit and the gas piping shall be sealed to prevent leakage of gas into the building

Exception: Products listed for such use

Section 1701.1 Standards

Add the following referenced standard to Table 1701.1:

STANDARD NUMBER
UL 2518-2016

STANDARD TITLE
Standard for Air Dispersion Systems

APPLICATION
Air Dispersion Systems

REFERENCED SECTION
603.13

AFFIDAVIT OF PUBLICATION

STATE OF NEVADA)
COUNTY OF CLARK) SS

RECEIVED
CITY CLERK

LV CITY CLERK
495 S MAIN ST
LAS VEGAS NV 89101

Account # 22515
Ad Number 0000995912

2019 JUL 24 P 12:08


Leslie McCormick, being 1st duly sworn, deposes and says: That she is the Legal Clerk for the Las Vegas Review-Journal and the Las Vegas Sun, daily newspapers regularly issued, published and circulated in the City of Las Vegas, County of Clark, State of Nevada, and that the advertisement, a true copy attached for, was continuously published in said Las Vegas Review-Journal and / or Las Vegas Sun in 1 edition(s) of said newspaper issued from 07/19/2018 to 07/19/2018, on the following days:


07 / 19 / 18

BILL NO. 2018-32
AN ORDINANCE TO ADOPT THE
2018 EDITION OF THE UNIFORM
MECHANICAL CODE, TOGETHER
WITH AMENDMENTS THERETO,
AND TO PROVIDE FOR OTHER
RELATED MATTERS.
Proposed by: Scott D. Adams,
City Manager
Summary: Adopts the 2018
Edition of the Uniform
Mechanical Code, together with
amendments thereto.
At the City Council meeting of
July 18, 2018
BILL NO. 2018-32 WAS READ BY
TITLE AND REFERRED TO A
RECOMMENDING COMMITTEE
COPIES OF THE COMPLETE
ORDINANCE ARE AVAILABLE FOR
PUBLIC INFORMATION IN THE
OFFICE OF THE CITY CLERK, 2ND
FLOOR, 495 SOUTH MAIN
STREET, LAS VEGAS, NEVADA
PUB: July 19, 2018
LV Review-Journal

IS/ 
LEGAL ADVERTISEMENT REPRESENTATIVE

Subscribed and sworn to before me on this 19th day of July, 2018

Notary 



AFFIDAVIT OF PUBLICATION

STATE OF NEVADA)
COUNTY OF CLARK) SS

**LV CITY CLERK
495 S MAIN ST
LAS VEGAS NV 89101**

**Account # 22515
Ad Number 0001001644**

**RECEIVED
CITY CLERK**

2018 AUG 23 A 11:55

Leslie McCormick, being 1st duly sworn, deposes and says: That she is the Legal Clerk for the Las Vegas Review-Journal and the Las Vegas Sun, daily newspapers regularly issued, published and circulated in the City of Las Vegas, County of Clark, State of Nevada, and that the advertisement, a true copy attached for, was continuously published in said Las Vegas Review-Journal and / or Las Vegas Sun in 1 edition(s) of said newspaper issued from 08/18/2018 to 08/18/2018, on the following days

08 / 18 / 18

**BILL NO. 2018-32
ORDINANCE NO. 6637**

AN ORDINANCE TO ADOPT THE 2018 EDITION OF THE UNIFORM MECHANICAL CODE, TOGETHER WITH AMENDMENTS THERETO, AND TO PROVIDE FOR OTHER RELATED MATTERS.

Proposed by:
Scott D. Adams, City Manager

Summary: Adopts the 2018 Edition of the Uniform Mechanical Code, together with amendments thereto.

The above and foregoing ordinance was first proposed and read by title to the City Council on the 18th day of July, 2018, and referred to a committee for recommendation; thereafter the committee reported favorably on said ordinance on the 15th day of August, 2018, which was a regular meeting of said City Council; and that at said regular meeting the proposed ordinance was read by title to the City Council as first introduced and adopted by the following vote:

VOTING "AYE": Mayor Goodman and Councilmembers Tarkanian, Anthony, Coffin, Seroka, Fiore and Crear
VOTING "NAY": NONE
EXCUSED: NONE

COPIES OF THE COMPLETE ORDINANCE ARE AVAILABLE FOR PUBLIC INFORMATION IN THE OFFICE OF THE CITY CLERK, 2ND FLOOR, 495 SOUTH MAIN STREET, LAS VEGAS, NEVADA

PUB: August 18, 2018
LV Review-Journal

/s/

LEGAL ADVERTISEMENT REPRESENTATIVE

Subscribed and sworn to before me on this 20th day of August, 2018

Notary

